

**decsystem10**

**FORTRAN  
PROGRAMMER'S  
REFERENCE MANUAL**

**digital**



January 1977

This document describes the language elements of the FORTRAN-10 compiler for the DECsystem-10.



# FORTRAN PROGRAMMER'S REFERENCE MANUAL

Order No. AA-0944E-TB

**SUPERSESSION/UPDATE INFORMATION:**

This document supersedes the document of the same name, Order No. DEC-10-LFORA-D-D, published June 1975.

**OPERATING SYSTEM AND VERSION:**

Any Digital-supported operating system for the DECsystem-10.

**SOFTWARE VERSION:**

FORTRAN-10, Version 5

To order additional copies of this document, contact the Software Distribution Center, Digital Equipment Corporation, Maynard, Massachusetts 01754.

**digital equipment corporation • maynard, massachusetts**

First Printing,	June 1973
Revised:	January 1974
	October 1974
	May 1975
	June 1975
	November 1975
	January 1977

The information in this document is subject to change without notice and should not be construed as a commitment by Digital Equipment Corporation. Digital Equipment Corporation assumes no responsibility for any errors that may appear in this document.

The software described in this document is furnished under a license and may be used or copied only in accordance with the terms of such license.

Digital Equipment Corporation assumes no responsibility for the use or reliability of its software on equipment that is not supplied by DIGITAL.

Copyright © 1973, 1974, 1975, 1977 by Digital Equipment Corporation

The postage prepaid READER'S COMMENTS form on the last page of this document requests the user's critical evaluation to assist us in preparing future documentation.

The following are trademarks of Digital Equipment Corporation:

DIGITAL	DECsystem-10	MASSBUS
DEC	DECtape	OMNIBUS
PDP	DIBOL	OS/8
DECUS	EDUSYSTEM	PHA
UNIBUS	FLIP CHIP	RSTS
COMPUTER LABS	FOCAL	RSX
COMTEX	INDAC	TYPESET-8
DDT	LAB-8	TYPESET-10
DECCOMM	DECsystem-20	TYPESET-11

## PREFACE

This manual has two parts: PART I, Introduction to Using FORTRAN-10 with SOS, and PART II, FORTRAN-10 Language Manual.

Part I is a short guide to using the DECsystem-10 Operating System. It describes the minimum set of commands necessary to input, edit, and execute FORTRAN programs. It assumes that the reader has a rudimentary knowledge of or is presently learning FORTRAN programming. It is a guide to implementing FORTRAN on the DECsystem-10.

The complete set of Operating System commands is given in the DECsystem-10 Operating Systems Commands Manual (DEC-10-OSCMA-A-D). The SOS text editor is described completely in the SOS User's Guide (DEC-10-USOSA-A-D).

Part II describes the FORTRAN language as implemented for the FORTRAN-10 Language Processing System (referred to as FORTRAN-10). The language manual (PART II) is intended for reference purposes only. The reader is expected to have some experience in writing FORTRAN programs and to be familiar with the standard FORTRAN language set and terminology as defined in the American National Standard FORTRAN, X3.9-1966. Descriptions of FORTRAN-10 extensions and additions to the standard FORTRAN language set are printed with gray shading.

Operating procedures and descriptions of the DECsystem-10 programming environment are included in the appendixes.



## MASTER TABLE OF CONTENTS

		Page
<b>PART I      INTRODUCTION TO USING FORTRAN-10 WITH SOS</b>		
CHAPTER	1   LOGGING IN	INTRO 1-1
CHAPTER	2   TYPING IN YOUR PROGRAM	INTRO 2-1
CHAPTER	3   RUNNING YOUR PROGRAM	INTRO 3-1
CHAPTER	4   CHANGING YOUR PROGRAM	INTRO 4-1
CHAPTER	5   FORTRAN-10 INPUT AND OUTPUT OF DATA	INTRO 5-1
CHAPTER	6   SOME HELPFUL COMMANDS	INTRO 6-1
CHAPTER	7   SAYING GOODBYE TO THE COMPUTER	INTRO 7-1
CHAPTER	8   EXAMPLES	INTRO 8-1
 <b>PART II    FORTRAN-10 LANGUAGE MANUAL</b>		
CHAPTER	1   INTRODUCTION	1-1
CHAPTER	2   CHARACTERS AND LINES	2-1
CHAPTER	3   DATA TYPES, CONSTANTS, SYMBOLIC NAMES, VARIABLES, AND ARRAYS	3-1
CHAPTER	4   EXPRESSIONS	4-1
CHAPTER	5   COMPILE CONTROL STATEMENTS	5-1
CHAPTER	6   SPECIFICATION STATEMENTS	6-1
CHAPTER	7   DATA STATEMENT	7-1
CHAPTER	8   ASSIGNMENT STATEMENTS	8-1
CHAPTER	9   CONTROL STATEMENTS	9-1
CHAPTER	10 I/O STATEMENTS	10-1
CHAPTER	11 NAMELIST STATEMENTS	11-1
CHAPTER	12 FILE CONTROL STATEMENTS	12-1
CHAPTER	13 FORMAT STATEMENT	13-1
CHAPTER	14 DEVICE CONTROL STATEMENTS	14-1
CHAPTER	15 SUBPROGRAM STATEMENTS	15-1
CHAPTER	16 BLOCK DATA SUBPROGRAMS	16-1
APPENDIX	A   ASCII-1968 CHARACTER CODE SET	A-1
APPENDIX	B   USING THE COMPILER	B-1
APPENDIX	C   WRITING USER PROGRAMS	C-1
APPENDIX	D   FOROTS	D-1
APPENDIX	E   FORDDT	E-1
APPENDIX	F   COMPILER MESSAGES	F-1
APPENDIX	G   FORTRAN-10 REALTIME SOFTWARE	G-1
APPENDIX	H   FOROTS ERROR MESSAGES	H-1



PART I

Introduction to Using FORTRAN-10 with SOS



## CONTENTS

		Page
CHAPTER	1 LOGGING IN	INTRO 1-1
CHAPTER	2 TYPING IN YOUR PROGRAM TO STOP ENTERING LINES INTO YOUR PROGRAM ENDING OR STORING YOUR PROGRAM(E) THE RUBOUT OR DELETE KEY (CORRECTING TYPING MISTAKES)	INTRO 2-1 INTRO 2-2 INTRO 2-2 INTRO 2-3
CHAPTER	3 RUNNING YOUR PROGRAM THE EXECUTE COMMAND CTRL/C (^C) (GETTING THE MONITOR'S ATTENTION Stopping Your Program's Execution Deleting a Command CTRL/U (^U) (CHANGING A LINE)	INTRO 3-1 INTRO 3-1 INTRO 3-3 INTRO 3-3 INTRO 3-3 INTRO 3-4
CHAPTER	4 CHANGING YOUR PROGRAM THE R SOS COMMAND (CORRECTING MISTAKES IN YOUR PROGRAM) SOS COMMANDS I - Inserting Lines Into Your Program D - Deleting Lines From Your Program R - Replacing Lines In Your Program P - Printing Lines Of Your Program On The Terminal N - Changing The Line Numbers E - End (Ends Editing and Stores the Program) EQ - Returning To the Monitor Without Storing Your Program A FEW SOS CONVENTIONS TAB (CTRL/I) CORRECTING MISTAKES	INTRO 4-1 INTRO 4-1 INTRO 4-1 INTRO 4-3 INTRO 4-3 INTRO 4-4 INTRO 4-5 INTRO 4-5 INTRO 4-5 INTRO 4-5 INTRO 4-6 INTRO 4-6 INTRO 4-6 INTRO 4-6
CHAPTER	5 FORTRAN-10 INPUT AND OUTPUT OF DATA READ STATEMENT WRITE STATEMENT DEVICE UNIT NUMBERS ACCEPT STATEMENT TYPE STATEMENT DATA FILES Letting FORTRAN Use a Predefined Filename Using Your Own Filename	INTRO 5-1 INTRO 5-1 INTRO 5-1 INTRO 5-2 INTRO 5-2 INTRO 5-2 INTRO 5-3 INTRO 5-3 INTRO 5-3
CHAPTER	6 SOME HELPFUL COMMANDS TYPE COMMAND (PRINTING OUT YOUR PROGRAM) DIRECT COMMAND (LISTING ALL STORED PROGRAMS AND FILES) DELETE COMMAND (ERASING A PROGRAM OR FILE)	INTRO 6-1 INTRO 6-1 INTRO 6-1 INTRO 6-2

CONTENTS (CONT.)

	Page
RENAME COMMAND (GIVING A PROGRAM OR FILE A NEW NAME)	INTRO 6-2
CTRL/O (SUPPRESSNG PRINTED OUTPUT)	INTRO 6-2
GRIPIES	INTRO 6-2
CHAPTER 7 SAYING GOODBYE TO THE COMPUTER	INTRO 7-1
KJOB COMMAND (LOGGING OUT)	INTRO 7-1
K/F Command (Fast Logout)	INTRO 7-1
HELP Command (Getting Assistance)	INTRO 7-1
WHAT TO DO IF YOU ARE DISCONNECTED FROM YOUR JOB (ATTACH)	INTRO 7-3
FORGOT YOUR JOB NUMBER? (SYS)	INTRO 7-4
CHAPTER 8 EXAMPLES	INTRO 8-1

## CHAPTER 1

### LOGGING-IN

To begin programming on the DECsystem-10 Timesharing System, you need an account number and a password. You may also need to make a telephone connection to the computer; if so, you need the computer's telephone number. Write this information here:

Telephone Number: \_\_\_\_\_  
(if needed)

Account Number: \_\_\_\_\_

Password: \_\_\_\_\_

#### NOTE

Before logging-in, be sure to read Chapter 7 on KJOB (logging-out). If you do not log out, but merely disconnect your terminal, the DECsystem-10 accounting system will not know you have finished and WILL CONTINUE TO CHARGE YOU FOR TERMINAL TIME.

First, make sure that the terminal is turned on to LINE. If you are to make a telephone connection to the computer, turn on the acoustic coupler and then dial the telephone number to make the connection to the DECsystem-10.

The computer now may print a few lines identifying itself and will print:

PLEASE LOGIN OR ATTACH

followed by a line beginning with a period (.). This period signifies the computer's readiness to accept your LOGIN command. If the computer does not print a period, type CTRL/C (^C). The ^C may appear as an † on some terminals. The computer will respond with a period.

#### NOTE

C To type CTRL/C, hold the Control (CTRL) key down while typing C. This causes the computer to print the characters ^C on the terminal. In this book, the symbols ^C will mean that you are to type CTRL/C. In order to signal the computer system that you wish to give it a command, you can type ^C. This is your way of getting the computer's attention so that you can give it your next command.

## LOGGING-IN

MONITOR Monitor: In what follows we shall often call the computer system the monitor; this is the operating system or executive program that directs the execution of all the programs and performs the record-keeping duties for the computer.

You may now log in by typing:

LOGIN .LOGIN account number <CR> ("<CR>" means carriage return.)

Example: If your account number were 27,240 you would type

.LOGIN 27,240<CR>

### NOTE

We shall use the symbol <CR> to show where you are to press the RETURN key. This key may also be labelled CR or CAR RET and is often referred to as a "carriage return". To distinguish between characters you type and those the computer prints, underlining will be used for the characters you, the user, type.

The monitor will now respond with the lines:

JOB job number system number TTY terminal line number  
PASSWORD:

(The job number is assigned by the monitor.)

PASSWORD The monitor is now asking for your password. You should respond by typing your password and pressing the RETURN key. Since many users prefer to keep their passwords secret, the password is not printed. If your password were the word TROLL, and if everything you typed were printed, the output would appear as:

PASSWORD: TROLL

But what actually appears is

PASSWORD:

The monitor signals its acceptance of your account number and password by typing the time, date, and perhaps a message. Then it types a period (.) indicating that it is ready to accept your command. What you now have on the page will look something like this (remember that the underlined passages are those that you have typed).

Example:

.LOGIN 27,240<CR>  
JOB 25 R5725D SYS #40/2 TTY106  
PASSWORD: <CR>  
1242 18-NOV-76 THUR

## CHAPTER 2

### TYPING IN YOUR PROGRAM

R SOS To type in your program, you will use an editing program called SOS. Call SOS by giving the monitor command:

.R SOS<CR>

SOS responds with:

FILE:

asking you for the name of your file. (The computer stores your program on a disk.) You must give the file a name by which you and the computer can refer to it - you may think of this name as the name of your program. This name must be from one to six letters or digits. Because the computer can handle several different computer languages, you must also declare that this file will be used to store a program written in FORTRAN language. This is done by extending the name of your file with the letters FOR. These letters will be separated from the filename (or program name) by a period. Some examples of filenames in which you may store programs written for FORTRAN are:

ASPEN.FOR  
ASC123.FOR  
INSPIR.FOR

Whenever you refer to your program, use its full name with extension.

Now you should type in the name of your file/program.

Example: (Here the name of the file or program is ASPEN.FOR.)

.R SOS<CR>

FILE: ASPEN.FOR<CR>

SOS will now print:

INPUT: ASPEN.FOR  
00100

and the carriage will move to the correct position (column 1) for you to begin typing your program. Remember that in a FORTRAN program, columns 1 through 5 are reserved for the

## TYPING IN YOUR PROGRAM

statement number, column 6 is the continuation field, and columns 7 through 72 are for the FORTRAN statement. The number 00100 that SOS has printed is not part of your program, but is SOS's line number for the first statement of your program. If this first statement is not a numbered or comment statement, you must skip 6 spaces (to column 7) before beginning to type in the statement. When you have typed in the first line of your program, press the RETURN key, and SOS will print the next line number (in increments of 100); you may enter the next line of your program. Thus, when SOS prints a line number, you know that it is ready to accept a line of your program. (For a fast way of skipping the label field, see the section on TAB, page INTRO 4-6.)

### TO STOP ENTERING LINES INTO YOUR PROGRAM (ESCAPE)

**ESCAPE** When you wish to stop entering lines into your program, you should press the ESCape key (on some terminals labeled ESC, ALT, ALTMODE, or PREFIX). We shall refer to this key as ESCape. Pressing the ESCape key causes a \$ to be printed on the terminal.

Example: (In this example, the first statement is a comment statement: the character C is in column 1.)

^C

.R SOS<CR>

```
FILE: ASPEN.FOR<CR>
INPUT: ASPEN.FOR
00100 C THIS IS AN EXAMPLE.<CR>
00200       TYPE 10<CR>
00300 10 FORMAT (' ASPEN IS A NICE PLACE TO SKI!')<CR>
00400       ENI<CR>
00500 $
*
```

### **SOS**

Note that we have two programs that are already stored in the computer - the system monitor program and SOS. As you know, the monitor indicates its readiness to accept your command by printing a period (.); SOS indicates its readiness to accept your command by printing an asterisk (\*). When you press the ESCape key, SOS returns with an asterisk (\*) showing that it is ready to accept a command.

### **E**

### ENDING OR STORING YOUR PROGRAM (E)

It is very important, when you have finished writing your program, that you tell SOS you are done and that it should store your program until you are ready to use it again. You respond to SOS's request for a command by typing the End command (the letter E) and the RETURN key.

Example:

\*E<CR>

[DSKC:ASPEN.FOR]

## TYPING IN YOUR PROGRAM

In this example, SOS tells us that the program ASPEN.FOR has been stored on the disk (named DSKC:). Then SOS turns control over to the monitor, which signals its readiness to accept your next command by printing a period.

### NOTE

The SOS END command, E, is essential. If you don't tell SOS to store your file before you return to the monitor, your program will be lost.

## RUBOUT      THE RUBOUT OR DELETE KEY (CORRECTING TYPING MISTAKES)

If you make a mistake while typing a line, the RUBOUT (DELETE or DEL) key allows you to correct your mistake without having to retype the entire line. Press the RUBOUT key once for each character you wish deleted. This causes the deleted characters to be printed with a backslash (\) before and after them. Then, type the correct characters.

Example:

FILE: ASPN\N\EN.FOR<CR>

In this example, the character 'N' has been rubbed out.

Example:

00300 10 FORMAT (' APE\EP\SPEN IS A NICE PLACE TO SKI!')<CR>

In this example, the RUBOUT key was pressed twice to erase the unwanted characters PE. Note also that the deleted characters are printed in reverse order.

Think of the RUBOUT key as a "backspace plus erasure" key!



## CHAPTER 3

### RUNNING YOUR PROGRAM

#### THE EXECUTE COMMAND

##### EXECUTE

EX To execute or cause the computer to follow the instructions given by the program, command the monitor to:

```
.EXECUTE filename.extension<CR>
```

Example:

```
*EXECUTE ASPEN.FOR<CR>
FORTRAN: ASPEN
MAIN.
LINK: LOADING
[LINKXCT ASPEN EXECUTION]
ASPEN IS A NICE PLACE TO SKI!

END OF EXECUTION
CPU TIME: 0.05 ELAPSED TIME: 0.15
EXIT
```

\*

EXECUTE may be abbreviated to EX.

#### NOTE

You may have been puzzled at the occurrence of lines written by the monitor before the actual execution in the above example. They appear because before your FORTRAN source program can be executed, it must be translated or compiled into a machine language program (the object program) that the computer can execute. This is done during the step labeled FORTRAN: filename. This object program, like the original source program, is stored in a disk file. Before the program can be executed, a copy of the compiled or object program must be placed (loaded) into the working memory of the computer - this copy is often called a core image of the object program. This is accomplished during the LINK: LOADING step. Finally, the execution step is performed.

## RUNNING YOUR PROGRAM

Few programs will complete execution the very first time you try to execute them. Do not be discouraged! Chances are that the compiler will find at least one mistake in your program. To help you find your mistake(s), it will type out a message to you. For example, suppose that you have made the following mistake in the program on page INTRO 2-2: in the FORMAT statement in line 300 the closing quote has been omitted. The program would look like this:

```
00100 C THIS IS AN EXAMPLE.  
00200      TYPE 10  
00300 10   FORMAT (' ASPEN IS A NICE PLACE TO SKI!)  
00400      END
```

\*

An attempt to EXECUTE it will cause the following:

```
.EX ASPEN,FORKCR>  
FORTRAN: ASPEN  
00300      10   FORMAT (' ASPEN IS A NICE PLACE TO SKI!)  
?FTNCQL LINE:00300 NO CLOSING QUOTE IN LITERAL  
?FTNFWE LINE:00300 FOUND END OF STATEMENT WHEN EXPECTING A  
")"
```

### UNDEFINED LABELS

```
10  
  
?FTNFNL MAIN.          3 FATAL ERRORS AND NO WARNINGS  
LINK: LOADING  
[LNKNSA NO START ADDRESS]  
  
EXIT  
  
*
```

If the compiler has found errors in your program that make execution impossible, you will again have to call on SOS to help you correct your program. Do this by using the R SOS command discussed in Chapter 4.

### NOTE

The compiler will only print error messages for cases where the program is not clearly understood. It is possible to have a program that consists of valid FORTRAN statements, but gives the wrong answers. For example, suppose you intended to enter

TAX = RATE\*AMOUNT

but by mistake typed

TAX = RATE+AMOUNT

## RUNNING YOUR PROGRAM

The compiler cannot detect this as an error because both are possibly valid formulas. Errors of this type (logic errors) are the most difficult to find. The program will run, but the answers will be wrong. Frequently the author of the program will read the statement and see what he meant to write instead of what he actually wrote. One extremely valuable method of finding errors of this kind is to attempt to explain to someone else why the program should work. The act of explaining will often highlight the error. Another method of locating errors is to have another programmer "proofread" your code.

^C

### CTRL/C (^C) (GETTING THE MONITOR'S ATTENTION)

CTRL/C informs the monitor that you wish to give it a command. The monitor interrupts whatever the computer is doing and prints a period to indicate that it is ready to accept your command. To type CTRL/C, hold the Control (CTRL) key down while typing C.

### Stopping Your Program's Execution

CTRL/C interrupts a program during execution, returning control to the monitor. Sometimes it is necessary to type CTRL/C twice to interrupt a program.

Example:

```
.EXECUTE ASPEN.FOR<CR>
FORTRAN:  ASPEN
```

^C^C

### Deleting a Command

You may also use CTRL/C to delete the line you are presently typing and return control to the monitor.

Example:

```
.EXECUTE ASPEN.FOR^C
```

Typing "CONT" in answer to a monitor prompt will return you to your previous activity IF AND ONLY IF you have not:

- tampered with the core image, OR
- caused the FORTRAN compiler image in core to be overwritten.

If, for instance, you interrupt the executing program to send a message to someone on another terminal, you can

## RUNNING YOUR PROGRAM

return. If you, say, request a directory activity, then the FORTRAN compiler is overwritten and you cannot return to your previous activity. When in doubt, wait until the execution is complete, unless you want to restart the execution anyway.

### CTRL/U (^U) (CHANGING A LINE)

^U

CTRL/U deletes the entire line you are typing and moves the carriage to the beginning of the next line. You may then retype the line. Note that CTRL/U only deletes that part of the line you have typed and not the part the computer prints, i.e., in the following example the line number is not deleted. CTRL/U is typed by holding the Control (CTRL) key down while typing U.

Example:

01800	40	SROOT = SRT (DISC) ^U
	40	<u>SROOT = SQRT (DISC)&lt;CR&gt;</u>
01900		

In this example, CTRL/U deletes your input line, which you then reenter. CTRL/U does not delete the line number, 1800, printed by SOS.

If you wish to delete the line entirely, follow CTRL/U with the RETURN key.

## CHAPTER 4

### CHANGING YOUR PROGRAM

#### THE R SOS COMMAND (CORRECTING MISTAKES IN YOUR PROGRAM)

R SOS To correct a mistake in a program, you must return to SOS. As we saw on page INTRO 2-1, we turn control over to SOS by commanding the monitor:

R SOS<CR>

SOS responds with:

FILE: QUAD.FOR<CR>

and we type the filename and extension, in this case QUAD.FOR. But now SOS recognizes that this program already exists and correctly assumes that, instead of inputting a file, you wish to edit it. SOS thus types:

EDIT: QUAD.FOR  
\*

The asterisk (\*) indicates that SOS is at your command. The remainder of this section lists SOS commands that are essential for typing and editing simple FORTRAN programs. Use the ESCape to terminate these commands.

#### SOS COMMANDS

##### I I - Inserting Lines Into Your Program

INSERT To Insert lines into your program beginning with line 2700, for instance, you give SOS the command:

\*I2700<CR>

SOS types out each line number, and you respond by inserting the line into the program. When you press the RETURN key after typing each line, SOS will type the next line number. (This is called "Insert Mode".)

## CHANGING YOUR PROGRAM

Example:

```
*I2700<CR>
02700      IF (DISC) 20, 30, 40<CR>
02800      40      ROOT1 = (-B + SQRT (DISC))/(2*A)<CR>
02900
```

Terminate the Insert command by typing ESCape (ALTMODE/PREFIX); this causes a \$ to be printed on the terminal.

Example:

```
*I4000<CR>
04000      20      WRITE (5, 70)<CR>
04100      $*
*
```

Note that in the above examples, SOS has numbered the lines in increments of 100. The reason for providing this increment is to allow you room to maneuver - suppose you have accidentally omitted lines that must now be Inserted, or suppose you now find it necessary to change your original program. If you have left out 2 lines that should have gone between lines 3200 and 3300, you may Insert these lines by changing the increment size, say, to 20, using the command:

```
*I3210,20<CR>
```

This allows you to Insert lines 3210, 3230, 3250, 3270, and 3290 into your program. The size of the increment is of no importance as long as it is small enough to accommodate all additional lines. Each time you change the increment size, the new size is kept until you change it.

Example:

```
*I3210,20<CR>
03210 WRITE (5, 50) ROOT1, ROOT2<CR>
03230 50 FORMAT (' ROOTS ARE', F10.2, 'AND', F10.2)<CR>
03250  $*
*
```

If you try to insert a line whose line number is greater than or equal to that of the next existing line, SOS will:

- . use a different line number, or
- . ignore the command entirely

## CHANGING YOUR PROGRAM

D            D - Deleting Lines From Your Program  
DELETE    To delete line 500 from your program, type

\*D500<CR>

Example:

```
*D500<CR>
1 LINES (00500/1) DELETED
*
```

If you wish to delete lines 1400 through 1600 from your program, use:

\*D1400:1600<CR>

Example:

```
*D1400:1600<CR>
3 LINES (01400/1:1600) DELETED
*
```

R            R - Replacing Lines in Your Program

REPLACE    The Replace command is a combination of a Delete command followed by an Insert command. To instruct SOS to delete line 1700 and to begin inserting lines at line 1700, use the Replace command:

\*R1700<CR>

This is equivalent to the command D1700 followed by the command I1700.

Example:

```
*R1700<CR>
01700 60      FORMAT (' ROOT IS', F10.2)<CR>
1 LINES (01700/1) DELETED
*
```

To replace lines 500 through 700 use:

\*R500:700<CR>

This is equivalent to D500:700 commanding SOS to delete lines 500 through 700, followed by the command I500 instructing SOS to begin inserting lines at 500.

## CHANGING YOUR PROGRAM

Example:

```
*R500:700<CR>
00500 80      FORMAT ('OGIVE COEFFICIENTS')<CR>
00600      READ (5, 10) A, B, C<CR>
00700 10      FORMAT (F10.2)<CR>
3 LINES (00500/1:00700) DELETED
*
```

If you also wish to change the increment size to 10, use the Replace command:

```
*R1000:1100,10<CR>
```

This is equivalent to the command D1000:1100 followed by the command I1000,10.

Example:

```
*R1000:1100,10<CR>
01000 40      SROOT = SQRT (DISC)<CR>
01010      DENOM = 2*A<CR>
01020      ROOT1 = (-B + SROOT) / DENOM<CR>
01030      ROOT2 = (-B - SROOT) / DENOM<CR>
01040  $
2 LINES (01000/1:01100) DELETED
*
```

As with the Insert command, to terminate the Replace command, use the ESCape as in the above example.

P

P - Printing Lines of Your Program on the Terminal

PRINT

If you wish to print line 1800 of your program, type

```
*P1800<CR>
```

Example:

```
*P1800<CR>
01800 40      SROOT = SQRT (DISC)
*
```

To print lines 2700 through 3000 of your program, use

```
*P2700:3000<CR>
```

## CHANGING YOUR PROGRAM

Example:

```
*P2700:3000<CR>
02700 30      ROOT = -B / (2*A)
02800          WRITE (5, 60) ROOT
02900 60      FORMAT (' ROOT IS ', F10.2)
03000          GO TO 100
*
```

N

### N - Changing the Line Numbers

NUMBER

The Number command instructs SOS to renumber your program beginning at line 100 in increments of 100. SOS does not print anything on the terminal. If you wish to see the renumbered program, you must use the Print command.

Example:

```
*N<CR>
*
```

E

### E - End (Ends Editing and Stores the Program)

END

When you have completed editing your program, inform SOS that it should now store your program on the disk by typing E (end). If you do not instruct SOS to store your program, the editing you have just completed will be lost.

Example:

```
*E<CR>
[DSKC:QUAD.FOR]27,240]]
```

\*

This indicates that the program named QUAD.FOR has been stored on DSKC:. The End command turns control over to the monitor, which prints a period to indicate its readiness to accept your next command.

EQ

### EQ - Returning to the Monitor Without Storing Your Program

QUIT

If you decide that the current editing session is worthless, you may return to the monitor without storing your program by using the Quit command.

## CHANGING YOUR PROGRAM

Example:

\*EQ<CR>

\*

This restores the original copy of the program as it was when you last typed R SOS. If the program is a new one, it is deleted since an original program did not exist.

### A FEW SOS CONVENTIONS

1. A range of lines is indicated by a colon between the first and last line numbers of the range, i.e., 500:700.
2. A period represents the current line. Thus, D. means delete the current line.

Example:

```
00700    80      FORMAT ('OGIVE COEFFICIENTS')
*D.<CR>
1 LINES (00700/1) DELETED
*
```

In the above example the current line is line 700 and it is deleted.

3. An asterisk is used to represent the last line of the file. Thus, to instruct SOS to print out your entire file use:

\*FO:\*<CR>

TAB

TAB (CTRL/I)

The TAB or Horizontal Tab (sometimes labeled HT or  $\rightarrow$ ) is handy when you are entering lines into your program. The TAB, similar to that on a typewriter, is set at 8-character intervals. It moves the carriage to the next column that is a multiple of 8; no characters are output on the terminal. As you know, a FORTRAN statement must be located within columns 7 through 72, although it may appear at any point within this range. Using the TAB to skip over all or part of the label field will bring the carriage to column 8, enabling you to begin your FORTRAN statement in that column. If your terminal does not have a key labeled TAB, use CTRL/I instead. To type CTRL/I, hold down the Control (CTRL) key while typing I.

### CORRECTING MISTAKES

To correct one or more characters use the RUBOUT key (see page INTRO 2-3).

To change an entire line use CTRL/U (see page INTRO 3-4).

## CHANGING YOUR PROGRAM

Example:

```
*D1500 ^U<CR>
I2000<CR>
2000
```

In the above example, CTRL/U (^U) allows you to change the command "Delete line 1500" to an insert command.

Example:

```
.R SOS<CR>
```

```
FILE: ZELDA.FOR<CR>
INPUT: ZELDA.FOR
00100 C THIS PROGRAM DOES NOTHING.<CR>
00200      TYPE 10<CR>
00300 10 FORMAT (' IT''S WORKING!')<CR>
00400      TYPE\N\FE 20<CR>
00500 $
*P400<CR>
00400      TYPE 20
*I500<CR>
00500 20 FORMAT (' WHAT IS YOUR NAME?')<CR>
00600      ACCEPT 30, YORNAM ^U
ACCEPT 30, YORNAM<CR>
00700 30 FORMAT (A5)<CR>
00800      TYPE 40, YORNAM<CR>
00900 40 FORMAT ('O', 'HI,', A5, 'DO YOU EANT')<CR>
01000 $
*R900<CR>
00900 40 FORMAT ('OHI, ', A5, ' ,DO YOU')<CR>
01000      TYPE 50<CR>
01100 50 FORMAT ('      WANT TO BE FRIENDS?')<CR>
01200      END<CR>
01300 $
1 LINES (00900/1) DELETED
*R900:1100<CR>
00900 40 FORMAT ('OHI, ', A5, ' , WANT TO BE FRIENDS?')<CR>
01000 $
3 LINES (00900/1:01100) DELETED
*N<CR>
*FO:*<CR>
00100 C THIS PROGRAM DOES NOTHING.
00200      TYPE 10
00300 10 FORMAT (' IT''S WORKING!')
00400      TYPE 20
00500 20 FORMAT (' WHAT IS YOUR NAME?')
00600      ACCEPT 30, YORNAM
00700 30 FORMAT (A5)
00800      TYPE 40, YORNAM
00900 40 FORMAT ('OHI, ', A5, ' , WANT TO BE FRIENDS?')
01000      END
*E<CR>

CDSKC: ZELDA.FOR]
```

\*

## CHANGING YOUR PROGRAM

Let us look at the above example in detail.

.R SOS<CR>

Commands the monitor to turn control over to the editor program SOS.

FILE: ZELDA.FOR<CR>

SOS requests the name of the file you wish to edit. You respond with the name of your file or program: ZELDA.FOR.

INPUT: ZELDA.FOR  
00100 C THIS PROGRAM DOES NOTHING.<CR>

When SOS fails to find a file by this name, it concludes that you intend to create a new file. SOS then prints the name of the file and the first line number. Now you are ready to enter the first line of the program.

00200 TYPE 10<CR>

Each time you finish typing a line and press the RETURN key, SOS prints out the next line number so that you may input that line. In typing line 200, the first character actually typed was a TAB (CTRL/I), which caused the label field to be skipped over; this avoids the necessity of counting spaces so that our FORTRAN statement would begin in the proper column. TAB is a non-printing character.

00300 10 FORMAT (' IT''S WORKING!')<CR>

This statement is labeled. After typing the FORTRAN statement label (10), you type the non-printing character TAB (CTRL/I) to skip over the remainder of the label field. Remember that the first character of a printing FORMAT statement must be the carriage control (here a blank, which means single space output). Notice that because apostrophes are used to enclose literal fields, they are not allowable characters within a literal field but must instead be represented by two successive apostrophes. In other words, although line 300 appears in the program with two successive apostrophes (IT''S), in the execution it causes the word IT'S to be printed (see the EXECUTION which follows).

00400 TYPE\NPE 20<CR>

Again, a non-printing TAB is used here to skip over the label field. The RUBOUT key erases the E.

00500 \$

The ESCape key terminates the input of lines into the program.

\*F400<CR>

## CHANGING YOUR PROGRAM

SOS is now ready for a new command. You ask it to print line 400.

00400            TYPE 20

SOS prints line 400.

\*I500<CR>

Your next step is to insert lines into your program beginning with line 500.

00500    20     FORMAT (' WHAT IS YOUR NAME?')<CR>

You type line 500 into your program.

00600            ACCEPT 30, YORNAM ^U  
ACCEPT 30, YORNAM<CR>

After typing in line 600 but before pressing the RETURN key, you pause and notice that you have misspelled ACCEPT. CTRL/U (^U) deletes the line, which you then retype beginning with the non-printing TAB.

00700    30     FORMAT (A5)<CR>  
00800            TYPE 40, YORNAM<CR>  
00900    40     FORMAT ('0','HI,',A5,'DO YOU EANT')<CR>  
01000    \$

You enter lines 700 through 900 into your program and terminate the insert. The carriage control '0' in the FORMAT statement causes the output to be double spaced.

\*R900<CR>

At this point, you decide to replace line 900. The R900 command causes it to be deleted and initiates an Insert command beginning with line 900.

00900    40     FORMAT ('OHI,', A5, ' ,DO YOU')<CR>  
01000            TYPE 50<CR>  
00100    50     FORMAT (' WANT TO BE FRIENDS?')<CR>  
01200            END<CR>  
01300    \$  
1 LINES (00900/1) DELETED

When you use the ESCape key to terminate the insert command (initiated by the replace command), SOS informs you that one line (line 900) has been deleted.

\*R900:1100<CR>

## CHANGING YOUR PROGRAM

You decide to replace lines 900 through 1100.

```
00900 40 FORMAT ('OHI,, AS,, WANT TO BE FRIENDS?')<CR>
01000 $  
3 LINES (00900/1100) DELETED
```

Line 900 is replaced and the command is terminated. SOS confirms that three lines (900 through 1100) have been deleted.

\*N<CR>

SOS is now asked to renumber the lines beginning with 100 and in steps of 100.

\*P0:\*<CR>

You instruct SOS to print out your entire program.

\*E<CR>

To conclude the editing session, instruct SOS to store your program on the disk.

[DSKC:ZELDA.FOR]

\*

Your program has been stored on DSKC:. The monitor is now in control.

The EXECUTION of the above program:

```
>EX ZELDA.FOR<CR>
FORTRAN: ZELDA
MAIN.
LINK: LOADING
[LINKXCT ZELDA EXECUTION]
IT'S WORKING!
WHAT IS YOUR NAME?
HAL<CR>
```

HI, HAL , WANT TO BE FRIENDS?

```
END OF EXECUTION
CPU TIME: 0.10 ELAPSED TIME: 10.20
EXIT
```

\*

## CHAPTER 5

### FORTRAN-10 INPUT AND OUTPUT OF DATA

Although FORTRAN-10 is essentially the same as standard FORTRAN, a few minor differences do arise in statements that involve the input and output of data.

#### READ STATEMENT

READ      The statement

```
    READ (u,f)list
```

where u=device unit number and

f=FORMAT statement number

reads data from the device with unit number u (refer to the section on Device Unit Numbers, below) according to the specifications given by FORMAT statement f.

Example:

```
00800      READ (5, 35) IGRADE  
00900      35      FORMAT (I3)
```

#### WRITE STATEMENT

WRITE      This has the form

```
    WRITE (u,f) list
```

where u=device unit number and

f=FORMAT statement number

Example:

```
01000      WRITE (1, 30) (STUDNT(I), I=1,8), IGRADE  
01100      30      FORMAT (8A5, I3)
```

#### NOTE

The ERR option of the OPEN and CLOSE statements is also applicable to the READ and WRITE statements. Refer to Chapter 12

## FORTRAN-10 INPUT AND OUTPUT OF DATA

### DEVICE UNIT NUMBERS

In READ and WRITE statements, we must specify to which device (Disk, Line Printer, Terminal, etc.) we are referring. For the DECsystem-10, the device unit numbers, u, are uniform - they are the same on all DECsystem-10s. The most commonly used are:

Device	Device Unit Number, u
Disk	01
Card Reader	02
Line Printer	03
Terminal	05

(For a complete list see FORTRAN-10 Language Manual, Table 10-1.)

Thus, WRITE (5,7) causes output to be printed on your terminal; READ (1,25) causes data to be read from the disk.

### ACCEPT STATEMENT

ACCEPT To input data from the terminal you may use

ACCEPT f,list

where f=the FORMAT statement number.

Example:

```
00500      ACCEPT 20, IGRADE
00600  20      FORMAT (I3)
```

Thus, "ACCEPT f,list" is equivalent to "READ (5,f) list".

### TYPE STATEMENT

TYPE To have output typed on your terminal use

TYPE f,list

where f=the FORMAT statement number.

Example:

```
00200      TYPE 10
00300  10      FORMAT ('ASPEN IS A NICE PLACE TO SKI!')
```

Thus, "TYPE f,list" is equivalent to "WRITE (5,f) list".

### NOTE

To print something on your terminal, you must include a carriage control character similar to the way you do for a line printer. For example, to print the word HELLO on your terminal, use the format statement below:

```
00200      TYPE 101
00300  101      FORMAT (' HELLO')
```

## FORTRAN-10 INPUT AND OUTPUT OF DATA

The space before HELLO tells the system to start on a new line.

### DATA FILES

You may use data files in one of two ways:

1. In the first method, you let FORTRAN use a predefined filename.
2. In the second method, you choose the filename by using the OPEN statement.

#### Letting FORTRAN Use A Predefined Filename

There are six Device Unit Numbers for disk files; whenever you use one of them, FORTRAN uses a predetermined filename. The device numbers and their filenames are listed below.

Device Unit Number	Filename
1	FOR01.DAT
20	FOR20.DAT
21	FOR21.DAT
22	FOR22.DAT
23	FOR23.DAT
24	FOR24.DAT

#### NOTE

If you omit the filename from an OPEN statement, FORTRAN uses the filename corresponding to the device unit number.

#### Examples:

00200    WRITE (1,101) X	Writes the value of X in the file FOR01.DAT, according to FORMAT statement 101.
00300    READ (23,109) Y	Reads the value of Y from the file FOR23.DAT, according to FORMAT statement 109.

### Using Your Own Filename

#### OPEN

To use your own filename, place an OPEN statement before the first READ or WRITE statement that accesses the file. The OPEN statement has the format:

```
OPEN (UNIT=n, FILE='filename.ext')
```

n is the device unit number, and filename.ext is the name of the file you want to use.

## FORTRAN-10 INPUT AND OUTPUT OF DATA

Example:

00200 OPEN (UNIT=20, FILE='TEST.DAT')

Instructs FORTRAN to open  
the file TEST.DAT on  
logical unit number 20.

00300 READ (20,105) Y

Reads Y from logical unit  
number 20. (The file  
name implied is the same  
as the file name in the  
OPEN statement with the  
same logical unit  
number.)

After the last READ or WRITE statement that accesses a file,  
it is recommended (though not required) that you include a  
CLOSE statement. The CLOSE statement has the format:

CLOSE

CLOSE (UNIT=n, FILE='filename.ext')

n is the device unit number, and filename.ext is the name of  
the file you are closing.

Example:

00500 CLOSE (UNIT=20, FILE='TEST.DAT')

Closes the file TEST.DAT on logical unit number 20.

## CHAPTER 6

### SOME HELPFUL COMMANDS

#### TYPE COMMAND (PRINTING OUT YOUR PROGRAM)

TYPE      Usually you will have made many changes in your program. If you would like the monitor to TYPE out your program on your terminal as it now stands, command it to:

```
.TYPE filename.extension<CR>
```

Example:

```
.TYPE ASPEN.FOR<CR>
00100 C THIS IS AN EXAMPLE.
00200      TYPE 10
00300 10      FORMAT ('' ASPEN IS A NICE PLACE TO SKI!'')
00400      END
```

\*

#### DIRECT COMMAND (LISTING ALL THE STORED PROGRAMS AND FILES)

DIR      The DIRECT command causes the monitor to list all the programs and files stored in disk files under your account number. It also lists the length of each program or file in terms of DECsystem-10 disk blocks (a disk block is 640 characters) and the date on which each was created. This command may be abbreviated to DIR.

Example:

```
.DIR<CR>
```

```
ASPEN   REL     1 <055>  18-NOV-76  DSKC: [27,240]
ASPEN   QOR     1 <055>  18-NOV-76
ASPEN   FOR     1 <055>  18-NOV-76
NEW     QOR     2 <055>  18-NOV-76
QUAD    REL     3 <055>  18-NOV-76
NEW     FOR     2 <055>  18-NOV-76
QUAD    QOR     2 <055>  18-NOV-76
SNOW    FOR     1 <055>  18-NOV-76
QUAD    FOR     2 <055>  18-NOV-76
TOTAL OF 15 BLOCKS IN 9 FILES ON DSKC: [27,240]
```

\*

These files belong to the programmer(s) with account number 27,240.

## SOME HELPFUL COMMANDS

You may find that files you did not create are also listed. These may be programs and files created by the computer in editing and compiling your program. The compiled program is contained in a file named "filename.REL" where the filename is the same one that you used. If you have edited your program there will be a program whose name is identical to yours except that it has a Q as the first letter of the extension. This is a backup file containing your program as it existed prior to your most recent editing of it. Each time your program is edited, the program immediately before editing becomes the backup, and the previous backup - if it existed - is lost. In the foregoing example, the only files explicitly created were ASPEN.FOR, NEW.FOR, SNOW.FOR, and QUAD.FOR. The backups are ASPEN.QOR, NEW.QOR, and QUAD.QOR. SNOW.FOR has not been edited, so it has no backup.

### DELETE COMMAND (ERASING A PROGRAM OR FILE)

#### DELETE

To erase a file from the disk, command the monitor to:

```
.DELETE filename.extension<CR>
```

Example:

```
.DELETE ASPEN.FOR<CR>
FILES DELETED:
ASPEN.FOR
01 BLOCKS FREED
```

\*

### RENAME COMMAND (GIVING A PROGRAM OR FILE A NEW NAME)

#### RENAME

To rename a file use the command

```
.RENAME newfilename.extension = oldfilename.extension<CR>
```

Example:

```
.RENAME EXAMP.FOR=SNOW.FOR<CR>
FILES RENAMED:
SNOW.FOR
```

\*

This will cause the name of SNOW.FOR to be changed to EXAMP.FOR

### CTRL/O (SUPPRESSING PRINTED OUTPUT)

^O

CTRL/O (^O) stops printed output on the terminal. The program sending the output CONTINUES TO RUN. Use CTRL/O, for example, to stop the message of the day during LOGIN or to stop the monitor as it TYPES a program you have asked for. CTRL/O is typed by holding the Control (CTRL) key down while typing the letter O.

## SOME HELPFUL COMMANDS

Example:

```
* TYPE ASPEN,FOR<CR>
00100 C THIS IS AN EXAMPLE,
40200      TYPE 10
00300  ~0
```

Although CTRL/C also stops output on the terminal, it also stops program execution.

### Complaints to the Computer - the "Court of Last Resort"

GRIPE When all else fails and you must gripe to someone, GRIPE to the computer by commanding the monitor to:

```
*R GRIPE<CR>
```

The computer will respond with:

```
YES? (DEPRESS ESCAPE KEY WHEN THROUGH)
```

Now enter your gripe and press the ESCape key when you have finished. Remember that typing ESCape causes a \$ to be printed.

Example:

```
*R GRIPE<CR>
```

```
YES? (DEPRESS ESCAPE KEY WHEN THROUGH)
```

THIS CONSOLE IS ALMOST OUT OF PAPER.\$

THANK YOU



CHAPTER 7  
SAYING GOODBYE TO THE COMPUTER

KJOB COMMAND (LOGGING-OUT)

To say goodbye to the computer, command the monitor to KJOB (KillJOB) :

KJOB            « KJOB<CR>

The monitor will respond with

CONFIRM:

KILL  
PRESERVE  
SAVE

Should you now decide to abort the logout, type CTRL/C (^C). If you still wish to logout, you must instruct the monitor to kill, preserve, or save each of your disk files. If a file is killed, it is erased from the computer memory; saved and preserved files, on the other hand, are retained in the computer memory. Preserve and save are essentially alike except in the matter of protection against inadvertent loss or destruction. Preserve, unlike save, protects your files from accidental destruction by another user who shares your account number. This may occur if, for instance, the other user fails to recognize the name of your program during his logout and, failing to see any need for its preservation, kills it. To take advantage of the protection afforded by the preserve file status, it is best to respond to the CONFIRM with the letter U:

CONFIRM: U <CR>

This will automatically preserve any files that have already been preserved during a previous logout. After you have typed in the letter U and pressed the RETURN key, the monitor will list the name and storage information of each unpreserved file stored in your disk area, pausing after each name for your response. Following the name of each file you must respond by typing one of the three commands:

- (a) K if you wish to kill the file,
- (b) P to preserve it, and
- (c) S to save it.

Please remember the saved or preserved files occupy valuable space on the disk.

In general, the only files you need preserved have the extension FOR. If you have no further changes to make in your program, you may preserve the compiled version - this will have the extension REL.

## SAYING GOODBYE TO THE COMPUTER

### NOTE

The DECsystem-10 offers the option of detaching the terminal from your job, thereby freeing the terminal and the telephone line for another task while your program is executing. (This option is, of course, only used for programs with long execution times; for details see the DECsystem-10 Operating System Commands Manual.) Therefore, TURNING OFF THE TERMINAL OR BREAKING THE TELEPHONE CONNECTION TO THE COMPUTER DOES NOT END YOUR JOB, NOR DOES IT STOP THE COMPUTER CLOCK; ONLY THE COMMAND KJOB WILL DO THIS. If you should inadvertently hang up without using KJOB, the computer clock, thinking that you have not yet completed your job, will keep ticking and CHARGING YOU FOR TERMINAL TIME. So please remember to USE KJOB BEFORE LEAVING THE TERMINAL. If you should be accidentally disconnected, always call again and end your job properly. (See page INTRO 7-3.)

### Example

```
+KJOB<CR>
CONFIRM? U<CR>
DSKA:
DSKC:
ASPEN .REL <055> 5.BLKS : S<CR>
ASPEN .QOR <055> 5.BLKS : K<CR>
NEW .QOR <055> 5.BLKS : K<CR>
QUAD .REL <055> 5.BLKS : S<CR>
EXAMP .FOR <055> 5.BLKS : S<CR>
QUAD .QOR <055> 5.BLKS : K<CR>
SNOW .FOR <055> 5.BLKS : F<CR>
QUAD .FOR <055> 5.BLKS : F<CR>
NEW .FOR <055> 5.BLKS : K<CR>
ASPEN .FOR <055> 5.BLKS : F<CR>
DSKB:
JOB 25, USER [27,240] LOGGED OFF TTY106 1430 18-NOV-76
DELETED 4 FILES (20 BLOCKS)
SAVED FILES (30 BLOCKS)
RUNTIME 32.34 SEC
```

### K/F Command (Fast Logout)

K/F For a fast logout in which all programs and files are saved, use

```
+K/F<CR>
```

Although this form of the KJOB command has the advantage of being fast, you cannot preserve the programs you wish to keep nor kill those you no longer need.

## SAYING GOODBYE TO THE COMPUTER

Example:

```
*K/F<CR>
JOB 25,USER[27,240] LOGGED OFF TTY106 1432 18-NOV-76
SAVED ALL FILES (30 BLOCKS)
RUNTIME 1.56 SEC
```

### HELP Command (Getting Assistance)

To get assistance during logout, type H (for Help) and the monitor will respond.

### WHAT TO DO IF YOU ARE DISCONNECTED FROM YOUR JOB (ATTACH)

#### ATTACH

Although this can happen to anyone, it will most often happen when the telephone lines connecting you and the computer break that connection. If necessary, redial the telephone number to the computer. Under normal conditions, the computer will print:

PLEASE LOGIN OR ATTACH

You will wish to attach yourself to the job on which you had been working. To do this you must know its job number. This is given after your LOGIN command. For example, in the LOGIN example on page INTRO 1-3, the job number is 25.

You may attach to a job by using your account number

.ATTACH job number [account number]

The programmer with account number 27,240 may attach to job 25 by typing:

.ATTACH 25 [27,240]<CR>

If the programmer with this account number is the owner or originator of job 25, the monitor asks for his password. Otherwise, access to the program is denied. As during LOGIN, the password is not printed. If the password is accepted, the monitor prints a period and the programmer now is attached to his job.

Example:

.ATTACH 25 [27,240]<CR>
PASSWORD: \_\_\_\_\_ <CR>

\*

### NOTE

Account numbers are often called Project-Programmer Numbers (PPNs). In the ATTACH command, the account number must be enclosed in square brackets [ ]. If your terminal does not have keys labeled [ and ], use SHIFT/K for the left square bracket, [, and SHIFT/M for the right square bracket, ].

## SAYING GOODBYE TO THE COMPUTER

### FORGOT YOUR JOBNUMBER?(SYS)

SYS

Suppose you have forgotten your job number. You have thrown away your LOGIN, or perhaps you are using a Visual Display (CRT) terminal and the LOGIN has long since disappeared from the screen. What now? You may find out which jobs are being run under your account number by typing:

.SYS [account number]<CR>

Example:

```
*SYS [27,240]<CR>
25      DET      3      ^C SW      1
```

```
*KJOB<CR>
*ATTACH 25 [27,240]<CR>
PASSWORD? <CR>
```

Here, the programmer with account number 27,240 wishes to find out which jobs are logged in under his account number. The monitor answers that job 25 is logged in under account number 27,240 and that this job is DETached from a terminal. Then the programmer ATTACHes to job 25.

The SYS command may be given whether or not the user is logged in. If the user is not logged in, the SYS command automatically ends with the KJOB command.

## CHAPTER 8

### EXAMPLES

#### Example 1 (Executing a Program More than Once):

This program computes the roots of the quadratic equation  $ax^2 + bx + c = 0$ . Note that FORTRAN statement labels may be in any order and also that carriage control characters are necessary for each of the printing FORMAT statements.

```
.TYPE QUAD.FOR<CR>
00100 C      THIS PROGRAM COMPUTES THE ROOTS OF A
00200 C      QUADRATIC EQUATION OF THE FORM:
00300 C          2
00400 C          AX2 + BX + C = 0
00500 C
00600      WRITE (5, 80)
00700 80      FORMAT ('OGIVE COEFFICIENTS')
00800      READ (5, 10) A, B, C
00900 10      FORMAT (F10.2)
01000 C
01100 C      CALCULATE THE DISCRIMINANT
01200      DISC = B*B - 4*A*C
01300 C
01400 C      DO THE RIGHT THING ACCORDING TO THE SIGN OF DISC
01500      IF (DISC) 20, 30, 40
01600 C
01700 C      POSITIVE DISCRIMINANT
01800 40      SROOT = SQRT (DISC)
01900      DENOM = 2*A
02000      ROOT1 = (-B + SROOT) / DENOM
02100      ROOT2 = (-B - SROOT) / DENOM
02200      WRITE (5, 50) ROOT1, ROOT2
02300 50      FORMAT (' ROOTS ARE', F10.2, ' AND', F10.2)
02400      GO TO 100
02500 C
02600 C      ZERO DISCRIMINANT
02700 30      ROOT = -B / (2*A)
02800      WRITE (5, 60) ROOT
02900 60      FORMAT (' ROOT IS', F10.2)
03000      GO TO 100
03100 C
03200 C      NEGATIVE DISCRIMINANT
03300 20      WRITE (5, 70)
03400 70      FORMAT (' ROOTS ARE COMPLEX')
03500 100     STOP
03600     END
```

Below, this program is EXECUTED twice. In the second execution the words FORTRAN: QUAD are missing because the program has already been

## EXAMPLES

compiled, making it unnecessary for the compile step to be repeated. The program is simply loaded into core and executed. (See page INTRO 3-1.)

```
.EXECUTE QUAD,FOR<CR>
FORTRAN: QUAD
MAIN.
LINK:  LOADING
[LNKXCT QUAD EXECUTION]

GIVE COEFFICIENTS
2.<CR>
-10.<CR>
12.<CR>
ROOTS ARE      3.00 AND      2.00
STOP

END OF EXECUTION
CPU TIME: 0.13  ELAPSED TIME: 18.95
EXIT

 EXECUTE QUAD,FOR<CR>
LINK:  LOADING
[LNKXCT QUAD EXECUTION]

GIVE COEFFICIENTS
5.<CR>
-2.<CR>
10.<CR>
ROOTS ARE COMPLEX
STOP

END OF EXECUTION
CPU TIME: 0.12  ELAPSED TIME: 18.30
EXIT
```

### Example 2 (Reading A Disk File):

Student grades are recorded on a disk file named STDGRA.DES. Each record has a student name (40 characters) and his numerical grade (a 3-digit integer). The following program will read the grades and compute the mean and standard deviation.

```
.TYPE GRADE,FOR<CR>
00100  C  THIS PROGRAM COMPUTES THE MEAN AND
00200  C  STANDARD DEVIATION OF STUDENT GRADES
00300  C
00400      OPEN (UNIT=1, FILE='STDGRA.DES')
00500      NUMBER = 0
00600      SUM = 0
00700      SUMSQR = 0
00800  20      READ (1, 10, END=100) IGRADE
00900  10      FORMAT (40X, I3)
01000      NUMBER = NUMBER + 1
01100      SUM = SUM + IGRADE
01200      SUMSQR = SUMSQR + IGRADE*IGRADE
01300      GO TO 20
01400  100     AMEAN = SUM/NUMBER
01500     VARIAN = (SUMSQR - (SUM*SUM) / NUMBER) / (NUMBER-1)
01600     STDEV = SQRT (VARIAN)
01700     TYPE 30, NUMBER, AMEAN, STDEV
```

## EXAMPLES

```
01800 30      FORMAT ('NUMBER OF STUDENTS = ', I3 /  
01900           1' MEAN GRADE = ', F6.2 /  
02000           1' STANDARD DEVIATION = ', F6.2)  
02100           CLOSE (UNIT =1, FILE='STDGRA.DES')  
02200           END
```

```
.EX GRADE.FOR<CR>  
FORTRAN: GRADE  
MAIN.  
LINK: LOADING  
ELNKXCT GRADE EXECUTION]
```

```
NUMBER OF STUDENTS = 17  
MEAN GRADE = 80.29  
STANDARD DEVIATION = 10.45  
  
END OF EXECUTION  
CPU TIME: 0.23 ELAPSED TIME: 1.00  
EXIT
```

We are opening a disk file, reading the grades stored in it, and, closing the file. (See lines 400 and 2100.) Note that the logical unit number given in the OPEN and CLOSE statements (UNIT = 1) is the same as that given in the READ statement (line 800) and refers to the device disk.

Execution starts at statement 400 (the OPEN statement). There is a controlled loop at statements 800 - 1300. The last statement executed is the END statement at 2200.

### CONTINUATION LINES

Lines 1800, 1900, and 2000 are one FORTRAN statement, lines 1900 and 2000 being continuations of line 1800. Since TABs have been used at the beginning of each line to skip over all or part of the label field, a way must be provided to inform the computer that the line is a continuation line.

The rule is: If the first character (after the TAB) is any number between 1 and 9, then the line is a continuation line.

### Example 3 (Writing A Disk File):

The following is the program that created the data file STDGRA.DES. Notice that in the OPEN, WRITE, and CLOSE statements (lines 500, 1100, and 1400) the device unit number is an integer variable, IUNIT. IUNIT has been given the value 1 (line 400) before it is used.

```
.R SOS  
  
FILE: WOE.FOR<CR>  
EXIT: WOE.FOR  
*FO:*<CR>  
00100  C THIS PROGRAM ENTERS STUDENT GRADES  
00200  C ENTER GRADE OF -1 AFTER LAST STUDENT GRADE TO END  
00300          DIMENSION STUDNT (8)  
00400          IUNIT=1  
00500          OPEN (UNIT=IUNIT, FILE='STDGRA.DES')  
00600  40      ACCEPT 10, (STUDNT(I),I=1,8)  
00700  10      FORMAT (8A5)
```

## EXAMPLES

```
00800      ACCEPT 20, IGRADE
00900  20      FORMAT (I3)
01000      IF (IGRADE .EQ. -1) GO TO 100
01100      WRITE (IUNIT, 30) (STUDNT(I),I=1,8), IGRADE
01200  30      FORMAT (8A5, I3)
01300      GO TO 40
01400  100     CLOSE (UNIT=IUNIT, FILE='STDGRA.DES')
01500      STOP 'THIS IS THE END'
01600      END
*
```

After this program has been executed, the file STDGRA.DES will be listed by the DIRECT command (see page INTRO 6-1) and during the KJOB command (see page INTRO 7-1).

```
,EX WOE,FOR<CR>
FORTRAN: WOE
MAIN.
LINK: LOADING
[LNKXCT WOE EXECUTION]
GEORGE CLINTON<CR>
83<CR>
ELBRIIDGE GERRY<CR>
73<CR>
DANIEL D. TOMPKINS<CR>
58<CR>
JOHN CALHOUN<CR>
80<CR>
RICHARD M. JOHNSON<CR>
79<CR>
GEORGE DALLAS<CR>
95<CR>
WILLIAM R. KING<CR>
69<CR>
JOHN BRECKINRIDGE<CR>
77<CR>
HANNIBAL HAMLIN<CR>
65<CR>
SCHUYLER COLFAX<CR>
77<CR>
HENRY WILSON<CR>
77<CR>
WILLIAM WHEELER<CR>
96<CR>
CHESTER ARTHUR<CR>
88<CR>
LEVI F. MORTON<CR>
91<CR>
GARRET HOBART<CR>
89<CR>
CHARLES DAWES<CR>
93<CR>
CHARLES CURTIS<CR>
75<CR>
<CR>
-1<CR>
THIS IS THE END

END OF EXECUTION
CPU TIME: 0.92  ELAPSED TIME: 4:21.33
EXIT
```

\*

## EXAMPLES

### Example 4:

This program prepares grade reports for the students whose grades are recorded on the disk file STDGRA.DES.

```
.TYPE REPORT,FOR<CR>
00100  C PROGRAM TO PREPARE GRADE REPORT
00200      DIMENSION ANAME(8)
00300      OPEN (UNIT=1, FILE='STDGRA.DES')
00400  C PRINT HEADINGS
00500      WRITE (5, 10)
00600  10      FORMAT ('0', 5X, 'STUDENT', 27X, 'GRADE')
00700  30      READ (1, 20, END=50) (ANAME(I),I=1,8), IGRADE
00800  20      FORMAT (8A5, I3)
00900      WRITE (5, 40) (ANAME(I),I=1,8), IGRADE
01000  40      FORMAT (' ', 8A5, I3)
01100      GO TO 30
01200  50      CLOSE (UNIT=1), FILE='STDGRA.DES')
01300      STOP '    END OF GRADE REPORT'
01400      END
```

.EX REPORT,FOR<CR>

```
FORTRAN: REPORT
MAIN.
LINK:  LOADING
CLNKXCT REPORT EXECUTION]
```

STUDENT	GRADE
GEORGE CLINTON	83
ELBRIDGE GERRY	73
DANIEL D. TOMPKINS	58
JOHN CALHOUN	80
RICHARD M. JOHNSON	79
GEORGE DALLAS	95
WILLIAM R. KING	69
JOHN BRECKINRIDGE	77
HANNIBAL HAMLIN	65
SCHUYLER COLFAX	77
HENRY WILSON	77
WILLIAM WHEELER	96
CHESTER ARTHUR	88
LEVI P. MORTON	91
GARRET HOBART	89
CHARLES DAWES	93
CHARLES CURTIS	75

END OF GRADE REPORT

END OF EXECUTION

CPU TIME: 0.68 ELAPSED TIME: 1:34.77

EXIT

\*

## EXAMPLES

### Example 5 (Trying To Read A Non-Existent File):

Now DELETE the data file containing the students' grades, STDGRA.DES, and then Execute REPORT.FOR (the program in Example 4). The READ statement in line 700 cannot be executed since the file to which it refers does not exist. The execution is thus aborted.

```
.DELETE STDGRA.DES<CR>
FILES DELETED:
STDGRA.DES
01 BLOCKS FREED

.EX REPORT.FOR<CR>
LINK:    LOADING
[LNKXCT REPORT EXECUTION]

      STUDENT                      GRADE
ZFRSDAT ATTEMPT TO READ BEYOND VALID INPUT
UNIT=1 DSK:STDGRA.DES[2,240]<055>/ACCESS=SEQINOU/MODE=ASCII

NAME      (LOC)    <<---- CALLER (LOC)    <#ARGS> [ARG TYPES]
IN.       (402703) <<---- MAIN.+11(220)  <#5>     CUIUIU

? JOB ABORTED

END OF EXECUTION
CPU TIME: 0.35  ELAPSED TIME: 1.22
EXIT
```

PART II  
FORTRAN-10 Language Manual

The FORTRAN-10 Language Manual reflects the software as of Version 5 of the FORTRAN-10 Compiler, Version 5 of the FORTRAN-10 Object Time System (FOROTS), and Version 5 of the FORTRAN-10 Debugging Program (FORDDT).



## CONTENTS

		Page
CHAPTER	1	PROLOGUE
	1.1	BACKGROUND
CHAPTER	2	CHARACTERS AND LINES
	2.1	CHARACTER SET
	2.2	STATEMENT, DEFINITION, AND FORMAT
	2.2.1	Statement Label Field and Statement Numbers
	2.2.2	Line Continuation Field
	2.2.3	Statement Field
	2.2.4	Remarks
	2.3	LINE TYPES
	2.3.1	Initial and Continuation Line Types
	2.3.2	Multi-Statement Lines
	2.3.3	Comment Lines and Remarks
	2.3.4	Debug Lines
	2.3.5	Blank Lines
	2.3.6	Line-Sequenced Input
	2.4	ORDERING OF FORTRAN-10 STATEMENTS
CHAPTER	3	DATA TYPES, CONSTANTS, SYMBOLIC NAMES, VARIABLES, AND ARRAYS
	3.1	DATA TYPES
	3.2	CONSTANTS
	3.2.1	Integer Constants
	3.2.2	Real Constants
	3.2.3	Double-Precision Constants
	3.2.4	Complex Constants
	3.2.5	Octal Constants
	3.2.6	Logical Constants
	3.2.7	Literal Constants
	3.2.8	Statement Label Constants
	3.3	SYMBOLIC NAMES
	3.4	VARIABLES
	3.5	ARRAYS
	3.5.1	Array Element Subscripts
	3.5.2	Dimensioning Arrays
	3.5.3	Order of Stored Array Elements
CHAPTER	4	EXPRESSIONS
	4.1	ARITHMETIC EXPRESSIONS
	4.1.1	Rules for Writing Arithmetic Expressions
	4.2	LOGICAL EXPRESSIONS
	4.2.1	Relational Expressions
	4.3	EVALUATION OF EXPRESSIONS
	4.3.1	Parenthesized Subexpressions
	4.3.2	Hierarchy of Operators
	4.3.3	Mixed Mode Expressions

CONTENTS (CONT.)

		Page	
	4.3.4	Use of Logical Operands in Mixed Mode Expressions	4-11
CHAPTER	5	COMPILE CONTROL STATEMENTS	5-1
	5.1	INTRODUCTION	5-1
	5.2	PROGRAM STATEMENT	5-1
	5.3	INCLUDE STATEMENT	5-1
	5.4	END STATEMENT	5-1
CHAPTER	6	SPECIFICATION STATEMENTS	6-1
	6.1	INTRODUCTION	6-1
	6.2	DIMENSION STATEMENT	6-1
	6.2.1	Adjustable Dimensions	6-2
	6.3	TYPE SPECIFICATION STATEMENTS	6-3
	6.4	IMPLICIT STATEMENTS	6-5
	6.5	COMMON STATEMENTS	6-5
	6.5.1	Dimensioning Arrays in COMMON Statements	6-7
	6.6	EQUIVALENCE STATEMENT	6-7
	6.7	EXTERNAL STATEMENT	6-8
	6.8	PARAMETER STATEMENT	6-9
CHAPTER	7	DATA STATEMENT	7-1
	7.1	INTRODUCTION	7-1
CHAPTER	8	ASSIGNMENT STATEMENTS	8-1
	8.1	INTRODUCTION	8-1
	8.2	ARITHMETIC ASSIGNMENT STATEMENTS	8-1
	8.3	LOGICAL ASSIGNMENT STATEMENTS	8-4
	8.4	ASSIGN (STATEMENT LABEL) ASSIGNMENT STATEMENT	8-4
CHAPTER	9	CONTROL STATEMENTS	9-1
	9.1	INTRODUCTION	9-1
	9.2	GO TO CONTROL STATEMENTS	9-1
	9.2.1	Unconditional GO TO Statements	9-1
	9.2.2	Computed GO TO Statements	9-2
	9.2.3	Assigned GO TO Statements	9-2
	9.3	IF STATEMENTS	9-3
	9.3.1	Arithmetic IF Statements	9-3
	9.3.2	Logical IF Statements	9-4
	9.3.3	Logical Two-Branch IF Statements	9-4
	9.4	DO STATEMENT	9-5
	9.4.1	Nested DO Statements	9-6
	9.4.2	Extended Range	9-8
	9.4.3	Permitted Transfer Operations	9-9
	9.5	CONTINUE STATEMENT	9-10
	9.6	STOP STATEMENT	9-10
	9.7	PAUSE STATEMENT	9-11
	9.7.1	T (TRACE) Option	9-12
CHAPTER	10	I/O STATEMENTS	10-1
	10.1	DATA TRANSFER OPERATIONS	10-1
	10.2	TRANSFER MODES	10-1
	10.2.1	Sequential Mode	10-1
	10.2.2	Random Access Mode	10-1

CONTENTS (CONT.)

		Page
10.2.3	Append Mode	10-2
10.3	I/O STATEMENTS, BASIC FORMATS AND COMPONENTS	10-2
10.3.1	I/O Statement Keywords	10-3
10.3.2	FORTRAN-10 Logical Unit Numbers	10-3
10.3.3	FORMAT Statement References	10-3
10.3.4	I/O List	10-6
10.3.4.1	Implied DO Constructs	10-6
10.3.5	The Specification of Records for Random Access	10-7
10.3.6	List-Directed I/O	10-8
10.3.7	NAMELIST I/O Lists	10-10
10.4	OPTIONAL READ/WRITE ERROR EXIT AND END-OF-FILE ARGUMENTS	10-10
10.5	READ STATEMENTS	10-11
10.5.1	Sequential Formatted READ Transfers	10-11
10.5.2	Sequential Unformatted Binary READ Transfers	10-12
10.5.3	Sequential List-Directed READ Transfers	10-12
10.5.4	Sequential NAMELIST-Controlled READ Transfers	10-13
10.5.5	Random Access Formatted READ Transfers	10-13
10.5.6	Random Access Unformatted READ Transfers	10-13
10.6	SUMMARY OF READ STATEMENTS	10-14
10.7	REREAD STATEMENT	10-14
10.8	WRITE STATEMENTS	10-16
10.8.1	Sequential Formatted WRITE Transfers	10-16
10.8.2	Sequential Unformatted WRITE Transfer	10-16
10.8.3	Sequential List-Directed WRITE Transfers	10-17
10.8.4	Sequential NAMELIST-Controlled WRITE Transfers	10-17
10.8.5	Random Access Formatted WRITE Transfers	10-17
10.8.6	Random Access Unformatted WRITE Transfers	10-17
10.9	SUMMARY OF WRITE STATEMENTS	10-18
10.10	ACCEPT STATEMENT	10-18
10.10.1	Formatted ACCEPT Transfers	10-18
10.10.2	ACCEPT Transfers Into FORMAT Statement	10-19
10.11	PRINT STATEMENT	10-19
10.12	PUNCH STATEMENT	10-20
10.13	TYPE STATEMENT	10-21
10.14	FIND STATEMENT	10-21
10.15	ENCODE AND DECODE STATEMENTS	10-22
10.15.1	ENCODE Statement	10-23
10.15.2	DECODE Statement	10-23
10.15.3	Example of ENCODE/DECODE Operations	10-23
10.16	SUMMARY OF I/O STATEMENTS	10-25
 CHAPTER	 11	
	NAMELIST STATEMENTS	11-1
11.1	INTRODUCTION	11-1
11.2	NAMELIST STATEMENT	11-1
11.2.1	NAMELIST-Controlled Input Transfers	11-2
11.2.2	NAMELIST-Controlled Output Transfers	11-3

## CONTENTS (CONT.)

		Page	
CHAPTER	12	FILE CONTROL STATEMENTS	12-1
	12.1	INTRODUCTION	12-1
	12.2	OPEN AND CLOSE STATEMENTS	12-1
	12.2.1	Options for OPEN and CLOSE Statements	12-2
	12.2.2	Summary of OPEN/CLOSE Statement Options	12-10
CHAPTER	13	FORMAT STATEMENT	13-1
	13.1	INTRODUCTION	13-1
	13.1.1	FORMAT Statement, General Form	13-1
	13.2	FORMAT DESCRIPTORS	13-2
	13.2.1	Numeric Field Descriptors	13-4
	13.2.2	Interaction of Field Descriptors With I/O List Variables	13-6
	13.2.3	G, General Numeric Conversion Code	13-7
	13.2.4	Numeric Fields with Scale Factors	13-7
	13.2.5	Logical Field Descriptors	13-10
	13.2.6	Variable Numeric Field Widths	13-10
	13.2.7	Alphanumeric Field Descriptors	13-11
	13.2.8	Transferring Alphanumeric Data	13-12
	13.2.9	Mixed Numeric and Alphanumeric Fields	13-14
	13.2.10	Multiple Record Specifications	13-14
	13.2.11	Record Formatting Field Descriptors	13-15
	13.2.12	\$ Format Descriptor	13-16
	13.3	CARRIAGE CONTROL CHARACTERS FOR PRINTING ASCII RECORDS	13-16
CHAPTER	14	DEVICE CONTROL STATEMENTS	14-1
	14.1	INTRODUCTION	14-1
	14.2	REWIND STATEMENT	14-1
	14.3	UNLOAD STATEMENT	14-2
	14.4	BACKSPACE STATEMENT	14-2
	14.5	END FILE STATEMENT	14-2
	14.6	SKIP RECORD STATEMENT	14-3
	14.7	SKIP FILE STATEMENT	14-3
	14.8	BACKFILE STATEMENT	14-3
	14.9	SUMMARY OF DEVICE CONTROL STATEMENTS	14-3
CHAPTER	15	SUBPROGRAM STATEMENTS	15-1
	15.1	INTRODUCTION	15-1
	15.1.1	Dummy and Actual Arguments	15-1
	15.2	STATEMENT FUNCTIONS	15-3
	15.3	INTRINSIC FUNCTIONS (FORTRAN-10 DEFINED FUNCTIONS)	15-3
	15.4	EXTERNAL FUNCTIONS	15-7
	15.4.1	Basic External Functions (FORTRAN-10 Defined Functions)	15-8
	15.4.2	Generic Function Names	15-8
	15.5	SUBROUTINE SUBPROGRAMS	15-9
	15.5.1	Referencing Subroutines (CALL Statement)	15-13
	15.5.2	FORTRAN-10 Supplied Subroutines	15-14
	15.6	RETURN STATEMENT AND MULTIPLE RETURNS	15-14
	15.6.1	Referencing External FUNCTION Subprograms	15-16
	15.7	MULTIPLE SUBPROGRAM ENTRY POINTS (ENTRY STATEMENT)	15-17

CONTENTS (CONT.)			
			Page
CHAPTER	16	BLOCK DATA SUBPROGRAMS	16-1
	16.1	INTRODUCTION	16-1
	16.2	BLOCK DATA STATEMENT	16-1
APPENDIX	A	ASCII-1968 CHARACTER CODE SET	A-1
APPENDIX	B	USING THE COMPILER	B-1
	B.1	RUNNING THE COMPILER	B-1
	B.1.1	Switches Available with FORTRAN-10	B-1
	B.1.1.1	The /DEBUG Switch	B-3
	B.1.2	COMPIL-Class Commands	B-4
	B.2	READING A FORTRAN-10 LISTING	B-5
	B.2.1	Compiler-Generated Variables	B-6
	B.3	ERROR REPORTING	B-17
	B.3.1	Fatal Errors and Warning Messages	B-17
	B.3.2	Message Summary	B-18
	B.4	CREATING A REENTRANT FORTRAN PROGRAM WITH LINK-10	B-18
APPENDIX	C	WRITING USER PROGRAMS	C-1
	C.1	GENERAL PROGRAMMING CONSIDERATIONS	C-1
	C.1.1	Accuracy and Range of Double-Precision Numbers	C-1
	C.1.2	Writing FORTRAN-10 Programs for Execution on Non-DEC Machines	C-1
	C.1.3	Using Floating-Point DO Loops	C-2
	C.1.4	Computation of DO Loop Iterations	C-2
	C.1.5	Subroutines - Programming Considerations	C-2
	C.1.6	Reordering of Computations	C-3
	C.1.7	Dimensioning of Formal Arrays	C-4
	C.2	FORTRAN-10 GLOBAL OPTIMIZATION	C-4
	C.2.1	Optimization Techniques	C-5
	C.2.1.1	Elimination of Redundant Computations	C-5
	C.2.1.2	Reduction of Operator Strength	C-5
	C.2.1.3	Removal of Constant Computation From Loops	C-6
	C.2.1.4	Constant Folding and Propagation	C-7
	C.2.1.5	Removal of Inaccessible Code	C-7
	C.2.1.6	Global Register Allocation	C-7
	C.2.1.7	I/O Optimization	C-8
	C.2.1.8	Uninitialized Variable Detection	C-8
	C.2.1.9	Test Replacement	C-8
	C.2.2	Improper Function References	C-8
	C.2.3	Programming Techniques for Effective Optimization	C-9
	C.3	INTERACTING WITH NON-FORTAN-10 PROGRAMS AND FILES	C-9
	C.3.1	Calling Sequences	C-9
	C.3.2	Accumulator Usage	C-10
	C.3.3	Argument Lists	C-11
	C.3.4	Argument Types	C-12
	C.3.5	Description of Arguments	C-13
	C.3.6	Converting Existing MACRO-10 Libraries for use with FORTRAN-10	C-14
	C.3.7	Mixing FORTRAN-10 and F40 Compiled Programs	C-20
	C.3.8	Interaction with COBOL-10	C-20
	C.3.8.1	Calling FORTRAN-10 Subroutines from COBOL-10 Programs	C-21

CONTENTS (CONT.)

		Page
C.3.8.2	Calling COBOL-10 Subroutines from FORTRAN-10 Programs	C-22
C.3.9	LINK-10 Overlay Facilities	C-22
C.3.9.1	Conventions	C-23
C.3.10	FOROTS/FORSE Compatibility	C-23
C.3.10.1	FORTRAN-10/F40 Data File Compatibility	C-23
C.3.10.2	Converting FOROTS Data File to FORSE-Acceptable Form	C-25
C.3.10.3	General Restrictions	C-27
<b>APPENDIX D</b>	<b>FOROTS</b>	<b>D-1</b>
D.1	HARDWARE AND SOFTWARE REQUIREMENTS	D-1
D.2	FEATURES OF FOROTS	D-2
D.3	ERROR PROCESSING	D-3
D.4	INPUT/OUTPUT FACILITIES	D-3
D.4.1	Input/Output Channels Used Internally by FOROTS	D-3
D.4.2	File Access Modes	D-4
D.4.2.1	Sequential Transfer Mode	D-4
D.4.2.2	Random Access Mode	D-4
D.5	ACCEPTABLE TYPES OF DATA FILES AND THEIR FORMATS	D-4
D.5.1	ASCII Data Files	D-4
D.5.2	FORTRAN Binary Data Files	D-5
D.5.2.1	Format of Binary Files	D-5
D.5.3	Mixed Mode Data Files	D-12
D.5.4	Image Files	D-13
D.6	USING FOROTS	D-13
D.6.1	FOROTS Entry Points	D-14
D.6.2	Calling Sequences	D-14
D.6.3	MACRO Calls for FOROTS Functions	D-15
D.6.3.1	Formatted/Unformatted Transfer Statements, Sequential Access Calling Sequences	D-16
D.6.3.2	NAMELIST I/O Sequential Access Calling Sequences	D-17
D.6.3.3	Array Offsets and Factoring	D-18
D.6.3.4	I/O Statements Random Access Calling Sequences	D-20
D.6.3.5	Calling Sequences for Statements Which Use Default Devices	D-20
D.6.3.6	Statements to Position Magnetic Tape Units	D-22
D.6.3.7	List Directed Input/Output Statements	D-22
D.6.3.8	Input/Output Data Lists	D-23
D.6.3.9	OPEN and CLOSE Statements, Calling Sequences	D-26
D.6.3.10	Memory Allocation Routines	D-27
D.6.3.11	Software Channel Allocation and De-allocation Routines	D-28
D.7	FUNCTIONS TO FACILITATE OVERLAYS	D-29
D.8	LOGICAL/PHYSICAL DEVICE ASSIGNMENTS	D-32
<b>APPENDIX E</b>	<b>FORDDT</b>	<b>E-1</b>
E.1	INPUT FORMAT	E-2
E.1.1	Variables and Arrays	E-2
E.1.2	Numeric Conventions	E-3

CONTENTS (CONT.)

		Page
E.1.3	Statement Labels and Source Line Numbers	E-3
E.2	NEW USER TUTORIAL	E-3
E.2.1	Basic Commands	E-3
E.3	FORDDT AND THE FORTRAN-10 /DEBUG SWITCH	E-7
E.4	LOADING AND STARTING FORDDT	E-7
E.5	SCOPE OF NAME AND LABEL REFERENCES	E-8
E.6	FORDDT COMMANDS	E-8
E.7	ENVIRONMENT CONTROL	E-17
E.8	FORTRAN-10 /OPTIMIZE SWITCH	E-17
E.9	FORDDT MESSAGES	E-17
<b>APPENDIX F</b>	<b>COMPILER MESSAGES</b>	<b>F-1</b>
<b>APPENDIX G</b>	<b>FORTRAN-10 REALTIME SOFTWARE</b>	<b>G-1</b>
G.1	INTRODUCTION	G-1
G.2	USING FORRTF	G-2
G.2.1	Core	G-2
G.2.2	Modes	G-2
G.2.3	Priority Interrupt Levels	G-2
G.2.4	Masks	G-3
G.3	SUBROUTINES	G-3
G.3.1	LOCK	G-3
G.3.2	RTINIT	G-3
G.3.3	CONECT	G-4
G.3.4	RTSTRT	G-4
G.3.5	BLKRW	G-5
G.3.6	RTREAD	G-5
G.3.7	RTWRIT	G-5
G.3.8	STATO	G-5
G.3.9	STATI	G-5
G.3.10	RTSLP	G-6
G.3.11	RTWAKE	G-6
G.3.12	DISMIS	G-6
G.3.13	DISCON	G-6
G.3.14	UNLOCK	G-6
G.3.15	GETCOR, A Temporary Subroutine	G-7
<b>APPENDIX H</b>	<b>FOROTS ERROR MESSAGES RETURNED BY ERRSNS</b>	<b>H-1</b>

TABLES

<b>TABLE</b>	<b>1-1</b>	<b>FORTRAN-10 Statement Categories</b>	<b>1-2</b>
	2-1	FORTRAN-10 Character Set	2-1
	3-1	Constants	3-1
	3-2	Use of Symbolic Names	3-6
	4-1	Arithmetic Operations and Operators	4-1
	4-2	Type of the Result Obtained From Mixed Mode Operations	4-3
	4-3	Permitted Base/Exponent Type Combinations	4-4
	4-4	Logical Operators	4-5
	4-5	Logical Operations, Truth Table	4-6
	4-6	Relational Operators and Operations	4-7
	4-7	Hierarchy of FORTRAN-10 Operators	4-10
	8-1	Rules for Conversion in Mixed Mode Assignments	8-2
	10-1	FORTRAN-10 Logical Device Assignments	10-4
	10-2	Summary of READ Statements	10-25

CONTENTS (CONT.)

	Page
10-3              Summary of WRITE Statements	10-17
10-4              Summary of FORTRAN-10 I/O Statements	10-24
12-1              OPEN/CLOSE Statement Arguments	12-11
13-1              FORTRAN-10 Conversion Codes	13-3
13-2              Action of Field Descriptors On Sample Data	13-5
13-3              Numeric Field Codes	13-6
13-4              Descriptor Conversion of Real and Double Precision Data According to Magnitude	13-8
13-5              FORTRAN-10 Print Control Characters	13-17
14-1              Summary of FORTRAN-10 Device Control Statements	14-4
15-1              Intrinsic Functions (FORTRAN-10 Defined Functions)	15-4
15-2              Basic External Functions (FORTRAN-10 Defined Functions)	15-10
15-3              FORTRAN-10 Library Subroutines	15-19
B-1              FORTRAN-10 Compiler Switches	B-2
B-2              Modifiers to /DEBUG Switch	B-3
C-1              Argument Types and Type Codes	C-12
C-2              Upward Compatibility (FORSE TO FOROTS)	C-24
C-3              Downward Compatibility (FOROTS TO FORSE)	C-26
D-1              Function Numbers and Function Codes	D-30
D-2              FORTRAN Device Table	D-33
E-1              Table of Commands	E-1
G-1              Error Messages, Code Format and Full Message Format	G-7
H-1              FOROTS I/O Error Messages and ERRSNS Returned Values	H-2
H-2              FOROTS Arithmetic and Library Error Messages	H-5

## CHAPTER 1

### PROLOGUE

#### 1.1 BACKGROUND

The FORTRAN-10 language set is compatible with and encompasses the standard set described in "American National Standard FORTRAN, X3.9-1966" (referred to as the 1966 ANSI standard). FORTRAN-10 also provides many extensions and additions to the standard set that greatly enhance the usefulness of FORTRAN-10 and increase its compatibility with FORTRAN language sets implemented by other major computer manufacturers. In this manual, the FORTRAN-10 extensions and additions to the 1966 ANSI standard set are printed with gray shading.

A FORTRAN-10 source program consists of a set of statements constructed using the language elements and the syntax described in this manual. A given FORTRAN-10 statement will perform any one of the following functions:

1. It will cause operations such as multiplication, division, and branching to be carried out.
2. It will specify the type and format of the data being processed.
3. It will specify the characteristics of the source program.

FORTRAN-10 statements are composed of keywords, i.e., words that are recognized by the compiler, used with elements of the language set: constants, variable, and expressions. There are two basic types of FORTRAN-10 statements: executable and nonexecutable.

Executable statements specify the action of the program; nonexecutable statements describe the characteristics and arrangement of data, editing information, statement functions, and the kind of subprograms that may be included in the program. The compilation of executable statements results in the creation of executable code in the object program. Nonexecutable statements provide information only to the compiler; they do not create executable code.

In this manual, the FORTRAN-10 statements are grouped into 12 categories, each of which is described in a separate chapter. The name, definition, and chapter reference for each statement category are given in Table 1-1.

The basic FORTRAN-10 language elements, (constants, variables, and expressions), the character set from which they may be formed, and the rules that govern their construction and use are described in Chapters 2 through 4.

## PROLOGUE

Table 1-1  
FORTRAN-10 Statement Categories

Chapter Reference	Category Name	Description
5	Compilation Control Statements	Statements in this category identify programs and indicate their beginning and ending points.
6	Specification Statements	Statements in this category declare the properties of variables, arrays, and functions.
7	DATA Statement	This statement assigns initial values to variables and array elements.
8	Assignment Statements	Statements in this category cause named variables and/or array elements to be replaced by specified (assigned) values.
9	Control Statements	Statements in this category determine the order of execution of the object program and terminate its execution.
10	Input/Output Statements	Statements in this category transfer data between internal storage and a specified input or output medium.
11	NAMELIST Statement	This statement establishes lists that are used with certain input/output statements to transfer data that appears in a special type of record.
12	File Control Statements	Statements in this category identify, open, and close files and parameters for input and output operations between files and the processor.
13	FORMAT Statement	This statement is used with certain input/output statements to specify the form in which data appears in a FORTRAN record on a specified input/output medium.
14	Device Control Statements	Statements in this category enable the programmer to control the positioning of records or files on certain peripheral devices.

## PROLOGUE

Table 1-1 (Cont.)  
FORTRAN-10 Statement Categories

Chapter Reference	Category Name	Description
15	Subprogram Statements	Statements in this category enable the programmer to define functions and subroutines and their entry points.
16	BLOCK DATA Statements	Statements in this category are used to declare data specification subprograms that may initialize common storage areas.



## CHAPTER 2

### CHARACTERS AND LINES

#### 2.1 CHARACTER SET

Table 2-1 lists the digits, letters, and symbols recognized by FORTRAN-10. The remainder of the ASCII-1968 character set(1), is acceptable within literal constants or comment text, but these characters cause fatal errors in other contexts. An exception is CONTROL-Z, which, when used in Teletype input, means end-of-file.

#### NOTE

Lower-case alphabet characters are treated as upper-case outside the context of Hollerith constants, literal strings, and comments.

Table 2-1  
FORTRAN-10 Character Set

Letters		
A,a	J,j	S,s
B,b	K,k	T,t
C,c	L,l	U,u
D,d	M,m	V,v
E,e	N,n	W,w
F,f	O,o	X,x
G,g	P,p	Y,y
H,h	Q,q	Z,z
I,i	R,r	
Digits		
0		5
1		6
2		7
3		8
4		9

---

1. The complete ASCII-1968 character set is defined in the X3.4-1968 version of the "American National Standard for Information Interchange," and is given in Appendix A.

## CHARACTERS AND LINES


**Table 2-1 (Cont.)**  
**FORTRAN-10 Character Set**

Symbols	
! Exclamation Point " Quotation Marks # Number Sign \$ Dollar Sign & Ampersand ' Apostrophe ( Opening Parenthesis ) Closing Parenthesis * Asterisk + Plus	, Comma - Hyphen (Minus) . Period (Decimal Point) / Slant (slash) : Colon ; Semicolon < Less Than = Equals > Greater Than ^ Circumflex
Line Termination Characters	
Line Feed Form Feed Vertical Tab	
Line Formatting Characters	
Carriage Return Horizontal Tab Blank	

Note that horizontal tabs normally advance the character position pointer to the next position that is an even multiple of 8. An exception to this is the initial tab, which is defined as a tab that includes or starts in character position 6. (Refer to Section 2.3.1 for a description of initial and continuation line types.) Tabs within literal specifications count as one character even though they may advance the character position as many as eight places.

### 2.2 STATEMENT, DEFINITION, AND FORMAT

Source program statements are divided into physical lines. A line is defined as a string of adjacent character positions, terminated by the first occurrence of a line termination character regardless of context. Each line is divided into four fields:



## CHARACTERS AND LINES

### 2.2.1 Statement Label Field and Statement Numbers

You may place a number ranging from 1 to 99999 in the statement label field of an initial line to identify the statement. Any source program statement that is referenced by another statement must have a statement number. Leading zeroes and all blanks in the label field are ignored, e.g., the numbers 00105 and 105 are both accepted as statement number 105. You may assign the statement numbers in a source program in any order; however, each statement number must be unique with respect to all other statements in the program or subprogram. You cannot label non-executable statements other than FORMAT and END statements.

A main program and a subroutine may contain identical statement numbers. In this case, references to these numbers are understood to mean the numbers in the same program unit in which the reference is made. An example:

Assume that main module MAINMD and subprogram SUB1 both contain statement number 105. A GO TO statement, for instance, in MAINMD will refer to statement 105 in MAINMD, NOT to 105 in SUB1. A GO TO in SUB1 will transfer control to 105 in SUB1.

When you enter source programs into a DECsystem-10 system via a standard user terminal, you may use an initial tab to skip all or part of the label field.

If an initial tab is encountered during compilation, FORTRAN-10 examines the character immediately following the tab to determine the type of line being entered. If the character following the tab is one of the digits 1 through 9, FORTRAN-10 considers the line as a continuation line and the second character after the tab as the first character of the statement field. If the character following the tab is other than one of the digits 1 through 9, FORTRAN-10 considers the line to be an initial line and the character following the tab is considered to be the first character of the statement field. The character following the initial tab is considered to be in character position 6 in a continuation line, and in character position 7 in an initial line.

### 2.2.2 Line Continuation Field

Any alphanumeric character (except a blank or a zero) placed in this field (position 6) identifies the line as a continuation line. (See Section 2.3.1 for description.)

Whenever you use a tab to skip all or part of the label field of a continuation line, the next character you enter must be one of the digits 1 through 9 to identify the line as a continuation line.

### 2.2.3 Statement Field

Any FORTRAN-10 statement may appear in this field. Blanks (spaces) and tabs do not affect compilation of the statement and may be used freely in this field for appearance purposes, with the exception of textual data given within either a literal or Hollerith specification where blanks and tabs are significant characters.

#### 2.2.4 Remarks

In lines consisting of 73 or more character positions, only the first 72 characters are interpreted by FORTRAN-10. (Note that tabs generally occupy more than one character position, usually advancing the counter to the next character position that is an even multiple of eight.) All other characters in the line (character positions 73, 74 ...etc.) are treated as remarks and do not affect compilation.

Note that remarks may also be added to a line in character positions 7 through 72, provided the text of the remark is preceded by the symbol "!" (Refer to Section 2.3.3.)

### 2.3 LINE TYPES

A line in a FORTRAN-10 source program may be:

1. An initial line,
2. A continuation line,
3. A multi-statement line,
4. A comment line,
5. A debug line, or
6. A blank line.

Each of these line types is described in the following paragraphs.

#### 2.3.1 Initial and Continuation Line Types

A FORTRAN-10 statement may occupy the statement fields of up to 20 consecutive lines. The first line in a multi-line statement group is referred to as the initial line; the succeeding lines are referred to as continuation lines.

Initial lines may be assigned a statement number and must have either a blank or a zero in their continuation line field, i.e., character position 6.

If you enter an initial line via a keyboard input device, you may use an initial tab to skip all or part of the label field. If you use an initial tab for this purpose, you must immediately follow it with a non-numeric character, i.e., the first character of the statement field must be non-numeric.

Continuation lines cannot be assigned statement numbers; they are identified by any alphanumeric character (except for a blank or zero) placed in character position 6 of the line, i.e., continuation line field. The label field of a continuation line is treated as remark text.

If you are entering a continuation line via a keyboard, you may use an initial tab to skip all or part of the label field; however, the tab must be followed immediately by a numeric character other than zero. The tab-numeric combination identifies the line as a continuation line.

## CHARACTERS AND LINES

Note that blank lines, comments, and debug lines that are treated like comments, i.e., debug lines that are not compiled with the rest of the program (refer to Section 2.3.4) terminate a continuation sequence.

Following is an example of a 4-line FORTRAN-10 FORMAT statement using initial tabs:

```
105      FORMAT (1H1,17HINITIAL CHARGE = ,F10.6,10H COULOMB,6X,  
           213HRESISTANCE = ,F9.3,6H OHM/15H CAPACITANCE = ,F10.6,  
           38H FARAD,11X,13HINDUCTANCE = ,F7.3,8H HENRY///  
           421H TIME          CURRENT/7H          MS,10X.2HMA///)
```

Continuation Line Characters, i.e., 2, 3, and 4

### 2.3.2 Multi-Statement Lines

You may write more than one FORTRAN-10 statement in the statement field of one line. The rules for structuring a multi-statement line are:

1. Successive statements must be separated by a semicolon (;).
2. Only the first statement in the series can have a statement number.
3. Statements following the first statement cannot be a continuation of the preceding statement.
4. The last statement in a line may be continued to the next line if that next line is made a continuation line.

An example of a multi-statement line is:

```
450      DIST=RATE * TIME ;TIME=TIME+0.05 ;CALL PRIME(TIME,DIST)
```

### 2.3.3 Comment Lines and Remarks

Lines that contain descriptive text only are referred to as comment lines. Comment lines are commonly used to identify and introduce a source program, to describe the purpose of a particular set of statements, and to introduce subprograms.

To structure a comment line:

1. You must place one of the characters C (or c), \$,/,\*, or ! in character position 1 of the line to identify it as a comment line.
2. You may write the text into character positions 2 through the end of the line.
3. You may place comment lines anywhere in the source program, but they cannot precede a continuation line because comments terminate a continuation sequence.
4. You may write a large comment as a sequence of any number of lines; however, each line must carry the identifying character (C,\$,/,\*, or !) in its first character position.

## CHARACTERS AND LINES

The following is an example of a comment that occupies more than one line.

```
CSUBROUTINE - A12
CTHE PURPOSE OF THIS SUBROUTINE IS
CTO FORMAT AND STORE THE RESULTS OF
CTEST PROGRAM HEAT TEST-1101
```

Comment lines are printed on all listings, but are otherwise ignored by the compiler.

You may add a remark to any statement field, in character positions 7 through 72, provided the symbol ! precedes the text. For example, in the line

```
IF(N.EQ.0)STOP! STOP IF CARD IS BLANK
```

the character group "Stop if card is blank" is identified as a remark by the preceding ! symbol. Remarks do not result in the generation of object program code, but they will appear on listings. The symbol !, indicating a remark, must appear outside the context of a literal specification.

Note that characters appearing in character positions 73 and beyond are automatically treated as remarks, so that the symbol ! need not be used. (Refer to Section 2.2.4.)

### 2.3.4 Debug Lines

As an aid in program debugging, a D (or d) in character position 1 of any line causes the line to be interpreted as a comment line, i.e., not compiled with the rest of the program unless the /INCLUDE switch is present in the command string. (Refer to Appendix C for a description of the file switch options.) When the /INCLUDE switch is present in the command string, the D (or d) in character position 1 is treated as a blank so that the remainder of the line is compiled as an ordinary (noncomment) line. Note that the initial and all continuation lines of a debug statement must contain a D (or d) in character position 1.

### 2.3.5 Blank Lines

You may insert lines consisting of only blanks, tabs, or no characters anywhere in a FORTRAN-10 source program except immediately preceding a continuation line, because blank lines are by definition initial lines and as such terminate a continuation sequence. Blank lines are used for formatting purposes only; they cause blank lines to appear in their corresponding positions in source program listings; otherwise, they are ignored by the compiler.


### 2.3.6 Line-Sequence Input

FORTRAN-10 optionally accepts DECsystem-10 line-sequenced files as produced by LINED or BASIC. These sequence numbers are used in place of the listing line numbers normally generated by FORTRAN-10.

## CHARACTERS AND LINES

### 2.4 ORDERING OF FORTRAN-10 STATEMENTS

The order in which you place FORTRAN-10 Statements in a program unit is important. That is, certain types of statements have to be processed before others to guarantee that compilation takes place as you expect. The proper sequence for FORTRAN-10 statements is summarized by the following diagram.



Horizontal lines indicate the order in which FORTRAN-10 statements must appear. That is, you cannot intersperse horizontal sections. For example, all PARAMETER statements must appear after all IMPLICIT statements and before any DATA statements, i.e., PARAMETER, IMPLICIT, and DATA statements cannot be interspersed. Statement function definitions must appear after IMPLICIT statements and before executable statements.

Vertical lines indicate the way in which certain types of statements may be interspersed. For example, you may intersperse DATA statements with statement function definitions and executable statements. You may intersperse FORMAT statements with IMPLICIT statements, parameter statements, other specification statements, DATA statements, statement function definitions, and executable statements. The only restriction on the placement of FORMAT statements is that they must appear after any PROGRAM, FUNCTION, subprogram, and BLOCK DATA statements, and before the END statement.

## CHARACTERS AND LINES

### Special Cases:

1. The placement of an INCLUDE statement is dictated by the types of statements to be INCLUDED.
2. The ENTRY statement is allowed only in functions or subroutines. All executable references to any of the dummy parameters must physically follow the ENTRY statement unless the references appear in the function definition statement, the subroutine, or in a preceding ENTRY statement.
3. BLOCK DATA subprograms cannot contain any executable statements, statement functions, FORMAT statements, EXTERNAL statements, or NAMELIST statements. (Refer to Section 16.1.)

When statements are out of place, FORTRAN-10 issues messages, some of which may indicate fatal errors.

## CHAPTER 3

### DATA TYPES, CONSTANTS, SYMBOLIC NAMES, VARIABLES, AND ARRAYS

#### 3.1 DATA TYPES

The data types you may use in FORTRAN-10 source programs are:

1. integer,
2. real,
3. double-precision,
4. complex,
5. octal,
6. double-octal,
7. literal,
8. statement label, and
9. logical.

The use and format of each of the foregoing data types are discussed in the descriptions of the constant having the same data type (Sections 3.2.1 through 3.2.8).

#### 3.2 CONSTANTS

Constants are quantities that do not change value during the execution of the object program.

The constants you may use in FORTRAN-10 are listed in Table 3-1.

Table 3-1  
Constants

Category	Constant(s) Types
Numeric	Integer, real, double-precision, complex, and octal
Truth Values	Logical
Literal Data	Literal
Statement Label	Address of FORTRAN statement label

### 3.2.1 Integer Constants

An integer constant is a string of from one to eleven digits that represents a whole decimal number (a number without a fractional part). Integer constants must be within the range of  $(-2^{**35})-1$  to  $(+2^{**35})-1$  (-34359738367 to +34359738367). Positive integer constants may optionally be signed; negative integer constants must be signed. You cannot use decimal points, commas, or other symbols on integer constants (except for a preceding sign, + or -). Examples of valid integer constants are:

```
345
+345
-345
```

Examples of invalid integer constants are:

```
+345. (use of decimal point)
3,450 (use of comma)
34.5 (use of decimal point; not a whole number)
```

### 3.2.2 Real Constants

A real constant may have any of the following forms:

1. A basic real constant: a string of decimal digits followed immediately by a decimal point followed optionally by a decimal fraction, e.g., 1557.42.
2. A basic real constant followed immediately by a decimal integer exponent written in E notation (exponential notation) form, e.g., 1559.E2.
3. An integer constant (no decimal point) followed by a decimal integer exponent written in E notation, e.g., 1559E2.

Real constants may be of any size; however, each will be rounded to fit the precision of 27 bits (7 to 9 decimal digits).

Precision for real constants is maintained to approximately eight significant digits; the absolute precision depends upon the numbers involved.

The exponent field of a real constant written in E notation form cannot be empty (blank); it must be either a zero or an integer constant. The magnitude of the exponent must be greater than -38 and equal to or less than +38 (i.e.,  $-38 \leq n \leq +38$ ). The following are examples of valid real constants.

```
-98.765
7.0E+0 (7.)
.7E-3 (.0007)
5E+5 (500000.)
50115.
50.E1 (500.)
```

The following are examples of invalid real constants.

```
72.6E75 (exponent is too large)
.375E (exponent incorrectly written)
500 (no decimal point given)
```

### 3.2.3 Double-Precision Constants

Constants of this type are similar to real constants written in E notation form; the direct differences between these two constants are:

1. Double-precision constants, depending on their magnitude, have precision to either 15 to 17 places (system with a KA10 Processor) or 16 to 18 places (system with a KI10 or KL10 Processor), rather than the 8-digit precision obtained for real constants.
2. Each double-precision constant occupies two storage locations.
3. The letter D, instead of E, is used in double-precision constants to identify a decimal exponent.

You must use both the letter D and an exponent (even of zero) in writing a double-precision constant. The exponent need only be signed if it is negative; its magnitude must be greater than -38 and equal to or less than +38 (i.e.,  $-38 \leq n \leq +38$ ). The range of magnitude permitted a double-precision constant depends on the type of processor present in your system (on which the source program is to be compiled and run). The permitted ranges are:

Processor	Range
KA10	$1.97 \times 10^{(-31)}$ to $3.4 \times 10^{(+38)}$
KI10 or KL10	$0.14 \times 10^{(-38)}$ to $3.4 \times 10^{(+38)}$

The following are valid examples of double-precision constants.

```

7.9D03      (= 7900)
7.9D+03     (= 7900)
7.9D-3       (= .0079)
79D03       (= 79000)
79D0         (= 79)

```

The following are invalid examples of double-precision constants.

```

7.9D99      (exponent is too large)
7.9E5       ("E" denotes a single-precision constant)

```

### 3.2.4 Complex Constants

You can represent a complex constant by an ordered pair of integer, real, or octal constants written within parentheses and separated by a comma. For example, (.70712, -.70712) and (8.763E3, 2.297) are complex constants.

In a complex constant the first (leftmost) real constant of the pair represents the real part of the number; the second real constant represents the imaginary part of the number. Both the real and imaginary parts of a complex constant can be signed.

The real constants that represent the real and imaginary parts of a complex constant occupy two consecutive storage locations in the object program.

**3.2.5 Octal Constants**

You may use octal numbers (radix 8) as constants in arithmetic expressions, logical expressions, and data statements. Octal numbers up to 12 digits in length are considered standard octal constants; they are stored right-justified in one processor storage location. When necessary, standard octal constants are padded with leading zeros to fill their storage location.

If you specify more than 12 digits in an octal number, it is considered a double octal constant. Double octal constants occupy two storage locations and may contain up to 24 right-justified octal digits; zeros are added to fill any unused digits.

If you assign a single octal constant to a double precision or complex variable, it is stored, right-justified, in the high-order word of the variable. The low-order portion of the variable is set to zero.

If you assign a double octal constant to a double precision or complex variable, it is stored right-justified starting in the low-order (rightmost) word and precedes leftwards into the high-order word.

All octal constants must:

1. be preceded by a double quote ("') to identify the digits as octal, e.g., "777, and
2. be signed if negative, but optionally signed if positive.
3. contain one or more of the digits 0 through 7, but not 8 or 9.

The following are examples of valid octal constants:

```
"123456700007
"123456700007
+"12345
-"7777
"-7777
```

The following are examples of invalid octal constants:

```
"12368      (contains an 8)
7777       (no identifying double quotes)
```

When you use an octal constant as an operand in an expression, its form (bit pattern) is not converted to accommodate it to the type of any other operand. For example, the subexpression (A+"202 400 000 000) has as its result the sum of A with the floating point number 2.0; while the subexpression (I+"202 400 000 000) has as its result the sum of I with a large integer.

Octal constants may not be used as stand-alone arguments for library functions that require non-octal arguments. MIN0, for instance, requires INTEGER arguments and cannot accept octal arguments.

When you combine a double octal constant in an expression with either an integer or real variable, only the contents of the high order location (leftmost) are used.

## DATA TYPES, CONSTANTS, SYMBOLIC NAMES, VARIABLES, AND ARRAYS

### 3.2.6 Logical Constants

The Boolean values of truth and falsehood are represented in FORTRAN-10 source programs as the logical constants .TRUE. and .FALSE.. Always write logical constants enclosed by periods as in the preceding sentence.

Logical quantities may be operated on in arithmetic and logical statements. Only the sign bit of a numeric used in a logical IF statement is tested to determine if it is true (sign is negative) or false (sign is positive).

### 3.2.7 Literal Constants

A literal constant may be either of the following:

1. A string of alphanumeric and/or special characters contained within apostrophes, e.g., 'TEST#5'.
2. A Hollerith literal, which is written as a string of alphanumeric and/or special characters preceded by nH (e.g., nHstring). In the prefix nH, the letter n represents a number that specifies the exact number of characters (including blanks) that follow the letter H; the letter H identifies the literal as a Hollerith literal. The following are examples of Hollerith literals:

```
2HAB  
14HLOAD TEST #124  
6H#124-A
```

#### NOTE

A tab ( $\rightarrow$ ) in a Hollerith literal is counted as one character, e.g., 3H $\rightarrow$  AB.

You may enter literal constants into DATA statements as a string of:

1. up to ten 7-bit ASCII characters for complex or double precision type variables, and
2. up to five 7-bit ASCII characters for all other type variables.

The 7-bit ASCII characters that comprise a literal constant are stored left-justified (starting in the high-order word of a 2-word precision or complex literal) with blanks placed in empty character positions. Literal constants that occupy more than one variable are stored as successive variables in the list. The following example illustrates how the string of characters

#### A LITERAL OF MANY CHARACTERS

is stored in a six-element array called A.

```
DIMENSION A(6)  
DATA A/'A LITERAL OF MANY CHARACTERS'/
```

## DATA TYPES, CONSTANTS, SYMBOLIC NAMES, VARIABLES, AND ARRAYS

```
A(1) is set to 'A LIT'  
A(2) is set to 'ERAL '  
A(3) is set to 'OF MA'  
A(4) is set to 'NY CH'  
A(5) is set to 'ARACT'  
A(6) is set to 'ERS '
```

### 3.2.8 Statement Label Constants

Statement labels are numeric identifiers that represent program statement numbers.

You write statement label constants as strings of from one to five decimal digits, which are preceded by either a dollar sign (\$) or an ampersand (&). For example, either \$11992 or &11992 may be used as a statement label constant.

You use statement label constants only in the argument list of CALL statements to identify the statement to return to in a multiple RETURN statement. (Refer to Chapter 15.)

### 3.3 SYMBOLIC NAMES

Symbolic names may consist of any alphanumeric combination of from one to six characters. You may use more than six characters, but FORTRAN-10 will ignore all but the first six. The first character of a symbolic name must be an alphabetic character.

The following are examples of legal symbolic names:

```
AL2345  
IAMBIC  
ABLE
```

The following are examples of illegal symbolic names:

```
#AMBIC (symbol used as first character)  
1AB (number used as first character)
```

You use symbolic names to identify specific items of a FORTRAN-10 source program; Table 3-2 lists these items, together with an example of a symbolic name and text reference for each.

Table 3-2  
Use of Symbolic Names

Symbolic Names Can Identify	For Example	For a Detailed Description See Section
1. Variables 2. Arrays 3. Array elements 4. Functions 5. Subroutines 6. External library functions 7. COMMON block names	PI, CONST, LIMIT TAX TAX (NAME, INCOME) MYFUNC, VALFUN CALCSB, SUB2, LOOKUP SIN, ATAN, COSH  DATAR, COMDAT	3.4 3.5 3.5.1 15.2 15.5 15.4  6.5

3.4 VARIABLES

A variable is a datum (storage location) that is identified by a symbolic name and is not a constant, an array or an array element. Variables specify values that are assigned to them by either arithmetic statements (Chapter 8), DATA statements (Chapter 7), or at run time via I/O references (Chapter 10). Before you assign a value to a variable, it is termed an undefined variable, and you should not reference it except to assign a value to it.

If you reference an undefined variable, an unknown value (garbage) will be obtained.

The value you assign to a variable may be either a constant or the result of a calculation that is performed during the execution of the object program. For example, the statement  $IAB=5$  assigns the constant 5 to the variable IAB; in the statement  $IAB=5+B$ , however, the value of IAB at a given time will depend on the value of variable B at the time the statement was last executed.

The type of a variable is the type of the contents of the datum that it identifies. Variables may be:

1. integer
2. real
3. logical
4. double-precision, or
5. complex.

You may declare the type of a variable by using either implicit or explicit type declaration statements (Chapter 6). However, if you do not use type declaration statements, FORTRAN-10 assumes the following convention:

1. Variable names that begin with the letters I, J, K, L, M, or N are normally integer variables.
2. Variable names that begin with any letter other than I, J, K, L, M, or N are normally real variables.

Examples of determining the type of a variable according to the foregoing convention are given in the following table:

Variable	Beginning Letter	Assumed Data Type
ITEMP	I	Integer
OTEMP	O	Real
KA123	K	Integer
AABLE	A	Real

3.5 ARRAYS

An array is an ordered set of data identified by an array name. Array names are symbolic names and must conform to the rules given in Section 3.3 for writing symbolic names.

## DATA TYPES, CONSTANTS, SYMBOLIC NAMES, VARIABLES, AND ARRAYS

Each datum within an array is called an array element. As with variables, you may assign a value to an array element. Before you assign a value to an array element it is considered to be undefined; you should not reference it until you have assigned it a value. If you reference an undefined array element, the value of the element will be unknown and unpredictable (garbage).

Name each element of an array by using the array name together with a subscript that describes the position of the element within the array.

### 3.5.1 Array Element Subscripts

Give the subscript of an array element identifier within parentheses, as either one subscript quantity or a set of subscript quantities delimited by commas. Write the parenthesized subscript immediately after the array name. The general form of an array element name is AN (S<sub>1</sub>, S<sub>2</sub>,...S<sub>n</sub>), where AN is the array name and S<sub>1</sub> through S<sub>n</sub> represent n number of subscript quantities. You may use any number of subscript quantities in an element name; however, the number used must always equal the number of dimensions (Section 3.5.2) specified for the array.

A subscript can be any compound expression (Chapter 4), for example:


1. Subscript quantities may contain arithmetic expressions that involve addition, subtraction, multiplication, division, and exponentiation. For example, (A+B,C<sup>5</sup>,D/2) and (A<sup>\*\*3</sup>,(B/4+C)<sup>\*</sup>E,3) are valid subscripts.
2. Arithmetic expressions used in array subscripts may be of any type, but noninteger expressions (including complex) are converted to integer when the subscript is evaluated.
3. A subscript may contain function references (Chapter 14). For example: TABLE (SIN (A) \*B,2,3) is a valid array element identifier.
4. Subscripts may contain array element identifiers nested to any level as subscripts. For example, in the subscript (I(J(K(L))),A+B,C) the first subscript quantity given is a nested 3-level subscript.

Here are examples of valid array element subscripts:

1. IAB(1,5,3)
2. ABLE(A)
3. TABLE1(10/C+K<sup>\*\*2</sup>,A,B)
4. MAT(A,AB(2\*L),.3\*TAB(A,M+1,D),55)

## 3.5.2 Dimensioning Arrays

You must declare the size (number of elements) of an array in order to enable FORTRAN-10 to reserve the needed amount of locations in which to store the array. Arrays are stored as a series of sequential storage locations. Arrays, however, are visualized and referenced as if they were single or multi-dimensional rectilinear matrices, dimensioned on a row, column, and plane basis. For example, the following figure represents a 3-row, 3-column, 2-plane array.



10-1058

You specify the size of an array by an array declarator written as a subscripted array name. In an array declarator, however, each subscript quantity is a dimension of the array and must be either an integer variable or an integer constant.

For example, TABLE(I,J,K) and MATRIX (10,7,3,4) are valid array declarators.

The total number of elements that comprise an array is the product of the dimension quantities given in its array declarator. For example, the array IAB dimensioned as IAB (2,3,4) has 24 elements ( $2 \times 3 \times 4 = 24$ ).

You use dimension arrays only in the specification statements DIMENSION, COMMON, and type declaration (Chapter 6). Subscripted array names appearing in any of the foregoing statements are array declarators; subscripted array names appearing in any other statements are always array element identifiers. In array declarators the position of a given subscript quantity determines the particular dimension of the array (e.g., row, column, or plane) that it represents. The first three subscript positions specify the number of rows, columns, and planes that comprise the named array; each following subscript given then specifies a set comprised of n-number (value of the subscript) of the previously defined sets. For example:

## DATA TYPES, CONSTANTS, SYMBOLIC NAMES, VARIABLES, AND ARRAYS

The Dimension Declarator	Specifies the Array(s)												
TAB (2)	<table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="padding: 2px 10px;">1</td><td style="padding: 2px 10px;">2</td></tr></table>	1	2										
1	2												
TAB (2,2)	<table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="padding: 2px 10px;">1,1</td><td style="padding: 2px 10px;">1,2</td></tr><tr><td style="padding: 2px 10px;">2,1</td><td style="padding: 2px 10px;">2,2</td></tr></table>	1,1	1,2	2,1	2,2								
1,1	1,2												
2,1	2,2												
TAB (2,2,2)	<table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="padding: 2px 10px;">1,1,1</td><td style="padding: 2px 10px;">1,2,1</td><td style="padding: 2px 10px;">1,1,2</td><td style="padding: 2px 10px;">1,2,2</td></tr><tr><td style="padding: 2px 10px;">2,1,1</td><td style="padding: 2px 10px;">2,2,1</td><td style="padding: 2px 10px;">2,1,2</td><td style="padding: 2px 10px;">2,2,2</td></tr></table>	1,1,1	1,2,1	1,1,2	1,2,2	2,1,1	2,2,1	2,1,2	2,2,2				
1,1,1	1,2,1	1,1,2	1,2,2										
2,1,1	2,2,1	2,1,2	2,2,2										
TAB (2,2,2,2)	<table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="padding: 2px 10px;">1,1,1,1</td><td style="padding: 2px 10px;">1,2,1,1</td><td style="padding: 2px 10px;">1,1,2,1</td><td style="padding: 2px 10px;">1,2,2,1</td><td style="padding: 2px 10px;">1,1,2,2</td><td style="padding: 2px 10px;">1,2,2,2</td></tr><tr><td style="padding: 2px 10px;">2,1,1,1</td><td style="padding: 2px 10px;">2,2,1,1</td><td style="padding: 2px 10px;">2,1,2,1</td><td style="padding: 2px 10px;">2,2,2,1</td><td style="padding: 2px 10px;">2,1,2,2</td><td style="padding: 2px 10px;">2,2,2,2</td></tr></table>	1,1,1,1	1,2,1,1	1,1,2,1	1,2,2,1	1,1,2,2	1,2,2,2	2,1,1,1	2,2,1,1	2,1,2,1	2,2,2,1	2,1,2,2	2,2,2,2
1,1,1,1	1,2,1,1	1,1,2,1	1,2,2,1	1,1,2,2	1,2,2,2								
2,1,1,1	2,2,1,1	2,1,2,1	2,2,2,1	2,1,2,2	2,2,2,2								

### NOTE


FORTRAN-10 permits any number of dimensions in an array declarator.

#### 3.5.3 Order of Stored Array Elements

The elements of an array are arranged in storage in ascending order. The value of the first subscript quantity varies between its minimum and maximum values most rapidly. The value of the last given subscript quantity increases to its maximum value least rapidly. For example, the elements of the array dimensioned as I(2,3) are stored in the following order:

I(1,1) I(2,1) I(1,2) (2,2) (1,3) (2,3)

In the following list, the elements of the three-dimensional array (B(3,3,3)) are stored row by row from left to right and from top to bottom.



Thus B(3,1,1) is stored before B(1,2,1), and so forth.

## CHAPTER 4

### EXPRESSIONS

#### 4.1 ARITHMETIC EXPRESSIONS

Arithmetic expressions may be either simple or compound. Simple arithmetic expressions consist of an operand that may be:

1. a constant
2. a variable
3. an array element
4. a function reference (see Chapter 14 for description), or
5. an arithmetic or logical expression written within parentheses.

Operands may be of integer, real, double precision, complex, octal, or literal type.

The following are valid examples of simple arithmetic expressions:

105	(integer constant)
IAB	(integer variable)
TABLE(3,4,5)	(array element)
SIN (X)	(function reference)
(A+B)	(a parenthetical expression)

A compound arithmetic expression consists of two or more operands combined by arithmetic operators. Table 4-1 lists the arithmetic operations permitted in FORTRAN-10 and the operator recognized for each.

Table 4-1  
Arithmetic Operations and Operators

Operation	Operator	Example
1. Exponentiation	** or ^	A**B or A^B
2. Multiplication	*	A*B
3. Division	/	A/B
4. Addition	+	A+B
5. Subtraction	-	A-B

## EXPRESSIONS

### 4.1.1 Rules for Writing Arithmetic Expressions

Observe the following rules in structuring compound arithmetic expressions:

1. The operands comprising a compound arithmetic expression may be of different types. Table 4-2 illustrates all permitted combinations of data types and the type assigned to the result of each.

#### NOTE

Only one combination of data types, double-precision with complex, is prohibited in FORTRAN-10.

2. An expression cannot contain two adjacent and unseparated operators. For example, the expression  $A^*/B$  is not permitted.
3. All operators must be included; no operation is implied. For example, the expression  $A(B)$  does not specify multiplication although this is implied in standard algebraic notation. The expression  $A^*(B)$  is required to obtain a multiplication of the elements.
4. When you use exponentiation, the base quantity and its exponent may be of different types. For example, the expression  $ABC^{**} 13$  involves a real base and an integer exponent. The permitted base/exponent type combinations and the type of the result of each combination are given in Table 4-3.

<b>Double Octal</b>	1. Type of operation used 2. Type associated with result 3. Conversion on Argument 1 4. Conversion on Argument 2	1. Integer 2. Integer 3. High order word is used directly; low order word is ignored. 4. None	1. Real 2. Real 3. High order word is used directly; low order word is ignored. 4. None	1. Double Precision 2. Double Precision 3. None 4. None	1. Complex 2. Complex 3. None 4. None	1. Integer 2. Octal 3. High order word is used directly; low order word is ignored. 4. None
<b>Literal</b>	1. Type of operation used 2. Type associated with result 3. Conversion on Argument 1 4. Conversion on Argument 2	1. Integer 2. Integer 3. High order word is used directly; further words are ignored. 4. None	1. Real 2. Real 3. High order word is used directly; further words are ignored. 4. None	1. Double Precision 2. Double Precision 3. First two words are used directly; further words are ignored. 4. None	1. Complex 2. Complex 3. First two words are used directly; further words are ignored. 4. None	1. Integer 2. Octal 3. High order word is used directly; further words are ignored. 4. None

## EXPRESSIONS

Table 4-3  
Permitted Base/Exponent Type Combinations

Base Operand	Exponent Operand			
	Integer	Real	Double Precision	Complex
Integer	Integer	Real	Double Precision	Complex
Real	Real	Real	Double Precision	Complex
Double Precision	Double Precision	Double Precision	Double Precision	Complex
Complex	Complex	Complex	(Undefined)	Complex

### 4.2 LOGICAL EXPRESSIONS

Logical expressions may be either simple or compound. Simple logical expressions consist of a logical operand, which may be a logical type:

1. constant
2. variable
3. array element
4. function reference (see Chapter 15), or
5. another expression written within parentheses.

Compound logical expressions consist of two or more operands combined by logical operators.

Table 4-4 gives the logical operators permitted by FORTRAN-10 and a description of the operation each provides.

## EXPRESSIONS

Table 4-4  
Logical Operators

Operator	Description
.AND.	AND operator. Both of the logical operands combined by this operator must be true to produce a true result.
.OR.	Inclusive OR operator. If either or both of the logical operands combined by .OR. are true, the result will be true.
.XOR.	Exclusive OR operator. If either but not both of the logical operands combined by .XOR. is true, the result will be true.
.EQV.	Equivalence operator. If the logical operands being combined by .EQV. are both the same (both are true or both are false), the result will be true.
.NOT.	Complementation operator. This operator is used as a prefix that specifies complementation (inversion) of the item (operand or expression) that it modifies. The original item, if true by itself, becomes false, and vice versa.

Write logical expressions in the general form P .OP. Q, where P and Q are logical operand and .OP. is any logical operator but ".NOT.". The .NOT. operator complements the value of a logical operand; you must write it immediately before the operand that it modifies, e.g., .NOT.P. Table 4-5 is a truth table illustrating all possible logical combinations of two logical operands (P and Q) and the resultant of each combination.

When an operand of a logical expression is double-precision or complex, only the high-order word of the operand is used in the specified logical operation.

The assignment of a .TRUE. or a .FALSE. value to a given operand is based only on the sign of the numeric representation of the operand.

## EXPRESSIONS

Table 4-5  
Logical Operations, Truth Table

When P is	And Q is:	Then the Expression:	Is:
True	-----	.NOT.P	False
False	-----	.NOT.P	True
True	True	P .AND. Q	True
True	False	P .AND. Q	False
False	True	P .AND. Q	False
False	False	P .AND. Q	False
True	True	P .OR. Q	True
True	False	P .OR. Q	True
False	True	P .OR. Q	True
False	False	P .OR. Q	False
True	True	P .XOR. Q	False
True	False	P .XOR. Q	True
False	True	P .XOR. Q	True
False	False	P .XOR. Q	False
True	True	P .EQV. Q	True
True	False	P .EQV. Q	False
False	True	P .EQV. Q	False
False	False	P .EQV. Q	True

### Examples

Assume the following variables:

Variable	Type
REAL, RUN	Real
I,J,K	Integer
DP,D	Double Precision
L, A, B	Logical
CPX,C	Complex

Examples of valid logical expressions consisting of the foregoing variables are:

```

L.AND.B
((REAL*I).XOR.(DP+K)
L.AND.A.OR..NOT.(I-K)

```

## EXPRESSIONS

Logical functions are performed on the full 36-bit binary processor representation of the operands involved. The result of a logical operation is found by performing the specified function, simultaneously, for each of the corresponding bits in each operand. For example, consider the expression A=C.OR.D, where C="456" and D="201". The operation performed by the processor and the result is:

Word	0	1	24	25	26	27	28	29	30	31	32	33	34	35
Bits	0	1	→	24	25	26	27	28	29	30	31	32	33	34
Operand C	0	0	→	0	0	0	1	0	0	1	0	1	1	1
Operand D	0	0	→	0	0	0	0	1	0	0	0	0	0	1
Result A	0	0	→	0	0	0	1	1	0	1	0	1	1	1

Table 4-5 also illustrates all possible logical combinations of two one-bit binary operands (P and Q) and gives the result of each combination. Just read 1 for true and 0 for false.

### 4.2.1 Relational Expressions

Relational expressions consist of two expressions combined by a relational operator. The relational operator permits the programmer to test, quantitatively, the relationship between two arithmetic expressions.

The result of a relational expression is always a logically true or false value.

In FORTRAN-10, you may write relational operators either as a 2-letter mnemonic enclosed within periods, e.g., .GT., or symbolically using the symbols, >, <, = and #. Table 4-6 lists both the mnemonic and symbolic forms of the FORTRAN-10 relational operators and specifies the type of quantitative test performed by each operator.

Table 4-6  
Relational Operators and Operations

Operators		Relation Tested
Mnemonic	Symbolic	
.GT.	>	Greater than
.GE.	>=	Greater than or equal to
.LT.	<	Less than
.LE.	<=	Less than or equal to
.EQ.	==	Equal to
.NE.	#	Not equal to

## EXPRESSIONS

Write relational expressions in the general form A(1) .OP.A(2), where A represents an arithmetic operand and .OP. is a relational operator.

You may mix arithmetic operands of type integer, real, and double precision in relational expressions.

You may compare complex operands using only the operators .EQ. (==) and .NE. (#). Complex quantities are equal if the corresponding parts of both words are equal.

### Examples

Assume the following variables:

Variables	Type
REAL, RON	Real
I,J,K	Integer
DP,D	Double Precision
L,A,B	Logical
CPX,C	Complex

Examples of valid relational expressions consisting of the foregoing variables are:

```
(REAL).GT.10  
I == 5  
C.EQ.CPX
```

Examples of invalid relational expressions consisting of the foregoing variables are:

```
(REAL).GT 10 (closing period missing from operator)
```

```
C>CPX      (complex operands can only be combined by .EQ. and  
             .NE. operators)
```

Examples of valid expressions that use both logical and relational operators to combine the foregoing variables are:

```
(I.GT. 10).AND.(J<=K)  
((I*RON)==(I/J)).OR.K  
(I.AND.K)##((REAL).OR.(RON))  
C##CPX.OR.RON
```

## EXPRESSIONS

### 4.3 EVALUATION OF EXPRESSIONS

The following determine the order of computation of a FORTRAN-10 expression:

1. the use of parentheses
2. an established hierarchy for the execution of arithmetic, relational, and logical operations and
3. the location of operators within an expression.

#### 4.3.1 Parenthetical Subexpressions

In an expression, all subexpressions written within parentheses are evaluated first. When parenthetical subexpressions are nested (one contained within another) the most deeply nested subexpression is evaluated first, the next most deeply nested subexpression is evaluated second, and so on, until the value of the final parenthetical expression is computed. When more than one operator is contained by a parenthetical subexpression, the required computations are performed according to the hierarchy assigned operators by FORTRAN-10 (Section 4.3.2).

Example:

The separate computations performed in evaluating the expression

$A+B/((A/B)+C)-C$  are:

1.  $R1=A/B$
2.  $R2=R1+C$
3.  $R3=B/R2$
4.  $R4=R3-C$
5.  $R5=A+R4$

WHERE: R1 THROUGH R5 REPRESENT THE INTERIM AND FINAL RESULTS OF THE COMPUTATIONS PERFORMED.

#### 4.3.2 Hierarchy of Operators

The following hierarchy (order of execution) is assigned to the classes of FORTRAN-10 operators:

first, arithmetic operators,  
second, relational operators, and  
third, logical operators.

## EXPRESSIONS

Table 4-7 specifies the precedence assigned to the individual operators of the foregoing classes.

With the exception of integer division and exponentiation, all operations on expressions or subexpressions involving operators of equal precedence are computed in any order that is algebraically correct.

A subexpression of a given expression may be computed in any order. For example, in the expression  $(F(X) + A*B)$ , the function reference may be computed either before or after  $A*B$ .

Table 4-7  
Hierarchy of FORTRAN-10 Operators

Class	Level	Symbol or Mnemonic
EXPONENTIAL	First	$^{**}$
ARITHMETIC	Second Third Fourth	$-(\text{unary minus})$ and $+(\text{unary plus})$ $*, /$ $+, -$
RELATIONAL	Fifth	$.GT., .GE., .LT., .LE., .EQ., .NE.$ or $>, >=, <, <=, ==, \#$
LOGICAL	Sixth Seventh Eighth Ninth	$.NOT.$ $.AND.$ $.OR.$ $.EQV., .XOR.$

Operations specifying integer division are evaluated from left to right. For example, the expression  $I/J*K$  is evaluated as if it had been written as  $(I/J)*K$ . But this left-to-right evaluation process can be overridden by parentheses.  $I/J*K$  (evaluated as  $(I/J)*K$ ) does not equal  $I/(J*K)$ , which is evaluated as written here.

When a series of exponentiation operations occurs in an expression, it is evaluated in order from right to left. For example, the expression  $A^{**2}^{**}B$  is evaluated in the following order:

```
first R1 =  $2^{**}B$  (intermediate result)
second R2 =  $A^{**}R1$  (final result).
```

Similarly, here too, parentheses alter the evaluation of the expression.  $(A^{**2})^{**}B$  is evaluated in these two steps:

```
first R1 =  $A^{**}2$  (intermediate result)
second R2 =  $R1^{**}2$  (final result)
```

### 4.3.3 Mixed Mode Expressions

Mixed mode expressions are evaluated on a subexpression-by-subexpression basis, with the type of the results obtained converted and combined with other results or terms according to the conversion procedures described in Table 4-2.

## EXPRESSIONS

### Example

Assume the following:

Variable	Type
D	Double-Precision
X	Real
I,J	Integer

The mixed mode expression  $D+X*(I/J)$  is evaluated in the following manner:

- 1.R1 = I/J      R1 is integer
- 2.R2 = X\*R1      R1 is converted to type real and is multiplied by X to produce R2
- 3.R3 = D+R2      R2 is converted to type double precision and is added to D to produce R3

where R1 and R2, and R3 represent the interim and final results respectively of the computations performed.

#### 4.3.4 Use of Logical Operands in Mixed Mode Expressions

When you use logical operands in mixed mode expressions, the value of the logical operand is not converted in any way to accommodate it to the type of the other operands in the expression. For example, in  $L*R$ , where L is type logical and R is type real, the expression is evaluated without converting L to type real.



## CHAPTER 5

### COMPILATION CONTROL STATEMENTS

#### 5.1 INTRODUCTION

You use compilation control statements to identify FORTRAN-10 programs and to specify their termination. Statements of this type do not affect either the operations performed by the object program or the manner in which the object program is executed. The three compilation control statements described in this chapter are: **PROGRAM statement**, **INCLUDE statement**, and **END statement**.

#### 5.2 PROGRAM STATEMENT

This statement allows you to give the main program a name other than the compiler-assumed name "MAIN." The general form of a PROGRAM statement is:

PROGRAM name

where:

name        is a symbolic name that begins with an alphabetic character and contains a maximum of six characters. (Refer to Section 3.3 for a description of symbolic names.)

The following rule governs the use of the PROGRAM statement:

The PROGRAM statement must be the first statement in a program unit. (Refer to Section 2.4 for a discussion of the ordering of FORTRAN-10 statements.)

#### 5.3 INCLUDE STATEMENT

This statement allows you to include code segments or predefined declarations in a program unit without having them reside in the same physical file as the primary program unit. The general form of the INCLUDE statement is

INCLUDE 'dev:filename.ext[proj,prog]/NOLIST'

where:

dev:        is a device name. When no device name is specified, DSK: is assumed.

## COMPILE CONTROL STATEMENTS

filename.ext is the filename and extension of the FORTRAN-10 statements that you wish to include. The name of the file is required; the extension is optional. If you specify "filename" only, .FOR is the assumed extension. If you specify the filename and period (filename.), the null extension is assumed. You may not specify wild (\*) information.

[proj,prog] is the project-programmer number. Your project-programmer number is assumed if none is specified. You cannot specify subdirectory information.

/NOLIST is an optional switch indicating that the included statements are not to be included in the compilation listing.

The following rules govern the use of the INCLUDE statement:

1. The INCLUDED file may contain any legal FORTRAN-10 statement except another INCLUDE statement, or a statement that terminates the current program unit, such as the END, PROGRAM, FUNCTION, SUBROUTINE, or BLOCK DATA statements.
2. The proper placement of the INCLUDE statement within a program unit depends upon the types of statements to be INCLUDED. (Refer to Section 2.4 for information on the ordering of FORTRAN-10 statements.)
3. The file(s) to be INCLUDED must be on disk.

Note that an asterisk (\*) is appended to the line numbers of the INCLUDED statements on the compilation listing, provided /NOLIST is not specified.

### 5.4 END STATEMENT

Use this statement to signal FORTRAN-10 that the physical end of a source program or subprogram has been reached. END is a nonexecutable statement. The general form of an END statement is:

END

The following rules govern the use of the END statement:

1. This statement must be the last physical statement of a source program or subprogram.
2. When used in a main program, the END statement implies a STOP statement operation; in a subprogram, END implies a RETURN statement operation.
3. You may label an END statement.

## CHAPTER 6

### SPECIFICATION STATEMENTS

#### 6.1 INTRODUCTION

Use specification statements to specify the type characteristics, storage allocations, and data arrangement. There are seven types of specification statements:

1. DIMENSION
2. Statements that explicitly specify type, such as REAL or INTEGER
3. IMPLICIT
4. COMMON
5. EQUIVALENCE
6. EXTERNAL
7. PARAMETER

Specification statements are nonexecutable and conform to the ordering guidelines described in Section 2.4.

#### 6.2 DIMENSION STATEMENT

DIMENSION statements provide FORTRAN-10 with information needed to identify and allocate the space required for source program arrays. You may specify any number of subscripted array names as array declarators in a DIMENSION statement. The general form of a DIMENSION statement is

DIMENSION S<sub>1</sub>, S<sub>2</sub>, ..., S<sub>n</sub>

where S<sub>i</sub> is an array declarator. Array declarators are names of the following form:

name(max,...,max)      or      name(min:max,...,min:max)

where name is the symbolic name of the array, and each min:max value represents the lower and upper bounds of an array dimension.

## SPECIFICATION STATEMENTS

Each min:max value for an array dimension may be either an integer constant or, if the array is a dummy argument to a subprogram, an integer variable. The value given the minimum specification for a dimension must not exceed the value given the maximum specification. Minimum values of 1 with their following colon delimiters may be omitted from a dimension subscript. This is because minimum values are assumed to be 1 in the first place.

### Examples

```
DIMENSION EDGE (-1:1,4:8), NET (5,10,4), TABLE (567)
DIMENSION TABLE (IAB:J,K,M,10:20)
```

(where IAB, J, K, and M are of type integer).

Note that you may use a slash in place of a colon as the delimiter between the upper and lower bounds of an array dimension.

### 6.2.1 Adjustable Dimensions

When used within a subprogram, an array declarator may use type integer parameters as dimension subscript quantities. The following rules govern the use of adjustable dimensions in a subprogram:

1. For single entry subprograms, the array name and each subscript variable must be given by the calling program as parameters when the subprogram is called. The subscript variables may also be in COMMON.
2. For multiple entry subprograms in which the array name is a parameter, any subscript variables may be passed. If all subscript variables are not passed or in COMMON, the value of the subscript as passed for a previous entry will be used.
3. The type of the array dimension variables cannot be altered within the program.
4. If the value of an array dimension variable is altered within the program, the dimensionality of the array will not be affected.
5. The original size of the array cannot exceed the array dimensions assigned within a subprogram, i.e., the size of an array is not dynamically expandable.

### Examples

```
SUBROUTINE SBR (ARRAY,M1,M2,M3,M4)
DIMENSION ARRAY (M1:M2,M3:M4)
DO 27 L=M3,M4
DO 27 K=M1,M2
ARRAY (K,L)=VALUE
27 CONTINUE
END

SUBROUTINE SBL (ARR1,M,N)
DIMENSION ARR1(M,N)
ARR1(M,N)=VALUE
ENTRY SB2(ARR1,M)
ENTRY SB3(ARR1,N)
ENTRY SB4(ARR1)
```

## SPECIFICATION STATEMENTS

In the foregoing example, the first call made to the subroutine must be made to SB1. Assuming that the call is made at SB1 with the values M=11 and N=13, any succeeding call to SB2 should give M a new value. If a succeeding call is made to SB4, the last values passed through entries SB1, SB2, or SB3 will be used for M and N.

Note that for the calling program of the form:

```
CALL SB1(A,11,13)
M=15
CALL SB3(A,13)
```

the value of M used in the dimensionality of the array for the execution of SB3 will be 11 (the last value passed).

### 6.3 TYPE SPECIFICATION STATEMENTS

Type specification statements declare explicitly the data type of variable, array, or function symbolic names. You may give an array name in a type statement either alone (unsubscripted) to declare the type of all its elements or in a subscripted form to specify both its type and dimensions.

Write type specification statements in the following form:

type list

where type may be any one of the following declarators:

1. INTEGER
2. REAL
3. DOUBLE PRECISION
4. COMPLEX
5. LOGICAL

#### NOTE

In order to be compatible with the type statements used by other manufacturers, the data type size modifier, \*n, is accepted by FORTRAN-10. You may append this size modifier to the declarators, causing some to elicit messages warning users of the form of the variable specified by FORTRAN-10:

## SPECIFICATION STATEMENTS

### Declarator      Form of Variable Specified

INTEGER*2	Full word integer with warning message
INTEGER*4	Full word integer
LOGICAL*1	Full word logical with warning message
LOGICAL*4	Full word logical
REAL*4	Full word real
REAL*8	Double-precision real
COMPLEX*8	Complex
COMPLEX*16	Complex with warning message

In addition, you may append the data type size modifier to individual variables, arrays, or function names. Its effect is to override, for the particular element, the size modifier (explicit or implicit) of the primary type. For example,

```
REAL*4 A, B*8, C*8(10), D
```

A and D are single-precision (one full word) real, and B and C are double-precision (two full words) real.

The list consists of any number of variable, array, or function names that are to be declared the specified type. The names listed must be separated by commas and can appear in only one type statement within a program unit.

### Examples

```
INTEGER A, B, TABLE, FUNC  
REAL R, M, ARRAY (5:10,10:20,5)
```

### NOTE

Variables, arrays, and functions of a source program, which are not typed either implicitly or explicitly by a specification statement, are typed by FORTRAN-10 according to the following conventions:

1. Variable names, array names, and function names that begin with the letters I, J, K, L, M, or N are type integer.
2. Variable names, array names, and function names that begin with any letter other than I, J, K, L, M, or N are type real.

If a name that is the same as a predefined FORTRAN-10 function name appears in a conflicting type statement, it is assumed that the name refers to a user-defined routine of the given type. If you place a generic predefined FORTRAN-10 function name in an explicit type statement, it loses its generic properties.

## SPECIFICATION STATEMENTS

### 6.4 IMPLICIT STATEMENTS

IMPLICIT statements declare the data type of variables and functions according to the first letter of each variable name. IMPLICIT statements are written in the following form:

IMPLICIT type (A1,A2,...,An), type (B1,B2,...,Bn),...,type.....

As shown in the foregoing form statement, an IMPLICIT statement consists of one or more type declarators separated by commas. Each type declarator has the form

type (A1,A2,...,An)

where type represents one of the declarators listed in Section 6.3, and the parenthetical list represents a list of different letters.

Each letter in a type declarator list specifies that each source program variable (not declared in an explicit type specification statement) starting with that letter is assigned the data type named in the declarator. For example, the IMPLICIT type declarator REAL (R,M,N,O) declares that all names that begin with the letters R, M, N, or O are type REAL names, unless declared otherwise in an explicit type statement.

#### NOTE

Type declarations given in an explicit type specification override those also given in an IMPLICIT statement. IMPLICIT declarations do not affect the FORTRAN-10 supplied functions.

You may specify a range of letters within the alphabet by writing the first and last letters of the desired range separated by a dash, e.g., A-E for A,B,C,D,E. For example, the statement IMPLICIT INTEGER (I,L-P) declares that all variables which begin with the letters I,L,M,N,O, and P are INTEGER variables.

You may use more than one IMPLICIT statement, but they must appear before any other declaration statement in the program unit. Refer to Section 2.4 for a discussion on ordering FORTRAN-10 statements.

### 6.5 COMMON STATEMENT

The COMMON statement enables you to establish storage that may be shared by two or more programs and/or subprograms and to name the variables and arrays that are to occupy the common storage. The use of common storage conserves storage and provides a means to implicitly transfer arguments between a calling program and a subprogram. Write COMMON statements in the following form:

COMMON/A1/V1,V2,...,Vn.../An/V1,V2,...,Vn

where the enclosed letters /A1/, ..., /An/ represent optional name constructs (referred to as common block names when used).

## SPECIFICATION STATEMENTS

The list (e.g., V1,V2...,Vn) appearing after each name construct lists the names of the variables and arrays that are to occupy the common area identified by the construct. The items specified for a common area are ordered within the storage area as they are listed in the COMMON statement.

Either label COMMON storage areas or leave them blank (unlabeled). If the common area is to be labeled, give a symbolic name within slashes immediately before the list of items that is to occupy the names area. For example, the statement

```
COMMON/AREA1/A,B,C/AREA2/TAB(13,3,3)
```

establishes two labeled common areas (i.e., AREA1 and AREA2). Common block names bear no relation to internal variables or arrays that have the same name.

If a common area is to be declared as unlabeled, give either nothing or two sequential slashes (//) immediately before the list of items that is to occupy blank common. For example, the statement

```
COMMON/AREA1/A,B,C//TAB(3,3,3)
```

establishes one labeled (AREA1) and one unlabeled common area. Unlabeled common area is also called "blank common".

A given labeled common name may appear more than once in the same COMMON statement and in more than one COMMON statement within the same program or subroutine.

Each labeled common area is treated as a separate, specific storage area. The contents of a common area, i.e., variables and arrays, may be assigned initial values by DATA statements in BLOCK DATA subprograms. Declarations of a given common area in different subprograms must contain the same number, size, and order of variables and arrays as the reference area.

Items to be placed in a blank common area may also be given in COMMON statements throughout the source program.

During compilation of a source program, FORTRAN-10 will string together all items listed for each labeled common area and for blank common areas in the order in which they appear in the source program statements. For example, the series of source program statements:

```
COMMON/ST1/A,B,C/ST2/TAB(2,2)//C,D,E  
.  
.COMMON/ST1/TST(3,4)//M,N  
.  
.COMMON/ST2/X,Y,Z//O,P,Q
```

has the same effect as the single statement

```
COMMON/ST1/A,B,C,TST(3,4)/ST2/TAB(2,2),X,Y,Z//C,D,E,M,N,O,P,Q
```

All items specified for blank common are placed into one area. Items within blank common are ordered as they are given throughout the source program. Common block names must be unique with respect to all subroutine, function, and entry point names.

The largest definition of a given common area must be loaded first.

## SPECIFICATION STATEMENTS

### 6.5.1 Dimensioning Arrays in COMMON Statements

Subscripted array names may be given in COMMON statements as array dimension declarators. However, variables cannot be used as subscript quantities in a declarator appearing in a COMMON statement; variable dimensioning is not permitted in COMMON.

Each array name given in a COMMON statement must be dimensioned either by the COMMON statement or by another dimensioning statement within the program or subprogram that contains the COMMON statement but not both.

Example

```
COMMON /A/B(100), C(10,10)
COMMON X(5,15),Y(5)
```

### 6.6 EQUIVALENCE STATEMENT

The EQUIVALENCE statement enables you to control the allocation of shared storage within a program or subprogram. This statement causes specific storage locations to be shared by two or more variables of either the same or different types. Write the EQUIVALENCE statement in the following form:

```
EQUIVALENCE(V1,V2,...,Vn),(W1,W2,...,Wn),(X1,X2,...,Xn)
```

where each parenthetical list contains the names of variables and array elements that are to share the same storage locations. For example, the statements

```
EQUIVALENCE (A,B,C)
EQUIVALENCE (LOC,SHARE(1))
```

specify that the variables named A, B, and C are to share the same storage location, and that the variable LOC and array element SHARE(1) are to share the same location.

The relationship of equivalence is transitive; for example, the two following statements have the same effect:

```
EQUIVALENCE (A,B),(B,C)
EQUIVALENCE (A,B,C)
```

When you use array elements in EQUIVALENCE statements, they must have either as many subscript quantities as dimensions of the array or only one subscript quantity. In either of the foregoing cases, the subscripts must be integer constants. Note that the single case treats the array as a one-dimensional array of the given type.

You may use the items given in an EQUIVALENCE list in both the EQUIVALENCE statement and in a COMMON statement providing the following rules are observed:

1. You cannot set two quantities declared in a COMMON statement to be equivalent to one another.

## SPECIFICATION STATEMENTS

2. Quantities placed in a common area by means of an EQUIVALENCE statement are permitted to extend the end of the common area forwards. For example, the statements

```
COMMON/R/X,Y,Z  
DIMENSION A(4)  
EQUIVALENCE (A,Y)
```

cause the common block R to extend from Z to A(4) arranged as follows:

```
X  
Y A(1) (shared location)  
Z A(2) (shared location)  
A(3)  
A(4)
```

3. You cannot use EQUIVALENCE statements that cause the start of a common block to be extended backwards. For example, the invalid sequence

```
COMMON/R/X,Y,Z  
DIMENSION A(4)  
EQUIVALENCE(X,A(3))
```

would require A(1) and A(2) to extend the starting location of block R in a backwards direction as illustrated by the following diagram:

```
↑ A(1)  
↑ A(2)  
X A(3)  
Y A(4)  
Z
```

### 6.7 EXTERNAL STATEMENT

Any subprogram name to be used as an argument to another subprogram must appear in an EXTERNAL statement in the calling subprogram. The EXTERNAL statement declares names to be subprogram names to distinguish them from other variable or array names. Write the EXTERNAL statement in the following form:

```
EXTERNAL namel,name2,...,namen
```

where each name listed is declared to be a subprogram name. If desired, these subprogram names may be FORTRAN-10 defined functions.

You may also use FORTRAN-10 defined function names for your subprograms by prefixing the names by an asterisk (\*) or an ampersand (&) within an EXTERNAL statement. For example,

```
EXTERNAL *SIN, &COS
```

## SPECIFICATION STATEMENTS

declares SIN and COS to be user subprograms. (If a prefixed name is not a FORTRAN-10 defined function, then the prefix is ignored.)

Note that specifying a predefined FORTRAN-10 function in an EXTERNAL statement without a prefix, i.e., EXTERNAL SIN, has no effect upon the usage of the function name outside of actual argument lists. If the name has generic properties, they are retained outside of the actual argument list. (The name has no generic properties within an argument list.)

The names declared in a program EXTERNAL statement are reserved throughout the compilation of the program and cannot be used in any other declarator statement, with the exception of a type statement.

### 6.8 PARAMETER STATEMENT

The PARAMETER statement allows you to define constants symbolically during compilation.

The general form of the PARAMETER Statement is as follows:

```
PARAMETER P1=C1,P2=C2,...
```

where

P<sub>i</sub> is a standard user-defined identifier (referred to in this section as a parameter name)

C<sub>i</sub> is any type of constant (including literals) except a label or complex constant. (Refer to Chapter 3 for a description of FORTRAN-10 constants.)

During compilation, the parameter names are replaced by their associated constants, provided the following rules are observed:

1. Place parameter names only within the statement field of an initial or continuation line type, i.e., not within a comment line or literal text.
2. Place parameter names only where FORTRAN-10 constants are acceptable.
3. Place parameter name references after the PARAMETER statement definition.
4. Use parameter names that are unique with respect to all other names in the program unit.
5. Do not redefine parameter names in subsequent PARAMETER statements.
6. Do not use parameter names as part of some larger syntactical construct (such as a Hollerith constant count or a data type size modifier).



## CHAPTER 7

### DATA STATEMENT

#### 7.1 INTRODUCTION

DATA statements are used to supply the initial values of variables, arrays, array elements, and labeled common.(1) Write DATA statements as follows:

```
DATA List1/Data1/,List2/Data2/,...,Listn/Datan/
```

where the List portion of each List/Data/ pair identifies a set of items to be initialized and the /Data/ portion contains the list of values to be assigned the items in the List. For example, the statement

```
DATA IA/5/,IB/10/,IC/15/
```

initializes variable IA to the value 5, variable IB to the value 10, and the variable IC to the value 15. The number of storage locations you specify in the list of variables must be less than or equal to the number of storage locations you specify in its associated list of values. If the list of variables is larger (specifies more storage locations) than its associated value list, a warning message is output. When the value list specifies more storage locations than the variable list, the excess values are ignored.

The List portion of each List/Data/ set may contain the names of one or more variables, array names, array elements, or labeled common variables. You may specify an entire array (unsubscripted array name) or a portion of an array in a DATA statement List as an implied DO loop construct. (See Paragraph 10.3.4.1 for a description of implied DO loops.) For example, the statement

```
DATA (NARY(I),I=1,5)/1,2,3,4,5/
```

initializes the first five elements of array NARY as NARY(1)=1, NARY(2)=2, NARY(3)=3, NARY(4)=4, NARY(5)=5.

When you use an implied DO loop in a DATA statement, the loop index variable must be of type INTEGER and the loop Initial, Terminal, and Increment parameters must also be of type INTEGER. In a DATA statement, references to an array element must be integer expressions in which all terms are either integer constants or indices of embracing implied DO loops. Integer expressions of the foregoing types cannot include the exponentiation operator.

The /Data/ portion of each List/Data/ set may contain one or more numeric, logical, literal, or octal constants and/or alphanumeric strings.

---

1. Refer to Paragraph 6.5 for a description of labeled common.

## DATA STATEMENT

You must identify octal constants by preceding them with a double quote ("") symbol, e.g., "777.

You may specify literal data as either a Hollerith specification, e.g., 5HABCDE, or a string enclosed in single quotes, e.g., 'ABCDE'. Each ASCII datum is stored left-justified and is padded with blanks up to the right boundary of the variable being initialized.

When you assign the same value to more than one item in List, a repeat specification may be used. Write the repeat specification as N\*D where N is an integer that specifies how many times the value of item D is to be used. For example, a /Data/ specification of /3\*20/ specifies that the value 20 is to be assigned to the first three items named in the preceding list. The statement

```
DATA M,N,L/3*20/
```

assigns the value 20 to the variables M, N, and L.

When the specified data type is not the same as that of the variable to which it is assigned, FORTRAN-10 converts the datum to the type of the variable. The type conversion is performed using the rules given for type conversion in arithmetic assignments. (Refer to Chapter 8, Table 8-1.) Octal, logical, and literal constants are not converted.

Sample Statement	Use
DATA PRINT,I,O/'TEST',30,"77/,(TAB(J),J=1,30)/30*5/	The first 30 elements of array TAB are initialized to 5.0.
DATA((A(I,J),I=1,5),J=1,6)/30*1.0/	No conversion required.
DATA((A(I,J),I=5,10),J=6,15)/60*2.0/	No conversion required.

When a literal string is specified that is longer than one variable can hold, the string will be stored left-justified across as many variables as are needed to hold it. If necessary, the last variable used will be padded with blanks up to its right boundary.

### Example

Assuming that X, Y, and Z are single-precision, the statement

```
DATA X,Y,Z/'ABCDEFGHIKL'/
```

will cause

X to be initialized to 'ABCDE'  
Y to be initialized to 'FGHIJ'  
Z to be initialized to 'KL' ~~PP~~

When a literal string is to be stored in double-precision and/or complex variables and the specified string is only one word long, the second word of the variable is padded with blanks.

DATA STATEMENT

Example

Assuming that the variable C is complex, the statement

```
DATA C/'ABCDE','FGHIJ'/
```

will cause the first word of C to be initialized to 'ABCDE' and its second word to be initialized to 'FFFF'. The string 'FGHIJ' is ignored.



## CHAPTER 8

### ASSIGNMENT STATEMENTS

#### 8.1 INTRODUCTION

Use assignment statements to assign a specific value to one or more program variables. There are three kinds of assignment statements:

1. Arithmetic assignment statements
2. Logical assignment statements
3. Statement Label assignment (ASSIGN) statements.

#### 8.2 ARITHMETIC ASSIGNMENT STATEMENT

You use statements of this type to assign specific numeric values to variables and/or array elements. Write arithmetic assignment statements in the form

v=e

where v is the name of the variable or array element that is to receive the specified value and e is a simple or compound arithmetic expression.

In assignment statements, the equal symbol (=) does not imply equality as it would in algebraic expressions; it implies replacement. For example, the expression v=e is correctly interpreted as "the current contents of the location identified as v are to be replaced by the final value of expression e; the current contents of v are lost."

When the type of the specified variable or array element name differs from that of its assigned value, FORTRAN-10 converts the value to the type of its assigned variable or array element. Table 8-1 describes the type conversion operations performed by FORTRAN-10 for each possible combination of variable and value types.

## ASSIGNMENT STATEMENTS

Table 8-1  
Rules for Conversion in Mixed Mode Assignments

Expression Type (e)	Variable Type (v)			
	Real	Integer	Complex	Double-Precision
REAL	D	C	R, I	H, L
INTEGER	C	D	R, C, I	H, C, L
COMPLEX	R	C, K	D	prohibited
DOUBLE-PRECISION	H	C, H, L	D	prohibited
LOGICAL	D	D	R, I	H, L
OCTAL	D	D	R, I	H, C, L
LITERAL	D, H%	C, H%	D&	D%
DOUBLE OCTAL*	H	H	D#	D

## ASSIGNMENT STATEMENTS

Table 8-1 (Cont.)  
Rules for Conversion in Mixed Mode Assignments

Legend	
D	Direct replacement
C	Conversion between integer and floating-point with truncation
R	Real part only
I	Set imaginary part to 0
H	High-order only
L	Set low-order part to 0
Notes	
*	Octal numbers with 13 to 24 digits are termed double octal. Double octals require two storage locations. They are stored right-justified and are padded with zeros to fill the locations.
&	Use the first two words of the literal. If the literal is only one word long, the second word is padded with blanks.
%	Use the first word of the literal.
#	To convert double octal numbers to complex, the low-order octal digits are assumed to be the imaginary part, and the high-order digits are assumed to be the real part of the complex value.

## ASSIGNMENT STATEMENTS

### 8.3 LOGICAL ASSIGNMENT STATEMENTS

Use this type of assignment statement to assign values to variables and array elements of type logical. Write the logical assignment statement in the form

v=e

where v is one or more variables and/or array element names, and e is a logical expression.

#### Examples

Assuming that the variables L, F, M, and G are of type logical, the following statements are valid:

#### Sample Statement

L=.TRUE.	The contents of L is replaced by logical truth.
F=.NOT.G	The contents of L is replaced by the logical complement of the contents of G.
M=A.GT.T or M=A>T	If A is greater than T, the contents of M is replaced by logical truth; if A is less than or equal to T, the contents of M is replaced by logical false. This can also be read: If A is greater than T, then M is true, otherwise, M is false.
L=((I.GT.H).AND.(J<=K))	The contents of L are replaced by either the true or false resultant of the expression.

### 8.4 ASSIGN (STATEMENT LABEL) ASSIGNMENT STATEMENT

Use the ASSIGN statement to assign a statement label constant, i.e., a 1- to 5-digit statement number, to a variable name. Write the ASSIGN statement in the form

ASSIGN n TO I

where n represents the statement number and I is a variable name. For example, the statement

ASSIGN 2000 TO LABEL

specifies that the variable LABEL represents the statement number 2000.

With the exception of complex and double-precision, you may use any type of variable in an ASSIGN statement.

Once a variable has been assigned a statement number, FORTRAN-10 will consider it a label variable. If a label variable is used in an arithmetic statement, the result will be unpredictable.

## ASSIGNMENT STATEMENTS

Use the ASSIGN statement in conjunction with assigned GO TO control statements (Chapter 9). The ASSIGN verb sets up statement label variables that are then referenced in subsequent GO TO control statements. The following sequence illustrates the use of the ASSIGN statement:

```
555 TAX=(A+B+C)*.05
.
.
.
ASSIGN 555 TO LABEL
.
.
.
GO TO LABEL
```



## CHAPTER 9

### CONTROL STATEMENTS

#### 9.1 INTRODUCTION

FORTRAN-10 object programs normally execute statement-by-statement in the order in which they were presented to the compiler. The following source program control statements, however, enable you to alter the normal sequence of statement execution:

1. GO TO
2. IF
3. DO
4. CONTINUE
5. STOP
6. PAUSE

#### 9.2 GO TO CONTROL STATEMENTS

There are three kinds of GO TO statements:

1. Unconditional
2. Computed
3. Assigned

A GO TO control statement causes the statement that it identifies to be executed next, regardless of its position within the program. The following paragraphs describe each type of GO TO statement.

##### 9.2.1 Unconditional GO TO Statements

Write GO TO statements of this type in the form

GO TO n

where n is the label, i.e., statement number, of an executable statement, e.g., GO TO 555. When executed, an unconditional GO TO statement transfers control of the program to the statement that it specifies.

## CONTROL STATEMENTS

You may position an unconditional GO TO statement anywhere in the source program except as the terminating statement of a DO loop.

### 9.2.2 Computed GO TO Statements

Write GO TO statements of this type in the form

```
GO TO (N1,N2,...,Nk)E
```

where the parenthesized list is a list of statement numbers and E is an arithmetic expression. You may include any number of statement numbers in the list of this type of GO TO statement; however, each number you give must be used as a label within the program or subprogram containing the GO TO statement.

#### NOTE

A comma may optionally follow the parenthesized list.

The value of the expression E must be reducible to an integer value that is greater than 0 and less than or equal to the number of statement numbers given in the statement list. If the value of the expression E does not compute within the foregoing range, the next statement is executed.

When a computed GO TO statement is executed, the value of its expression, i.e., E, is computed first. The value of E specifies the position within the given list of statement numbers of the number that identifies the statement to be executed next. For example, in the statement sequence

```
GO TO (20, 10, 5)K  
CALL XRANGE(K)
```

the variable K acts as a switch, causing a transfer to statement 20 if K=1, to statement 10 if K=2, or to statement 5 if K=3. The subprogram XRANGE is called if K is less than 1 or greater than 3.

### 9.2.3 Assigned GO TO Statements

Write GO TO statements of this type in either of the following forms:

```
GO TO K  
GO TO K,(L1,L2,...Ln)
```

where K is a variable name and the parenthesized list of the second form contains a list of statement labels, i.e., statement numbers. The statement numbers you give must be within the program or subprogram containing the GO TO statement.

Assigned GO TO statements of either foregoing form must be logically preceded by an ASSIGN statement that assigns a statement label to the variable name represented by K. The value of the assigned label variable must be in the same program unit as the GO TO statement in which it is used. In statements written in the form

```
GO TO K,(L1,L2,...Ln)
```

## CONTROL STATEMENTS

if K is not assigned one of the statement numbers given in the statement list, the next sequential statement is executed.

### Examples

```
GO TO STAT1  
GO TO STAT1,(177,207,777)
```

### 9.3 IF STATEMENTS

There are three kinds of IF statements: arithmetic, logical, and logical two-branch.

#### 9.3.1 Arithmetic IF Statements

Write IF statements of this type in the form

```
IF(E)L1,L2,L3
```

where (E) is an expression enclosed within parentheses and L1, L2, L3 are the labels, i.e., statement numbers, of three executable statements.

This type of IF statement transfers control of the program to one of the given statements according to the computed value of the given expressions. If the value of the expression is:

1. Less than 0, control is transferred to the statement identified by L1;
2. Equal to 0, control is transferred to the statement identified by L2;
3. Greater than 0, control is transferred to the statement identified by L3.

You must give all three statement numbers in arithmetic IF statements; the expression given may not compute to a complex value.

### Examples

#### Sample Statement

IF(ETA)4, 7, 12	Transfers control to statement 4 if ETA is negative, to statement 7 if ETA is 0, and to statement 12 if ETA is greater than 0.
IF(KAPPA-L(10))20, 14, 14	Transfers control to statement 20 if KAPPA is less than the 10th element of array L and to statement 14 if KAPPA is greater than or equal to the 10th element of array L.

## CONTROL STATEMENTS

### 9.3.2 Logical IF Statements

Write IF statements of this type in the form

IF(E) S

where E is any expression enclosed in parentheses and S is a complete executable statement.

Logical IF statements transfer control of the program either to the next sequential executable statement or the statement given in the IF statement, i.e., S, according to the computed logical value of the given expression. If the value of the given logical expression is true (negative), control is given to the executable statement within the IF statement. If the value of the expression is false (positive or zero), control is transferred to the next sequential executable program statement.

The statement you give in a logical IF statement may be any FORTRAN-10 executable statement except a DO statement or another logical IF statement.

#### Examples

##### Sample Statement

IF (T.OR.S) X=Y+1	Performs an arithmetic replacement operation if the result of IF is true.
IF (Z.GT.X(K)) CALL SWITCH(S,Y)	Performs a subroutine call if the result of IF is true.
IF (K.EQ.INDEX) GO TO 15	Performs an unconditional transfer if the result of IF is true.

### 9.3.3 Logical Two-Branch IF Statements

Write IF statements of this type in the form

IF (E) N1, N2

where E is any parenthetical expression, and N1 and N2 are statement labels defined within the program unit.

Logical two-branch IF statements transfer control of the program to either statement N1 or N2, depending on the computed value of the given expression. If the value of the given logical expression is true (negative), control is transferred to statement N1. If the value of the expression is false (positive or zero), control is transferred to statement N2.

Note that you must number the statement immediately following the logical two-branch IF so that control can later be transferred to the portion of code that was skipped.

## CONTROL STATEMENTS

### Examples


#### Sample Statement

IF (LOG1) 10,20	Transfers control to statement 10 if LOG1 is negative; otherwise transfers control to statement 20.
IF (A.LT.B.AND.A.LT.C) 31,32	Transfers control to statement 31 if A is less than both B and C; transfers control to statement 32 if A is greater than or equal to either B or C.

### 9.4 DO STATEMENT

DO statements simplify the coding of iterative procedures; write them in the following form:

#### Indexing Parameters



where

1. Terminal Statement Label N is the statement number of the last statement of the DO statement range. The range of a DO statement is defined as the series of statements that follows the DO statements up to and including its specified terminal statement.
2. Index Variable I is an unsubscripted variable whose value is defined at the start of the DO statement operations. The index variable is available for use throughout each execution of the range of the DO statement, but its value should not be altered within this range. It is also available for use in the program when:
  - a. control is transferred outside the range of the DO loop by a GO TO, arithmetic IF or RETURN statement located within the DO range,
  - b. a CALL is executed from within the DO statement range that uses the index variable as an argument, and
  - c. if an input-output statement with either or both the options END= or ERR= (Chapter 10) appears within the DO statement range.

## CONTROL STATEMENTS

3. Initial Parameter M1 assigns the index variable, I, its initial value. This parameter may be any variable, array element, or expression.
4. Terminal Parameter M2 provides the value that determines how many repetitions of the DO statement range are performed.
5. Increment Parameter M3 specifies the value to be added to the initial parameter (M1) on completion of each cycle of the DO loop. If M3 and its preceding comma are omitted, M3 is assumed to be equal to 1.

An indexing parameter may be any **arithmetic** expression resulting in either a positive or negative value. The values of the indexing parameters are calculated only once, at the start of each DO-loop operation. The number of times that a DO loop will execute is specified by the formula:

$$\text{MAX } ((M2-M1)/M3+1,1)$$

Since the count is computed at the start of a DO loop operation, changing the value of the loop index variable within the loop cannot affect the number of times that the loop is executed. At the start of a DO loop operation, the index value is set to the value of the initial parameter (M1), and a count variable (generated by the compiler) is set to the negative of the calculated count. At the end of each DO loop cycle, the value of the increment parameter (M3) is added to the index variable, and the count variable is incremented. If the number of specified iterations have not been performed, another cycle of the loop is initiated.

One execution of a DO loop range is always performed regardless of the initial values of the index variable and the indexing parameters.

Exit from a DO loop operation on completion of the number of iterations specified by the loop count is referred to as a normal exit. In a normal exit, control passes to the first executable statement after the DO loop range terminal statement, and the value of the DO statement index variable is considered undefined.

Exit from a DO loop may also be accomplished by a transfer of control by a statement within the DO loop range to a statement outside the range of the DO statement (Paragraph 9.4.3).

### 9.4.1 Nested DO Statements



One or more DO statements may be contained, i.e., nested, within the range of another DO statement. The following rules govern the nesting of DO statements.

## CONTROL STATEMENTS

1. The range of each nested DO statement must be entirely within the range of the containing DO statement.

Example

Valid      Invalid





The range of  
DO 2 is outside  
that of DO 1.

2. The ranges of nested DO statements cannot overlap.

Example


Valid      Invalid



The ranges of  
loop DO 2 and  
DO 3 overlap.

3. More than one DO loop within a nest of DO loops may end on the same statement. When this occurs, the terminal statement is considered to belong to the innermost DO statement that ends on that statement. The statement label 4 of the shared terminal statement cannot be used in any GO TO or arithmetic IF statement that occurs anywhere other than within the range of the DO statement to which it belongs.


Example



All the DO statements  
share the same terminal  
statement, however, it  
belongs to DO 4.

#### 9.4.2 Extended Range

The extended range of a DO statement is defined as the set of statements that execute between the transfers out of the innermost DO statement of a set of nested DOs and the transfer back into the range of this innermost DO statement. The extended range of a nested DO statement is as follows:



The following rules govern the use of a DO statement extended range:

1. The transfer out statement for an extended range operation must be contained by the most deeply nested DO statement that contains the location to which the return transfer is to be made.
2. A transfer into the range of a DO statement is permitted only if the transfer is made from the extended range of that DO statement.
3. The extended range of a DO statement must not contain another DO statement.

## CONTROL STATEMENTS

4. The extended range of a DO statement cannot change the index variable or indexing parameters of the DO statement.
5. You may use and return from a subprogram within an extended range.


### 9.4.3 Permitted Transfer Operations

The following rules govern the transfer of program control from within a DO statement range or the ranges of nested DO statements:


1. A transfer out of the range of any DO loop is permitted at any time. When such a transfer executes, the value of the controlling DO statement's index variable is defined as the current value.
2. A transfer into the range of a DO statement is permitted if it is made from the extended range of the DO statement.
3. You may use and return from a subprogram from within the range of any:
  - a. DO loop,
  - b. nested DO loop, or
  - c. extended range loop (in which you leave the loop via a GO TO, execute statements elsewhere, and return to the original loop).

The following examples illustrate the transfer operations permitted from within the ranges of nested DO statements:

#### Valid Transfers



#### Invalid Transfer



## CONTROL STATEMENTS

### 9.5 CONTINUE STATEMENT

You may place CONTINUE statements anywhere in the source program without affecting the program sequence of execution. CONTINUE statements are commonly used as the last statement of a DO statement range in order to avoid ending with a GO TO, PAUSE, STOP, RETURN, arithmetic IF, another DO statement, or a logical IF statement containing any of the foregoing statements. Write this statement as

12 CONTINUE

#### Example

In the following sequence, the labeled CONTINUE statement provides a legal termination for the range of the DO loop.

```
DO 45 ITEM=1,1000
STOCK=NVNTRY (ITEM)
CALL UPDATE (STOCK,TALLY)
IF(ITEM.EQ.LAST) GO TO 77
45 CONTINUE
```

```
77 PRINT 20, HEADING,PAGENO
```

### 9.6 STOP STATEMENT

Execution of the STOP statement causes the execution of the object program to be terminated and returns control to the DECsystem-10 Monitor. A descriptive message may optionally be included in the STOP statement to be output to your I/O terminal immediately before program execution is terminated. Write this statement like this:

```
STOP
STOP 'N'
```

or

```
STOP n,
```

where 'N' is a string of ASCII characters enclosed by single quotes and n is an octal string up to 12 digits. The string N or the value n is printed at your I/O terminal when the STOP statement executes. The string N may be of any length. (Continuation lines may be used for large messages.)

## CONTROL STATEMENTS

### Examples

```
STOP 'Termination of the Program'
```

or

```
STOP 7777
```

### 9.7 PAUSE STATEMENT

Execution of a PAUSE statement suspends the execution of the object program and gives you the option to:

1. Continue execution of the program
2. Exit
3. Initiate a TRACE operation (Paragraph 9.7.1).

The permitted forms of the PAUSE statements are:

1. PAUSE
2. PAUSE 'literal string'
3. PAUSE n, where n is an octal string up to 12 digits.

Execution of a PAUSE statement of any of the foregoing forms causes the standard instruction:

```
TYPE G TO CONTINUE, X TO EXIT, T TO TRACE
```

to be printed at your terminal. If the form of the PAUSE statement contains either a literal string or an integer constant, the string or constant prints on a line preceding the standard message. For example, the statement

```
PAUSE 'TEST POINT A'
```

causes the following to be printed at your terminal:

```
TEST POINT A  
TYPE G TO CONTINUE, X TO EXIT, T TO TRACE
```

The statement

```
PAUSE 1
```

causes the following to be printed at your terminal:

```
PAUSE 000001  
TYPE G TO CONTINUE, X TO EXIT, T TO TRACE
```

## CONTROL STATEMENTS

### 9.7.1 T(TRACE) Option

The entry of the character T in response to the message output by the execution of a PAUSE statement starts a TRACE routine. This routine causes a complete history of all subroutine calls made during the execution of the program, up to the execution of the PAUSE statement to be printed at your terminal. The history printed by the TRACE routine consists of:

1. The names of all subroutines called, arranged in the reverse order of their call;
2. The absolute location (written within parentheses) of the called subroutine;
3. The name of the calling subroutine plus an offset factor and the absolute location (written within parentheses) of the statement within the routine that initiated the call;
4. The number of arguments involved (written within angle brackets);
5. An alphabetic code (written within square brackets) that specifies the types of each argument involved. The alphabetic codes used and the meaning of each are:

Code Character	Type Specified
U	Undefined type; the use of the argument will determine its type.
L	Logical
I	INTEGER
F	Single-precision REAL
O	Octal
S	Statement Number
D	Double-precision REAL
C	COMPLEX
K	A literal or constant

#### Example

The following printout illustrates the execution of the PAUSE statement "PAUSE 'TEST POINT A'", the entry of a T character to initiate the TRACE routine, the resulting trace printout, and the entry of the character G to continue the execution of the program.

```
TEST POINT A
TYPE G TO CONTINUE, X TO EXIT, T TO TRACE.
*T
```

```
NAME      (LOC)    <<---- CALLER   (LOC)    <#ARGS> [ARG TYPES]
TRACE.    (414056) <<---- PAUS.+141(376) <#1>          [U]
PAUS.    (235)      <<---- MAIN.+4(151)  <#1>          [U]
TYPE G TO CONTINUE, X TO EXIT, T TO TRACE.
*G
```

## CONTROL STATEMENTS

In addition to its use with the PAUSE statement, you may call the TRACE routine directly, using the form

CALL TRACE

or as a function, using the form

X=TRACE(X)

Execution of the foregoing statements starts the TRACE routine, which prints the history of all subprogram calls made during the execution of the program, up to the execution of the CALL statement or up to the execution of the function, respectively. The history printed by the TRACE routine under these circumstances is as described in the preceding paragraph.



## CHAPTER 10

### I/O STATEMENTS

#### 10.1 DATA TRANSFER OPERATIONS

FORTRAN-10 I/O statements permit the transfer of data between processor storage (core) and peripheral devices and/or between storage locations. Data in the form of logical records may be transferred by use of an a) sequential, b) random access, c) append transfer mode, or d) dump mode. The areas in core from which data is to be taken during output (write) operations and into which data is stored during input (read) operations are specified by:

1. A list in the I/O statement that initiated the transfer
2. A list defined by a NAMELIST statement, or
3. Between a specified FORMAT statement and the external medium.

The type and arrangement of transferred data may be specified by format specifications located in either a FORMAT statement or an array (formatted I/O), or by the contents of an I/O list (list-directed I/O).

The following sections describe the statements and data format required to initiate I/O transfer operations.

#### 10.2 TRANSFER MODES

The characteristics and requirements of the a) sequential, b) random access, and c) append data modes are described in the following paragraphs.

##### 10.2.1 Sequential Mode

Records are transferred during a sequential mode of operation in the same order they appear in the external data file. Each I/O statement executed in a sequential mode transfers the record immediately following the last record transferred from the accessed source file.

##### 10.2.2 Random Access Mode

This mode permits access to and transfer of records from a file in any desired order. Random access transfers, however, may be made only to (or from) a device that permits random-type data addressing operations, i.e., disk, and to files that have previously been set up

## I/O STATEMENTS

for random access transfer operation. Files for random access must contain a specified number of identically sized records that may be accessed, individually, by a record number.

You may use the FORTRAN-10 OPEN statement - see Chapter 12 - or a subroutine call to DEFINE FILE to set up random access files.

Use the OPEN statement to establish a random access mode to permit the execution of random access data transfer operations. The OPEN statement should logically precede the first I/O statement for the specified logical unit in the user source program.

### 10.2.3 Append Mode

This mode is a special version of the sequential transfer mode: Use it only for sequential output (write) operations. The append mode permits you to write a record immediately after the last logical record of the accessed file. During an append transfer, the records already in the accessed file remain unchanged. The only function performed is the appending of the transferred records to the end of the file.

You must use an OPEN statement to establish an append mode before append I/O operations can be executed.

## 10.3 I/O STATEMENTS, BASIC FORMATS AND COMPONENTS

The majority of the I/O statements described in this chapter are written in one of the following basic forms or in some modification of these forms:

Basic Statement Forms	Use
Keyword (u,f)list	Formatted I/O Transfer
Keyword (u#R,f)list	Random Access Formatted I/O Transfer
Keyword (u,*)list	List-Directed I/O Transfer
Keyword (u,N)	NAMELIST-Controlled I/O Transfer
Keyword (u)list	Binary I/O Transfer
Keyword (u#R)list	Random Access Binary I/O Transfer

where

Keyword	= the statement name (READ or WRITE)
u	= FORTRAN-10 logical unit number
f	= FORMAT statement number in the current program unit or the name of an array that contains the desired format specifications
list	= I/O list
#R	= the delimiter # followed by the number of a record in an established random-access file
*	= symbol specifying a list-directed I/O transfer
N	= the name of an I/O list defined by a NAMELIST statement

The following paragraphs provide details of the foregoing components.

## I/O STATEMENTS

### 10.3.1 I/O Statement Keywords

The keywords (names) of the FORTRAN-10 I/O statements described in this chapter are:

- |           |            |
|-----------|------------|
| 1. READ   | 6. WRITE   |
| 2. REREAD | 7. PRINT   |
| 3. ACCEPT | 8. PUNCH   |
| 4. FIND   | 9. TYPE    |
| 5. DECODE | 10. ENCODE |

### 10.3.2 FORTRAN-10 Logical Unit Numbers

Decimal numbers identify the physical devices used for most FORTRAN-10 I/O operations. During compilation, the compiler assigns default logical unit numbers for the REREAD, READ, ACCEPT, PRINT, PUNCH and TYPE statements. Default unit numbers are negatively signed decimal numbers that you cannot access.

You may make the logical device assignments at run time, or you may use the standard assignments contained by the FORTRAN-10 Object Time System (FOROTS). Table 10-1 lists the standard logical device assignments. We recommend that you specify the device explicitly in the OPEN statement.

### 10.3.3 FORMAT Statement References

A FORMAT statement contains a set of format specifications that defines the structure of a record and the form of the data fields comprising the record. Format specifications may also be stored in an array rather than in a FORMAT statement. (Refer to Chapter 13 for a complete description of the FORMAT statement.)

The execution of an I/O statement that includes either a FORMAT statement number or the name of an array that contains format specifications causes the structure and data of the transferred record to assume the form specified in the referenced statement or array. Records transferred under the control of a format specification are referred to as "formatted" records. Conversely, records transferred by I/O statements that do not reference a format specification are referred to as "unformatted" records. During unformatted transfers, data is transferred on a one-to-one correspondence between internal (processor) and external (device) locations, with no conversion or formatting operations.

Unformatted files are binary files divided into records by FORTRAN-10 embedded control words; the control words are invisible to you. You cannot prepare files of this type without using FOROTS. Unformatted files are for use only within the FORTRAN-10 environment.

## I/O STATEMENTS

Table 10-1  
FORTRAN-10 Logical Device Assignments

Device/Function	Default Filename	FORTRAN Logical Unit Number	Use
<b>Standard Devices*</b>			
0 DSK	FORxx.DAT	00	ILLEGAL
CDR		01	Disk
LPT		02	Card Reader
CTY		03	Line Printer
TTY		04	Console Teletype
PTR		05	User's Teletype
PTP		06	Paper Tape Reader
DIS		07	Paper Tape Punch
DTA1		08	Display
DTA2		09	DECtape
DTA3		10	
DTA4		11	
DTA5		12	
DTA6		13	
DTA7		14	DECtape
MTA0		15	Magnetic Tape
NTA1		16	
MTA2		17	
FORTR		18	Assignable Device
DSK		19	DISK
DSK		20	
DSK		21	
DSK		22	
DSR		23	
		24	

\*The total number of standard devices permitted is an installation parameter.

## I/O STATEMENTS

Table 10-1 (Cont.)  
FORTRAN-10 Logical Device Assignments

Device/Function	Default Filename	FORTRAN Logical Unit Number	Use
<b>Standard Devices*</b>			
DEV1	FORxx.DAT	25	
DEV2		26	
DEV3		27	
DEV4		28	
DEV5		29	
			Disk
DEV63	FOR63.DAT	63	
<b>Default Devices (inaccessible to the user)</b>			
REREAD	Current file	-6	REREAD statement
CDR	FORCDR.DAT	-5	READ statement
TTY	FORTTY.DAT	-4	ACCEPT statement
LPT	FORLPT.DAT	-3	PRINT statement
PTP	FORPTP.DAT	-2	PUNCH statement
TTY	FORTTY.DAT	-1	TYPE statement

\*The total number of standard devices permitted is an installation parameter.

## I/O STATEMENTS

### 10.3.4 I/O List

An I/O list specifies the names of variables, arrays, and array elements to which input data is to be assigned or from which data is to be output. Implied DO constructs (Paragraph 10.3.4.1), which specify sets of array elements, may also be included in I/O lists. The number of items in a statement list determines the amount of data to be transferred during each execution of the statement.

10.3.4.1 Implied DO Constructs - When an array name is given in an I/O list, all elements of the array are transferred in the order described in Chapter 3 (Paragraph 3.5.3). If only a specific set of array elements is involved, they may be specified in the I/O list either individually or in the form of an implied DO construct.

Write implied DOs within parentheses in a format similar to that of DO statements. They may contain one or more variable, array, and/or array element names, delimited by commas and followed by indexing parameters that are defined as for DO statements.

The general form of an implied DO is

(name(SL),I=M1,M2,M3)

where

name	= an array name
SL	= the subscript list of an array or an array element identifier
I	= the index control variable that may represent a subscript appearing in a preceding subscript list
M1,M2,M3	= the indexing parameters that specify, respectively, the initial, terminal, and increment values that control the range of I. If M3 is omitted (with its preceding comma), a value of 1 is assumed.

Examples

(A(S),S=1,5)	Specifies the first five elements of the one-dimension array A, i.e., A(1), A(2), A(3), A(4), A(5).
(A(2,S),S=1,10,2)	Specifies the elements A(2,1), A(2,3), A(2,5), A(2,7), A(2,9) of array A.
(I,I=1,5)	Specifies the integers 1,2,3,4, and 5.

As stated previously, implied DO constructs may also contain one or more variable names.

Example

I, J, B, and C must be integer variables.

((A(B,C),B=1,10),C=1,10),I,J	Specifies a 10 X 10 set of elements of array A, the location identified by I, and the location identified by J.
------------------------------	---

## I/O STATEMENTS

You may also nest implied DO constructs. Nested implied DOs may share one or more sets of indexing parameters.

### Example

((A(J,K),J=1,5),D(K),K=1,10) Specifies a 5 X 10 set of elements of array A and the first 10 elements of array D.

When you specify an array or set of array elements as either a storage or transmitting area for I/O purposes, the array elements involved are accessed in ascending order with the value of the first subscript quantity varying most rapidly and the value of the last given subscript increasing to its maximum value least rapidly. For example, the elements of an array dimensioned as TAB(2,3) are accessed in the order:

```
TAB(1,1)  
TAB(2,1)  
TAB(1,2)  
TAB(2,2)  
TAB(1,3)  
TAB(2,3)
```

**10.3.4.2 Formatted Record Handling** - Data is processed under format control so that each item in the I/O list is matched with a field descriptor in the FORMAT statement. If the end of the FORMAT specification is reached and more items remain in the I/O list, a new line or record is established and the data processing is restarted, either:

1. at the first item in the FORMAT specification or,
2. (if parenthesized sets of FORMAT specifications exist within the FORMAT specification) with the last set within the FORMAT specification.

On input, if the record is exhausted before the data transfers are completed, the remainder of the transfer is completed as if the record were extended with blanks. See Section 13.2.2 for more details.

### 10.3.5 Specification of Records for Random Access

You must identify records to be transferred in a random access mode in an I/O statement by an integer expression or variable preceded by an apostrophe used as a delimiter, e.g., '101.

#### NOTE

You may use a pound sign (#) in place of the apostrophe ('), e.g., both #101 and '101 are accepted by FORTRAN-10.

10.3.6 List-Directed I/O

The use of an asterisk in an I/O statement in place of a FORMAT statement number causes the specified transfer operation to be "list-directed". In a list-directed transfer, the data to be transferred and the type of each transferred datum are specified by the contents of an I/O list included in the I/O command used. The transfer of data in this mode is performed without regard for column, card, or line boundaries. The list-directed mode is specified by the substitution of an asterisk (\*) for the FORMAT statement reference, i.e., f, of an I/O statement. The general form of a list-directed I/O statement is

```
keyword (u,*)list
```

## Example

```
READ (5,*)I,IAB,M,L
```

You may use list-directed transfers to read data from any acceptable input device, including an input keyboard terminal.

## NOTE

Do not use device positioning commands, such as BACKSPACE, SKIP RECORD, etc., in conjunction with list-directed I/O operations. If you do, the results are unpredictable.


Data for list-directed transfers should consist of alternate constants and delimiters. The constants used should have the following characters:

1. Input constants must be of a type acceptable to FORTRAN-10. Octal constants, although acceptable, are not permitted in list-directed I/O operations.
2. Literal constants must be enclosed within single quotes, e.g., 'ABLE'. A quoted string which is too long to fit in one element of the input list will be placed in adjacent elements and will be padded with blanks. If a quoted string is being placed in any array and it fills more than one element of the array, the remaining elements of the array will be unchanged. In this case, it is assumed that the user meant for the long string to go into the array and for any following data to go into the rest of the input list. If the string fits into one element of the array, the array will continue to be filled.
3. Blanks are delimiters; therefore, they are not permitted in any but literal constants.
4. You may omit decimal points from real constants that do not have a fractional part. FORTRAN-10 assumes that the decimal point follows the rightmost digit of a real constant.
5. Complex constants must be enclosed in parentheses.

## I/O STATEMENTS

Delimiters in data for list-directed input must comply with the following:

1. Delimiters may be either commas or blanks.
2. Delimiters may be either preceded by or followed by any number of blanks, carriage return/line feed characters, tabs, or line terminators; any such combination is considered by FORTRAN-10 as being only a single delimiter.
3. Represent a null (the complete absence of a datum) by two consecutive commas that have no intervening constant(s). You may place any number of blanks, tabs, carriage return/line feed characters, or end-of-input conditions between the commas of a null. Each time you specify a null item in the input data, its corresponding list element is skipped (unchanged). The following illustrates the effect of a null input:



4. Slashes (/) cause the current input operation to terminate even if all the items of the directing list are not filled. The contents of items of the directing I/O list that either are skipped (by null inputs) or have not received an input datum before the transfer is terminated remain unchanged. Once the I/O list of the controlling I/O statement is satisfied, the use of the / delimiter is optional.
5. Once the I/O list has been satisfied (values have been transferred to each item of the list), any items remaining in the input record are skipped.

Constants or nulls in data for list-directed input may be assigned a repetition factor so that an item is repeated.

The repetition of a constant is written as

r\*K

where r is an integer constant that specifies the number of times the constant represented by K is to be repeated.

The repetition of a null is written as an integer followed by an asterisk.

Examples

10*5	represents 5,5,5,5,5,5,5,5,5,5
3*'ABLE'	represents 'ABLE','ABLE','ABLE'
3*	represents null,null,null

## I/O STATEMENTS

### 10.3.7 NAMELIST I/O Lists

You may define one or more lists by a NAMELIST statement (Chapter 11). Each I/O list defined in a NAMELIST statement is identified by a unique (within the routine) 1- to 6-character name that may be referenced by one or more READ or WRITE statements. The first character of each I/O list name must be alphabetic. By using the NAMELIST statement, you eliminate the need for specifying the entire I/O list.

I/O statements that reference a NAMELIST-defined I/O list cannot contain either a FORMAT statement reference or an I/O list. You cannot use NAMELIST-controlled I/O operation to transfer octal numbers or literal strings.

You may use only NAMELIST-controlled READ/WRITE statements to bring in/write out records formatted in the following manner. Format records for NAMELIST-controlled input operations as follows:

```
$NAME D1,D2,D3...Dn$
```

where

1. \$ symbols delimit the beginning and end of the record. The first \$ must be in column 2 of the input record; column 1 must be blank.
2. NAME is the name of a NAMELIST-defined input list. The named list identifies the processor storage locations that are to receive the data items read from the accessed record.
3. D1 through Dn are pairs of the form "variable=value" where the value is assigned to the associated variable. These items cannot be octal numbers or literal strings.

#### NOTE

Do not use device positioning commands such as BACKSPACE, SKIP RECORD, etc., in conjunction with NAMELIST-controlled I/O operations. If you do, the results are unpredictable.

See Chapter 11 for more information on NAMELIST I/O transfers.

### 10.4 OPTIONAL READ/WRITE ERROR EXIT AND END-OF-FILE ARGUMENTS

You may optionally add either or both an error exit or an end-of-file argument to the portion in parentheses of any form of the READ and WRITE statements when a unit is specified.

Write the error exit argument as ERR=c where c is a statement number in the current program unit. Using this argument terminates the current I/O operation and transfers program control to the statement identified by the argument if an error is detected. For example, the detection of an error during the execution of

```
READ(10,77,ERR=101)TABLE,I,M,J
```

## I/O STATEMENTS

terminates the input operation and transfers program control to statement 101. See the FORTRAN-10 Library Subroutine ERRSNS (Chapter 15) to find out how to identify the actual error that occurred.

When an ERR= transfer occurs, all items on the input list and all implied DO indexes on input or output lists become undefined.

Write the end-of-file argument as END=d, where d is a statement number in the current program unit. This branch, when taken, stops the current I/O operation and transfers program control to the statement identified by the argument. In the example below, the detection of an end-of-file condition during the execution of

```
READ(10,77,END=50) TABLE,I,M,J
```

results in the transfer of control to statement 50.

When an END= transfer occurs, all items on the input list receive the value zero and all implied DO indices on input lists become undefined.

If the END= argument is not present, but an ERR= argument is, an end-of-file (EOF) condition is treated as a user-trappable error. If neither the ERR= nor the END= argument is present and an end-of-file condition is detected, a message is printed, the file is closed, program execution is terminated, and control is returned to the monitor.

### 10.5 READ STATEMENTS

READ statements transfer data from peripheral devices into specified processor storage locations. The permitted forms of this type of input statement permit READ statements to be used on both sequential and random access transfer modes for formatted, unformatted, list-directed, and NAMELIST-controlled data transfers.

#### 10.5.1 Sequential Formatted READ Transfers

Descriptions of the READ statements that may be used for the sequential transfer of formatted data follow:

1. Form:      READ (u,f)list

Use:      Input data from logical unit u, formatted according to the specification given in f, into the processor storage locations identified in input list.

Example:    READ (10,555) TABLE(10,20),ABLE,BAKER,CHARL

2. Form:      READ(u,f)

Use:      Input the data from logical unit u directly into either a Hollerith (H) field descriptor or a literal field descriptor given within the format specifications of the referenced FORMAT statement. If the referenced FORMAT statement does not contain either of the foregoing types of format field descriptors, the input record is skipped. If a required field descriptor is present, its contents are replaced by the input data.

Example:    READ(15,101)

## I/O STATEMENTS

3. Form:      READ f

Use:      Input the data from the READ default device (card reader) directly into either a Hollerith (H) field descriptor or a literal field descriptor given within the format specifications of the referenced FORMAT statement. If the referenced FORMAT statement does not contain either of the foregoing types of format field descriptors, the input record is skipped. If a required field descriptor is present, its contents are replaced by the input data.

Example:    READ 66

4. Form:      READ f,list

Use:      Input the data from the READ default device (card reader) into the processor storage locations identified in the input list. The input data is formatted according to the specifications given in f.

Example:    READ 15, ARRAY (20,30)

### 10.5.2 Sequential Unformatted Binary READ Transfer

You may use only the following form of the READ statement for the sequential transfer of unformatted input FORTRAN binary data:

Form:      READ (u)list

Use:      Input one logical record of data from logical unit u into processor storage as the value of the location identified in list. You may read only binary files output by a FORTRAN-10 unformatted WRITE statement by this type of READ statement.

#### NOTE

If you use the form READ (u), one unformatted input record will be skipped.

Example:    READ (10) BINFIL (10,20,30)

### 10.5.3 Sequential List-Directed READ Transfer

You may use the following forms of the READ statements to control a sequential, list-directed input transfer:

1. Form:      READ(u,\*)list

Use:      Read data from logical device u into processor storage as the value of the locations identified in list. Each input datum is converted, if necessary, to the type of its assigned list variable.

Example:    READ(10,\*) IARY(20,20),A,B,M

## I/O STATEMENTS

2. Form:      READ \*,list

Use:      Read the data from the READ default device (card reader) into the processor storage locations identified in the input list. Each input datum is converted, if necessary, to the type of its assigned list variable.

Example:    READ \*,ABEL(10,20),I,J,K

### 10.5.4 Sequential NAMELIST-Controlled READ Transfers

You may use only the following form of the READ statement to initiate a sequential NAMELIST-controlled input transfer:

Form:      READ(u,N)

Use:      Read data from logical unit u into processor storage as the value of the locations identified by the NAMELIST input specified by the name N. The input data is converted to the type of assigned variable if type conflicts occur. Only input files that contain records formatted and identified for NAMELIST operations (Paragraph 10.3.7) may be read by READ statements of this form.

### 10.5.5 Random Access Formatted READ Transfers

You may use only the following form of the READ statement to initiate a random access formatted input transfer:

Form:      READ (u#R,f)list

Use:      Input data from record R of logical unit u. Format each input datum according to the format specifications of f and place into processor storage as values of the locations identified in list. Only disk files that have been set up by either an OPEN or DEFINE FILE statement may be accessed by a READ statement of this form. (If record R has not been written, an error results.)

Example:    READ(1#20,100) I, X(J)

### 10.5.6 Random Access Unformatted READ Transfers

You may use only the following form of the READ statement to initiate a random access unformatted input transfer:

## I/O STATEMENTS

Form:	READ (u#R)list
Use:	Input data from record R of logical unit u. Place the input data into processor storage as the value of the locations identified in list. Only binary files that have been output by an unformatted random access WRITE statement may be accessed by a READ statement of this form. (If record R has not been written, an error results.)
Example:	READ (1#20) BINFILE Read record number 20 into array BINFILE.
NOTE If the form READ (u#R) is used, it will cause logical input record R to be skipped.	

### 10.6 SUMMARY OF READ STATEMENTS

Table 10-2 summarizes the various forms of the READ statements.

Table 10-2  
Summary of READ Statements

Type of Transfer	Transfer Mode	
	Sequential	Random Access
Formatted	READ(u,f)list READ(u,f) READ f,list READ f	READ(u#R,f)list
Unformatted	READ(u)list READ(u)	READ(u#R)list READ(u#R)
List-Directed	READ(u,*)list READ *,list	
NAMELIST	READ(u,N)	

Note: You may include the ERR=c and END=d arguments in any of the above READ statements. When included, the foregoing arguments must be last, e.g., READ (10,20,END=101,ERR=500) ARRAY(50,100).

### 10.7 REREAD STATEMENT

The REREAD statement causes the last record read from the last active input device to again be accessed and processed.

## I/O STATEMENTS

You cannot use the REREAD feature of FORTRAN-10 until an input (READ) transfer from a file has been accomplished. If you use REREAD prematurely, an error results.

Once a record has been accessed by a formatted READ statement, the record transferred may be reread as many times as desired. In a formatted transfer, you may use the same or new format specification by each successive REREAD statement.

You may use the REREAD statement only for sequential formatted data transfers. The form of the REREAD statement is:

Form:      REREAD f,list

Use:      Reread the last record read during the last initiated READ operation and input the data contained by the record into the processor storage locations specified in the input list. Format the data read according to the format specifications given in statement f.

Example:    DIMENSION ARRAY(10,10),FORMA(10,10),FORMB(10,10),  
1       FORMC(10,10)  
90      READ(16,100)ARRAY  
.  
.      .  
100     FORMAT (-----)  
.      .  
.      .  
110     REREAD 100,FORMA  
115     REREAD 150,FORMB  
120     REREAD 160,FORMC  
  
150     FORMAT (-----)  
160     FORMAT (-----)

In the above sequence, statement 90 inputs data formatted according to statement 100 into the array ARRAY. Statement 110 reads the record read by statement 90 and inputs the data formatted as in the initial READ operation into the array FORMA.

Statement 115 reads the record read by statement 90 and inputs the data formatted according to statement 150 into the array FORMB.

Statement 120 reads the record read by statement 90 and inputs the data formatted according to statement 160 into the array FORMC.

### NOTE

If you try to REREAD a record input from the teletype, you will get either the current record or the last 150 characters of the current record, whichever is the lesser.

**10.8 WRITE STATEMENTS**

WRITE statements transfer data from specified processor storage locations to peripheral devices. The various forms of the WRITE statement enable it to be used in sequential, append, and random access transfer modes for formatted, unformatted, list-directed, and NAMELIST-controlled data transfers.

**10.8.1 Sequential Formatted WRITE Transfers**

You may use the following forms of the WRITE statement for the sequential transfer of formatted data:

1. Form:      WRITE(u,f)list  
 Use:      Output the values of the processor storage locations identified in list into the file associated with logical unit u. Convert and arrange the output data according to the specifications given in f.  
 Example:    WRITE(06,500)OUT(10,20),A,B
2. Form:      WRITE f,list  
 Use:      Output the values of the processor storage locations identified in list to the default device (line printer). Convert and arrange the output data according to the specifications given in f.  
 Example:    WRITE 10,SEND(5,10),A,B,C
3. Form:      WRITE f  
 Use:      Output the contents of any Hollerith (H) or literal ('') field descriptor(s) contained by f to the default device (line printer). If neither of the foregoing types of field specifications is found in f, no output transfer is performed.  
 Example:    WRITE 10

**10.8.2 Sequential Unformatted Binary WRITE Transfer**

You may use the following form of the WRITE statements for the sequential transfer of unformatted data:

- Form:      WRITE (u)list  
 Use:      Output the values of the processor storage locations identified in list into the file associated with logical unit u. No conversion or arrangement of output data is performed.  
 Example:    WRITE(12)ITAB(20,20),SUMS(10,5,2)

10.8.3 Sequential List-Directed WRITE Transfers

You may use the following form of the WRITE statement to initiate a sequential list-directed output transfer.

**Form:**        `WRITE(u,*)list`

**Use:**        Output the values of the processor storage locations identified in list into the file associated with logical unit u. The conversion of each datum from internal to external form is performed according to the type of the list variable from which the datum is taken.

**Example:**     `WRITE(12,*)C,X,Y,ITAB(10,10)`

10.8.4 Sequential NAMELIST-Controlled WRITE Transfers

You may use only the following form of the WRITE statement to initiate a sequential NAMELIST output transfer.

**Form:**        `WRITE(u,N)`

**Use:**        Output the values of the processor storage locations identified by the contents of the NAMELIST-defined list specified by name N into the file associated with logical unit u.

**Example:**     `WRITE(12,NMLST)`

10.8.5 Random Access Formatted WRITE Transfers

You may use only the following form of the WRITE statement to initiate a random access type formatted output transfer:

**Form:**        `WRITE(u#R,f)list`

**Use:**        Output the values of the processor storage locations identified by the contents of list to record R of the file associated with logical device u. Only disk files that have been set up by either an OPEN statement or a call to the subroutine DEFINE FILE may be accessed by a WRITE transfer of this form. The data transferred will be formatted according to the specifications given in f. Only those records that have been specifically written are available to be read.

10.8.6 Random Access Unformatted WRITE Transfers

You may use only the following form of the WRITE statement to initiate a random access unformatted output transfer:

**Form:**        `WRITE(u#R)list`

**Use:**        Output the values of the processor storage locations identified by the contents of list to record R of the file associated with logical

## I/O STATEMENTS

device unit u. Only disk files that have been set up by either an OPEN or a call to the DEFINE FILE subroutine may be accessed by a WRITE transfer of this form. Only those records that have been specifically written are available to be read.

### 10.9 SUMMARY OF WRITE STATEMENTS

Table 10-3 summarizes the various forms of the WRITE statements.

Table 10-3  
Summary of WRITE Statements

Type of Transfer	Transfer Mode	
	Sequential	Random Access
Formatted	WRITE(u,f)list WRITE f,list WRITE f	WRITE(u#R,f)list
Unformatted	WRITE(u)list	WRITE(u#R)list
List-Directed	WRITE(u,*)list	
NAMELIST-controlled	WRITE(u,N)	
Note:	You may include the ERR=c and END=d arguments in any WRITE statement which has a unit number; however, they must be last.	

### 10.10 ACCEPT STATEMENT

The ACCEPT statement enables you to input data via either a terminal keyboard or a batch control file directly into specified processor storage locations. Use this statement only in the sequential transfer mode for the formatted transfer of inputs from your terminal keyboard during program execution. The following paragraphs describe the permitted forms of the ACCEPT statement.

#### 10.10.1 Formatted ACCEPT Transfers

Use the following forms of the ACCEPT statement for the sequential transfer of formatted data.

1. Form:      ACCEPT f,list

Use:      Input data character-by-character from the user's terminal into the processor storage locations identified by the contents of list. Format the input data according to the format specifications given in f.

Example:    ACCEPT 101,LINE(73)

## I/O STATEMENTS

2. Form: ACCEPT \*,list

Use: Input data character-by-character from the user's terminal into the processor storage locations identified by the contents of list. Convert the input characters, where necessary, to the type of its assigned list variable.

Example: ACCEPT \*,IAB,ABE,KAB,MAR

### 10.10.2 ACCEPT Transfers Into FORMAT Statements

You may use the following form of the ACCEPT statement to input data from your terminal keyboard directly into a specified FORMAT statement if the FORMAT statement has either or both a Hollerith (H), or a literal ('s') field descriptor. If the referenced statement has neither of the foregoing descriptors, the input record is skipped.

Form: ACCEPT f

Use: Replace the contents of the appropriate fields of statement f with the data entered at the user's terminal keyboard.

Example: ACCEPT 101

### 10.11 PRINT STATEMENT

The PRINT statement causes data from specified processor storage locations to be output on the standard output device (line printer). Use this statement only for sequential formatted data transfer operation; write it in either of the three following forms:

1. Form: PRINT f,list

Use: Output the values of the processor storage locations identified by the contents of list to the line printer. The values output are to be formatted and arranged according to the format specifications given in f.

Example: PRINT 55, TABLE(10,20), I,J,K

2. Form: PRINT \*,list

Use: Output the values of the processor storage locations identified by the contents of list to the line printer. The conversion of each datum from internal to external form is performed according to the type of the list variable from which the datum is taken.

Example: PRINT \*,C,X,Y,ITAB(10,10)

3. Form: PRINT f

Use: Output the contents of the FORMAT statement Hollerith (H) or literal field descriptors to the line printer. If neither an H nor a literal field

## I/O STATEMENTS

descriptor is present in the referenced FORMAT statement, no operation is performed.

Example: PRINT 55

The second form of the PRINT statement is particularly useful when employed with ACCEPT f statements to cause desired data (comments or headings) to be inserted into reports at program execution time.

Example

The sequence

```
55  FORMAT(' END OF ROUTINE')
      .
      .
      .
      PRINT 55
```

results in the printing of the phrase "END OF ROUTINE" on the line printer.

### 10.12 PUNCH STATEMENT

The PUNCH statement causes data from specified processor storage locations to be output to the system standard paper tape punch. Use this statement only for sequential formatted data transfers; write it in one of the three following forms:

1. Form: PUNCH f,list

Use: Output the values of the processor storage locations identified by the contents of list to the standard paper tape punch unit. The values output are to be formatted and arranged according to the format specifications given in f.

Example: PUNCH 10, TABLE(10,20), I,J,K

2. Form: PUNCH \*,list

Use: Output the values of the processor storage locations identified by the contents of list to the paper tape punch unit. The conversion of each datum from internal to external form is performed according to the type of the list variable from which the datum is taken.

Example: PUNCH \*,I,A,B,M,TAB(5,10)

3. Form: PUNCH f

Use: Output the contents of the referenced FORMAT statement Hollerith (H) or literal field descriptors to the standard paper tape punch unit. If neither an H nor a literal field descriptor is present in the referenced FORMAT statement, no operation is performed.

The third form of the PUNCH statement is particularly useful when employed in conjunction with an ACCEPT f statement to cause user-entered data (comments or headings) to be added to an output file at program execution time.

## I/O STATEMENTS

### 10.13 TYPE STATEMENT

The TYPE statement causes data from specified processor storage locations to be output to your (control) terminal printing or display device. Use this statement only for sequential formatted data transfers; write it in one of the following forms:

1. Form:      **TYPE f,list**

Use:      Output the values of the processor storage locations identified by the contents of list to the user's terminal. The values output are to be formatted according to the format specifications given in f.

Example:    **TYPE 101, TABLE(10,20) I,J,K**

2. Form:      **TYPE f**

Use:      Output the contents of the referenced FORMAT statement Hollerith (H) or literal field descriptors to the user's terminal device. If the referenced FORMAT statement does not contain either an H or a literal field descriptor, no operation is performed.

Example:    **TYPE 101**

3. Form:      **TYPE \*,list**

Use:      Output the values of the processor storage locations identified by the contents of list to the user's terminal. The conversion of each datum from internal to external form is performed according to the type of the list variable from which the datum is taken.

Example:    **TYPE \*,IAB(1,5),A,B**

### 10.14 FIND STATEMENT

The FIND statement does not initiate a data transfer operation; use it during random access read operations to locate the next record to be read while the current record is being input. The program does not have access to the "found" record until the next READ statement is executed.

The form of the FIND statement is

**FIND(u#R)**

Example:

In the sequence

```
READ(01#90)
FIND(01#101)
.
.
.
READ(01#101)
```

## I/O STATEMENTS

the FIND statement will locate record #101 on device 01 after record 90 has been retrieved. Record #101 is not processed until the second READ statement in the sequence is executed.

### 10.15 ENCODE AND DECODE STATEMENTS

Use the ENCODE and DECODE statements to perform sequential formatted data transfer between two defined areas of processor storage, i.e., an I/O list and a user-defined buffer; no peripheral I/O device is involved in the operations performed by these statements.

The ENCODE statement transfers data from the variables of a specified I/O list into a specified storage area. ENCODE operations are similar to those performed by a WRITE statement.

The DECODE statement transfers data from a specified storage area into the processor storage locations identified by the variables of an I/O list. DECODE operations are similar to those performed by a READ statement.

Write the ENCODE and DECODE statements in the following forms:

```
ENCODE(c,f,s)list  
DECODE(c,f,s)list
```

where

c specifies the number of characters to be in each internal storage area. This argument may be an integer, an integer expression, or either a real or double precision expression that is converted to an integer form.

#### NOTE

5 characters per storage location are stored in the buffer without regard to the type of variable given as the starting location.

f specifies either a FORMAT statement or an array that contains format specifications.

s specifies the address of the first storage location that is to be used in the transfer operations. When multiple records are specified by the format being used, the succeeding records follow each other in order of increasing storage addresses.

list specifies an I/O list of the standard form (Paragraph 10.3.4).

When multiple records are stored by ENCODE, each new record starts on a new storage location boundary rather than there being a CRLF inserted between records.

## I/O STATEMENTS

### 10.15.1 ENCODE Statement

A description of the form and use of the ENCODE statement follows:

Form: ENCODE(c,f,s)list

Use: The values of the processor storage locations identified by the contents of list are converted to ASCII character strings according to the format specifications given in f. The converted characters are then written into the destination area starting at location s. If you try to transfer more characters than the specified area can contain, the excess characters are ignored.

If you transfer fewer characters than specified for the record size, the empty character locations are filled with blanks.

Example: ENCODE(500,101,START) TABLE

### 10.15.2 DECODE Statement

A description of the form and use of the DECODE statement follows:

Form: DECODE(c,f,s)list

Use: The character strings are taken starting at location s, converted (decoded) according to the format specifications given in f, and stored as the values of the processor storage locations identified in list.

If the format specification requires more characters from a record than are specified by c, the extra characters are assumed to be blanks. If fewer characters are required from a record than are specified by c, the extra characters are ignored.

Example: DECODE(50,50,START) GET(5,10)

### 10.15.3 Example Of ENCODE/DECODE Operations

The following program illustrates the use of both the ENCODE and DECODE statements:

Example

Assume the contents of the variables to be as follows:

A(1) contains the floating point number 300.45  
A(2) contains the floating point number 3.0  
J is an integer variable  
B is a 4-word array of indeterminate contents  
C contains the ASCII string 12345

(1) DO 2 J=1,2  
(2) ENCODE(16,10,B)J,A(J)  
(3) 10 FORMAT(1X,2HA(,I1,4H) = ,F8,2

## I/O STATEMENTS

```
(4)      TYPE 11,B
(5) 11    FORMAT(4A5)
(6) 2     CONTINUE
(7)      DECODE(5,12,C)B
(8) 12    FORMAT(3F1.0,1X,F1.0)
(9)      TYPE 13,B
(10) 13   FORMAT(4F5.2)
(11)     END
```

Array B can contain 20 ASCII characters. The result of the ENCODE statement after the first iteration of the DO loop is:

```
B(1) =      'A(1)'           Typed at line 4 as
B(2) =      '='
B(3) =      '300.4',          A(1) = 300.45
B(4) =      '5'
```

The result after the second iteration is:

```
B(1) =      'A(2)'           Typed at line 4 as
B(2) =      '='
B(3) =      '3.0'             A(2) = 3.0
B(4) =      '
```

The DECODE statement:

1. Extracts the digits 1, 2, and 3 from C
2. Converts them to floating point values
3. Stores them in B(1), B(2), and B(3)
4. Skips the next character (the digit 4)
5. Extracts the digit 5 from C
6. Converts it to a floating-point value, and,
7. Stores it in B(4)

The output from the TYPE statement at line 9 is:

```
1.00 2.00 3.00 4.00 5.00
```

## I/O STATEMENTS

### 10.16 SUMMARY OF I/O STATEMENTS

Table 10-4 on pages 10-26 and 10-27 presents a summary of all permitted forms of the FORTRAN-10 I/O statement.

## I/O STATEMENTS

Table 10-4  
Summary of FORTRAN-10 I/O Statements

I/O Statements	Formatted	Transfer Format Control		List-Directed
		Unformatted	Namelist	
READ Sequential	READ (u,f)list READ f, list READ f	READ (u)list	READ (u,N)	READ (u,*)list READ *,list
	READ (u#R,f)list	READ (u#R)list		
WRITE Sequential or Append(1)	WRITE (u,f)list WRITE f, list WRITE f	WRITE(u)list	WRITE(u,N)	WRITE(u,*)list
	WRITE (u#R,f)list	WRITE (u#R)list		
REREAD Sequential	REREAD f, list			
FIND Random-only	FIND (u#R)	FIND (u#R)		
ACCEPT Sequential only	ACCEPT f, list ACCEPT f	ACCEPT * ,list		

- 1. You must use an OPEN statement to set up an append mode.
- 2. You must use either the OPEN statement or a call to the DEFINE FILE subroutine to set up a random access mode.

## I/O STATEMENTS

Table 10-4 (Cont.)  
Summary of FORTRAN-10 I/O Statements

I/O Statements	Formatted	Transfer Format Control			List-Direction
		Unformatted	Namelist		
PRINT Sequential only	PRINT f, list PRINT f				PRINT *, list
PUNCH Sequential only	PUNCH f, list PUNCH f				PUNCH *, list
TYPE Sequential only	TYPE f, list TYPE f				TYPE *, list
ENCODE Sequential only	ENCODE (c,f,s) list				
DECODE Sequential only	DECODE (c,f,s) list				

Legend:

u	*	symbol used to specify list-directed I/O
f	#R	operator
list	C	variable which specifies logical record position
I/O list	S	number of characters per internal record address of the first storage location to be used
N		
I/O list		



## CHAPTER 11

### NAMELIST STATEMENTS

#### 11.1 INTRODUCTION

Use the NAMELIST statement to define I/O lists similar to those described in Chapter 10 (Paragraph 10.3.4). Reference defined NAMELIST I/O lists in special forms of the READ and WRITE statements to provide a method of transferring and converting data without referencing format specifications or specifying an I/O list in the I/O statement.

#### 11.2 NAMELIST STATEMENT

Write NAMELIST statements in the following form:

NAMELIST/N1/A1,A2,...,An/N2/B1,B2,...,Bn/Nn/...

where

/N1/ through /Nn/ represents names of individual lists. Always enclose the name with slashes (/N/)

A1 through An  
and  
B1 through Bn are the items of the lists identified, respectively, by names N1 and N2. A list may contain one or more variable, array, or array element names. Delimit the items of a list by commas. Each list of a NAMELIST statement is identified (and referenced) by the name immediately preceding the list.

#### Example

```
DIMENSION C(2,4)
NAMELIST/TABLE/A,B,C/SUMS/TOTAL
```

In the foregoing example, the name TABLE identifies the list A,B,C(2,4), and the name SUMS identifies the list consisting of the array TOTAL.

Once a list has been defined in a NAMELIST statement, one or more I/O statements may reference its name.

## NAMELIST STATEMENTS

The rules for structuring a NAMELIST statement are:

1. You may use a maximum of six characters for a NAMELIST name.
2. You must begin it with an alphabetic character.
3. You must enclose it in slashes.
4. The NAMELIST name must precede the list of entries to which it refers.
5. The NAMELIST name must be unique within the program.
6. You may define a NAMELIST name only once, and you must define it by a NAMELIST statement. Once defined, you may use a name only in READ or WRITE statements.
7. You must define the NAMELIST name in advance of the I/O statement in which it is used.
8. You cannot use a variable used in a NAMELIST statement as a dummy argument in a SUBROUTINE definition.
9. You must define any dimensioned variable contained in a NAMELIST statement in an array declaration statement preceding the NAMELIST statement.

### 11.2.1 NAMELIST-Controlled Input Transfers

During input (READ) transfer operations in which a NAMELIST-defined name is referenced, the records are read until a record is found that begins with the sequence ' \$' (a space followed by a dollar sign) followed by the referenced name. The dollar sign must be the second character in the record; the first character in the record must be a blank. Once the proper symbol-name combination is found, the data items following it are transferred on a one-to-one basis to the processor storage locations identified by the contents of the referenced list. The input data is always converted to the type of the list variable when there is a conflict of types. The input operation continues until another \$ symbol is detected. If variables appear in the NAMELIST record that do not appear in the NAMELIST list, an error condition will occur. Data items of records to be input (read) using NAMELIST-defined lists must be separated by commas and may be of the following form:

V=K1,K2,...,Kn

where

1. V may be a variable, array, or array element name.
2. K1 through Kn are constants of type integer, real, double precision, complex (written as (A,B) where A and B are real), or logical (written as T for true or F for false). A series of identical constants may be represented as a single constant preceded by a repetition factor (5\*5 represents 5,5,5,5,5).

## NAMELIST STATEMENTS

In transfers of this type, logical and complex constants must be equated to variables of their own type. Other type constants (real, double-precision, and integer) may be equated to any other type of variable (except logical or complex), and will be converted to the variable type. For example, assume A is a 2-dimensional real array, B is a 1-dimensional integer array, C is an integer variable, and that the input data is as follows:

```
$FRED A(7,2)=4, B=3,6*2.8, C=3.32$
```

A READ statement referring to the NAMELIST defined name FRED will result in the following: The integer 4 will be converted to floating point and placed in A(7,2). The integer 3 will be placed in B(1), and the integer 2 (converted) will be placed in B(2),B(3),...,B(7). The floating point number 3.32 will be converted to the integer 3 and placed in C.

### NOTE

"&" may be used instead of "\$" in NAMELIST-controlled input.

### 11.2.2 NAMELIST-Controlled Output Transfers

When a WRITE statement refers to a NAMELIST-defined name, all variables and arrays and their values belonging to the named list are written out, each according to its type. Arrays are written out by columns. Output data is written so that:

1. The fields for the data will be large enough to contain all the significant digits.
2. The output can be read by an input statement referencing a NAMELIST-defined list.

For example, if JOE is a 2 X 3 real array, the statement

```
NAMELIST/NAM1/JOE,K1,ALPHA  
WRITE (u,NAM1)
```

generates the following form of output:

Column



```
$NAME1  
JOE= -6.750000 , 0.2340000E-04, 680.0000 , -17.80000  
0.0000000E-01, -1970000. , K1= 73.10000 ,  
ALPHA= 3.000000 , $
```

### NOTE

Do not use device positioning commands such as BACKSPACE, SKIP, RECORD, etc., with NAMELIST-controlled I/O operations. If you do, the results are unpredictable.



## CHAPTER 12

### FILE CONTROL STATEMENTS

#### 12.1 INTRODUCTION

This chapter describes the OPEN and CLOSE statements.

They are file control statements used to set up files and establish parameters for I/O operations and to terminate I/O operations.

#### 12.2 OPEN AND CLOSE STATEMENTS

Both the OPEN and CLOSE statements are unique to FORTRAN-10; they both use the same format and have the same options and arguments.

The OPEN statement enables you to define all of the important aspects of each desired data transfer operation; it provides an extensive list of required and optional arguments that define in detail:

1. the name and location of the data file
2. the type of access required
3. the data format within the file
4. the protection code(1) to be assigned an output data file
5. the disposition of the data file
6. data file record, block and file sizes
7. a data file version identifier

In addition, a DIALOG argument is provided that permits you to establish a dialogue mode of operation when the OPEN statement containing it is executed. In a dialogue mode, interactive terminal/program communication is established. This enables you to define, redefine, or defer the values of the optional arguments contained by the current OPEN statement during program execution.

The general form of the OPEN statement is:

OPEN(Arg1,Arg2,...,Argn)

---

1. Refer to Chapter 8 of the DECsystem-10 Monitor Calls Manual, DEC-10-OMCMA-B-DN3, for a description of file access protection codes.

## FILE CONTROL STATEMENTS

Use the CLOSE statement in the termination of an I/O operation to dissociate the I/O device being used from the active file and file-related information, and to restore the core occupied by I/O buffers and other transfer-related operations. All required device dependent termination functions are also performed on the execution of a CLOSE statement. Note that the CLOSE statement can change the name, protection, directory, and disposition of the file being closed.

Once a CLOSE statement has been executed, you must use another OPEN statement to regain access to the closed file.

The general form of the CLOSE statement is:

```
CLOSE(Arg1.,Arg2.,...,Argn)
```

### CAUTION

If you use a filename argument in a CLOSE statement that is different from the current filename, the file will be renamed.

### 12.2.1 Options for OPEN and CLOSE Statements

The options and their arguments, which you may use in both the OPEN and CLOSE statements, are:

#### 1. UNIT

This option is required; it defines the FORTRAN I/O unit number to be used. FORTRAN devices are identified by assigned decimal numbers within the range 1-63; however, UNIT may be assigned an integer variable or constant. The general form of this argument is:

```
UNIT= An integer variable or constant
```

### NOTE

FORTRAN-10 standard logical unit assignments are described in Chapter 10 (Table 10-1). The range, i.e., 1-63, of the possible UNIT numbers is an installation-defined parameter.

#### 2. DEVICE

This option may specify either the physical or the logical name of the I/O device involved. (A logical name always takes precedence over a physical name.) The DEVICE arguments may specify I/O devices located at remote stations, as well as logical devices. The general form of the DEVICE argument is:

```
DEVICE= A literal constant or variable
```

## FILE CONTROL STATEMENTS

If you omit this option, the logical name u (where u is the decimal unit number) is tried; if this is not successful, the standard (default) device is attempted.

### 3. ACCESS

ACCESS describes the type of input and/or output statements and the file access mode to be used in a specified data transfer operation. You may assign ACCESS any one of six possible names, each of which specifies a specific type of I/O operation. The assignable names and the operations specified are:

- a. SEQIN      The specified data file is to be read in sequential access mode.
- b. SEQOUT     The specified data file is to be written in a sequential access mode.
- c. SEQINOUT   The specified data file may be first read, then written (READ/WRITE sequence) record-by-record in a sequential access mode. When you specify SEQINOUT, a WRITE/READ sequence is illegal. If no access is specified, SEQINOUT is assumed.
- d. RANDOM    The specified data file may be either read or written into, one record at a time. In a random access mode of operation, the relative position of each record is independent of the previous READ or WRITE statement; all records accessed must have a fixed logical record length. The RECORD SIZE option is required for random access operations. You must specify a disk device when the random argument is used.
- e. RANDIN    This argument enables you to establish a special, read-only random access mode with a named file. During a RANDIN mode, you may read the named file simultaneously with other users who have also established a RANDIN mode and with the owner of the file. The use of RANDIN enables a data base to be shared by more than one user at the same time.

## FILE CONTROL STATEMENTS

f. APPEND      The record specified by a corresponding WRITE statement is to be added to the logical end of a named file. You must close and then reopen the modified file to permit it to be read.

The general form of the ACCESS argument is:

```
'SEQIN'  
'SEQOUT'  
'SEQINOUT'  
ACCESS= 'RANDOM'  
'RANDIN'  
'APPEND'  
variable (set to  
literal)
```

### 4. MODE

This option defines the character set of an external file or record. The use of this argument is optional; if you do not use it, one of the following is assumed:

- a. ASCII for a formatted I/O file transfer
- b. Binary for an unformatted I/O file transfer.

#### NOTE

Refer to the DECsystem-10 Monitor Calls Manual for a detailed description of the data modes given in the following list.

You must use one of the following character set specifications with the MODE argument:

Literal	Action Indicated
'ASCII'	Specifies an ASCII character set.
'BINARY'	Specifies data formatted as a FORTRAN binary data file.
'IMAGE'	Specifies an image (I) mode data transfer for the associated READ or WRITE statements. IMAGE is an unformatted binary mode.
'DUMP'	The data file to be transferred is to be handled in a DUMP mode of operation.

The general form of the MODE argument is:

```
'ASCII'  
'BINARY'  
MODE= 'IMAGE'  
'DUMP'  
variable (set to literal)
```

## FILE CONTROL STATEMENTS

5. DISPOSE This option specifies an action to be taken regarding a file at close time. When used, DISPOSE must be either a variable or one of the following literals:

Literal	Action Indicated
'SAVE'	Leave the file on the device.
'DELETE'	If the device involved is either a DECTape or disk, remove the file; otherwise, take no action.
'PRINT'	If the file is on disk, queue it for printing; otherwise, take no action.
'LIST'	If the file is on disk, queue it for printing and delete the file; otherwise take no action.
'PUNCH'	Paper tape punch output.
'RENAME'	Change filename. (This is redundant if a new filename is given.)

If the DISPOSE argument is not given, the argument DISPOSE = 'SAVE' is assumed. The general form of the DISPOSE argument is:

```
'SAVE'  
'DELETE'  
DISPOSE= 'PRINT'  
'LIST'  
'PUNCH'  
'RENAME'  
variable (set to literal)
```

### 6. FILE

This option specifies the name of the file involved in the data transfer operation. FILE must be either a literal, double-precision, complex, or single-precision variable. Single-precision variables are assumed to contain a 1- to 5-character file specification; double-precision variables permit 10-character file specification. The format is a 1- to 6-character filename optionally followed by a period and a 0- to 3-character extension. Any excess characters in either the name or extension are ignored. If you omit the period and extension, the extension .DAT is assumed; if just the extension is omitted, a null extension is assumed. So if you want a filename without an extension, remember to use the period.

If a filename is not specified or is zero, a default name is generated that has the form

FORxx.DAT

where xx is the FORTRAN logical unit number (decimal) or is the logical unit name for the

## FILE CONTROL STATEMENTS

default statements ACCEPT, PRINT, PUNCH, READ, or TYPE. The general form of a FILE argument is:

FILE= A literal or variable set to a literal

### 7. PROTECTION

This option specifies a protection code to be assigned the data file being transferred. The protection code determines the level of access to the file that three possible classes of users (owner, member, or other) will have. PROTECTION may be a 3-digit octal literal or a variable; if the argument is assigned a zero value or is not given, the default protection code established for the DECsystem-10 installation is used. The general form of the PROTECTION argument is:

PROTECTION= 3-digit octal constant or integer variable

### 8. DIRECTORY

Use this option for disk files only. It specifies the location of the user file directory (UFD) or the sub-file directory (SFD) that contains the file specified in the OPEN statement. A directory identifier may consist of either:

- a. Your project programmer number that identifies the UFD, for example, 10,7, or
- b. A UFD/SFD directory path specification. A path specification lists the UFD and the names of its SFDs that form a path to the desired SFD. For example, the following path specification identifies the path leading to SFD 1234:

10,7,SFDA,SFDB,1234

#### NOTE

Refer to the DECsystem-10 Monitor Calls Manual for a complete description of directories and multilevel directory structures.

The general form of a DIRECTORY argument is:

DIRECTORY= Literal or array name containing directory path specification

You may also establish an array containing the directory specification as its elements and reference the array in the DIRECTORY argument. Single-precision arrays permit 5-character directory names to be used; double-precision arrays permit 6-character

## FILE CONTROL STATEMENTS

names to be used. You must use a zero (0) entry to terminate a directory path specification given in an array.

Examples of the use of single- and double-precision arrays in an OPEN statement DIRECTORY specification follow:

a. Single-Precision Array

OPEN (UNIT = 5, DIRECTORY = PATH,...)

where PATH and its elements are:

```
DIMENSION PATH (5)
PATH (1)= "10 ! (PROJECT NUMBER)
PATH (2)= "7 ! (PROGRAMMER NUMBER) UFD
PATH (3)= 'SFDA'    Names of sub-file
PATH (4)= 'SFDB'    directories (SFD's)
PATH (5)=0
```

b. Double-Precision Array

OPEN (UNIT=5, DIRECTORY = PATH,...)

where PATH and its elements are:

## DOUBLE PRECISION PATH (5)

```
PATH (2)='SFDABC'      !names of sub-file
PATH (3)='MYAREA'
PATH (4)='YOURIT'      !directories (SFDs)
PATH (5)=0
```

The elements of a directory specification may then be either a literal or a single- or double-precision array.

The following is an example of a literal specification:

DIRECTORY='10,7,SFD1,SFD2,SFD3'

Project	Sub-File
Programmer	Directory
Number	Path

Whenever the specification is an array, you may specify the required project and programmer numbers either of two ways. You can use one word with the project number in the left half and the programmer number in the right half, or, use the right halves of separate sequential word locations.

## FILE CONTROL STATEMENTS

9. BUFFER COUNT This option enables you to specify the number of I/O buffers to be assigned to a particular device. If this argument is not given or is assigned a value of zero, the Monitor default is assumed. The general form of this argument is:

BUFFER COUNT= An integer constant or variable

10. FILE SIZE Use this option for disk operations only; it enables you to estimate the number of words that an output file is going to contain. The use of FILE SIZE enables you to ensure at the start of a program that enough space is available for its execution. If the size specified is found to be too small during program executions, the Monitor allocates additional space according to the normal Monitor algorithms. The value assigned to the FILE SIZE arguments may be an integer constant or variable and will be rounded up to the next higher block boundary (multiple of 200 octal). The general form of this argument is:

FILE SIZE= An integer constant or variable

11. VERSION Use this option for disk operations only; it enables you to assign a 12-digit octal version number to a file when it is output. The quantity assigned to the VERSION argument may be either an octal constant or variable. The general form of the argument is:

VERSION= An octal constant or integer variable

12. BLOCK SIZE You can use this option for all storage media except disk and DECtape. It enables you to specify a physical storage block size for devices other than disk or DECtape. The value assigned the BLOCK SIZE arguments may be an integer constant or variable. The size specified must be greater than or equal to 3 and less than or equal to 4095. The general form of this argument is:

BLOCK SIZE= An integer constant or variable

13. RECORD SIZE This option enables you to force all logical records to be a specified length. If a logical record exceeds the specified length, it is truncated; if a logical record is less than the specified size, nulls are added to pad the record to its full size. The RECORD SIZE argument is required whenever a random access mode is specified. The value assigned to this argument may be either an integer constant or variable, and may be expressed as

## FILE CONTROL STATEMENTS

the number of words or characters, depending on the mode of the file being described. The general form of this argument is:

RECORD SIZE= An integer constant or variable

### 14. ASSOCIATE VARIABLE

Use this option for disk random access operations only. It provides storage for the number of the record to be accessed next if the program being executed were to continue to sequentially access records starting from the current READ. For example, if record number 3 were read, the ASSOCIATE VARIABLE would be equal to 4. The general form of this argument is:

ASSOCIATE VARIABLE = Integer variable

### 15. PARITY

Use this option for magnetic tape operations only; it permits you to specify the type of parity to be observed (odd or even) during the transfer of data. The general form of this option is:

PARITY= 'ODD'  
'EVEN'  
variable (set to literal)

### 16. DENSITY

Use this option for magnetic tape operations only; it permits you to specify any of four possible bit-per-inch (bpi) tape density parameters for magnetic tape transfer operations. The general form of this option is:

DENSITY= '200'  
'556'  
'800'  
'1600'  
variable (set to literal)

### 17. DIALOG

The use of this option in an OPEN statement enables you to supersede or defer, at execution time, the values previously assigned to the arguments of the statement. There are two forms of this argument. The first is:

DIALOG

This form establishes a dialogue with your terminal when the OPEN statement is executed. FOROTS outputs the following messages at the user's terminal.

UNIT=n:/ACCESS=SEQINOUT/MODE=ASCII  
ENTER NEW FILE SPECS. END WITH A \$ (ALT)

Once the message and defined file specification are output, you may enter any desired changes. You need enter only the arguments that are to be changed.

## FILE CONTROL STATEMENTS

The second form of the argument is:

DIALOG=      Literal or array

The value assigned to DIALOG may be a literal or an array containing a file specification with the desired information.

### 18. ERR

The use of this option in an OPEN or CLOSE statement enables you to transfer program control to an executable statement when an error is detected during the processing of the OPEN or CLOSE statement. The general form of this option is:

ERR= S

where S is the statement label of an executable statement (that appears in the same program unit as the error specifier) to which program control is transferred when an error is detected.

Associated with the ERR= option on OPEN/CLOSE is the subroutine ERRSNS that enables you to pinpoint the error. See Appendix H for FOROTS error values returned by ERRSNS.

#### Examples:

```
OPEN (UNIT= 1, DEVICE= 'DSK', ACCESS= 'SEQIN', MODE= 'BINARY')
```

causes a disk file named FOR01.DAT (since no FILE= option was specified) to be opened on unit 1 for sequential input in binary mode.

```
OPEN (UNIT= 3, DEVICE= 'DSK', FILE= 'PAYROL.DAT',
1      ACCESS= 'RANDOM', MODE= 'ASCII', RECORD SIZE= 80,
2      ASSOCIATE VARIABLE= I, ERR= 240)
```

causes a disk file named PAYROL.DAT to be opened on unit 3 for random input/output operations in ASCII mode. The records in PAYROL.DAT are 80 characters long; the ASSOCIATE VARIABLE for this file is I. If an error occurs during the execution of this OPEN statement, the OPEN will terminate and control will transfer to the statement labeled 240.

```
CLOSE (UNIT= 3, DISPOSE= 'DELETE')
```

causes the file on unit 3 to be closed and removed if the file is on DECTape or disk.

#### 12.2.2 Summary of OPEN/CLOSE Statement Options

Table 12-1 summarizes the options permitted and required in the OPEN and CLOSE statements and the type of value required by each.

## FILE CONTROL STATEMENTS

Table 12-1  
OPEN/CLOSE Statement Arguments

Argument	Possible Value	Open*	Close*
ACCESS=	'SEQIN', 'SEQOUT', 'SEQINOUT', 'RANDIN', 'RANDOM', 'APPEND', or variable	O	I
ASSOCIATE VARIABLE=	Integer variable	O	I
BLOCK SIZE=	Integer constant or variable	O	I
BUFFER COUNT=	Integer constant or variable	O	I
DENSITY=	Literal constant or variable	O	I
DEVICE=	Literal constant or variable	O	I
DIALOG=	Literal or array or none	O	I
DIRECTORY=	Literal or variable or array	O	O
DISPOSE=	Literal constant or variable	O	O
ERR=	Statement Number	O	OO
FILE=	Literal constant or variable	O	O
FILE SIZE=	Integer constant or variable	O	I
MODE=	Literal constant or variable	O	I
PARITY=	Literal constant or variable	O	I
PROTECTION=	An octal constant or integer variable	O	O
RECORD SIZE=	Integer constant or integer variable	O	I
UNIT=	Integer variable or constant	R	R
VERSION=	Octal constant or variable	O	O

\*  
R = Required  
O = Optional  
I = Ignored



## CHAPTER 13

### FORMAT STATEMENT

#### 13.1 INTRODUCTION

Use FORMAT statements in conjunction with the I/O list of I/O statements during formatted data transfer operations. The FORMAT statements contain field descriptors that, together with the list items of associated I/O statements, specify the forms of the data and data fields that comprise each record.

FORMAT statements may appear almost anywhere in a FORTRAN-10 source program. The only placement restrictions are that they follow PROGRAM, FUNCTION, SUBPROGRAM, or BLOCK DATA statements; and that they precede the END statement. (Refer to Section 2.4.)

You must label FORMAT statements so that I/O statements can reference them.

#### 13.1.1 FORMAT Statement, General Form

The general form of a FORMAT statement follows:

```
k FORMAT(SA1,SA2,...,SAn/SB1,SB2,...,SBn/...)
```

where

k = the required statement label (which can only be referenced by I/O statements).

SA1 through SAn = individual field descriptor sets  
and  
SB1 through SBn

In the foregoing statement form, the individual field descriptors are delimited by commas (,). Field descriptor sets and records are delimited by slashes (/). For example, a FORMAT statement of the form:

```
FORMAT(SA1,SA2/SB1,SB2/SC1,SC2)
```

contains format specifications for three records with each record containing two field descriptor sets.

Adjacent slashes (//) in a FORMAT statement specify that a record is to be skipped during input or is to consist of an empty record on output. For example, a FORMAT statement of the form:

```
FORMAT(SA1,SA2//SB1,SB2)
```

## FORMAT STATEMENT

specifies four records are to be processed; however, the second and third records are to be skipped.

You may represent repeated field descriptors or groups of field descriptors by using a repeat form. Indicate the repetition of a single field descriptor by preceding the descriptor with an integer constant that specifies how many times the descriptor is to be repeated. For example, a FORMAT statement of the form:

```
FORMAT(SA1,SA2,SA3,SA1,SA2,SA3,SA1,SA2,SA3)
```

may be written as

```
FORMAT(3(SA1,SA2,SA3))
```

You may nest the repeat forms of field descriptors to any depth. For example, a FORMAT statement of the form:

```
FORMAT(SA1,SA2,SA2,SA3,SA1,SA2,SA2,SA3)
```

may also be written in the form:

```
FORMAT(2(SA1,2SA2,SA3))
```

The following paragraphs discuss the manner in which you may use the foregoing statement forms and the effect each has on the data involved.

### 13.2 FORMAT DESCRIPTORS

FORMAT statement descriptors describe the record structure of the data, the format of fields within the record, and the conversion, scaling, and editing of data within specific fields. The following descriptors can be used with FORTRAN-10:

Descriptors	Comments
rFw.d rEw.d } rDw.d } rGw.d }	Floating point numeric field descriptors
rIw	Integer field descriptor
rLw	Logical field descriptor
rAw rRw }	Alphanumeric data field descriptor
kHs 'text' }	Alphanumeric data in a FORMAT statement field descriptor
rX Tw }	Field formatting descriptors
nP	Numerical scale factor descriptor
/	Record delimiter
\$	Carriage return suppression for terminal
rOw	Octal field descriptor

## FORMAT STATEMENT

where

- r = an optional unsigned integer representing a repeat count. This option enables a field descriptor to be repeated r times.
- w = an optional integer constant representing the width (total number of characters contained) of the external form of the field being described. All characters, including digits, decimal points, signs, and blanks that are to comprise the external form of the field, must be included in the value of w.
- .d = an optional unsigned integer specifying the number of fractional digits that are to appear in the external representation of the field being described. Note that w must be specified if .d is included in the descriptor.
- k = an unsigned integer specifying the number of characters to be processed during the transfer of alphanumeric data.
- s = represents a string of ASCII (alphanumeric) characters.
- n = a signed integer constant (plus signs are optional).

The characters A, D, E, F, G, H, I, L, O, P, and R indicate the manner of conversion and editing to be performed between the internal (processor) and external representations of the data within a specific field; these characters are referred to as conversion codes. Table 13-1 gives the FORTRAN-10 conversion codes and a brief description of the function of each.

Table 13-1  
FORTRAN-10 Conversion Codes

Code	Function
A	Transfer alphanumeric data
D	Transfer real data with a D exponent(1)
E	Transfer real data with an E exponent(1)
F	Transfer real data without an exponent
G	Transfer integer, real, complex, or logical data
H	Transfer literal data
I	Transfer integer data
L	Transfer logical data
O	Transfer octal data
P	Numerical scaling factor
R	Transfer alphanumeric data

1. An exponent of 0 is assumed if none is given.

The use of commas to delineate format descriptors within a format specification is optional as long as no ambiguity exists. For example,

FORMAT(3X,A2)

can be written as

FORMAT(3XA2)

## FORMAT STATEMENT

Since interpretation of a format specification is left associative, the specification

FORMAT(I22,I5)

can be written as

FORMAT(I22,I5)

However, a comma is required when you wish to specify

FORMAT(I2,2I5)

The following paragraphs provide detailed descriptions of the various types of format descriptors, the manner in which they are written and employed, and their use in FORMAT statements.

### 13.2.1 Numeric Field Descriptors

The forms of the field descriptors used to specify the format and conversion of numeric data follow.

Description	Type of Data Used For
Dw.d	Double-precision data with a D exponent
Ew.d	Real data with an E exponent
Ew.d,Ew.d	For the real and imaginary parts of a complex datum
Fw.d	Real or double-precision data without an exponent
Fw.d,Fw.d	For the real and imaginary parts of a complex datum
Iw	Integer data
Ow	Octal data
Gw.d	Real or double-precision data
Gw	For integer (or logical) data
Gw.d,Gw.d	For the real and imaginary parts of a complex datum

#### NOTE

The G conversion code may be used for all but octal numeric data types.

### Examples

Consider the following program segment:

```
INTEGER I1,I2
REAL R1,R2,R3
DOUBLE PRECISION D1,D2
I1 = 506
I2 = 8
R1 = 506.0
R2 = 18.1
R3 = 506001.0
D1 = 18.0
D2 = -504.0
.
.
```

## FORMAT STATEMENT

Table 13-2 describes the actions performed by several types of formatted WRITE statements on the data given in the foregoing program segment.

Table 13-2  
Action of Field Descriptors On Sample Data

Item	Descriptor Form	Sample Descriptor	WRITE Statement Using the Sample Descriptor	External Form of Sample Field Described	External Appearance of Sample Data
1	Dw.d	D8.2	WRITE(---)D1	Z.nnD nn	0.18D+02
2	Ew.d	E8.2	WRITE(---)R1	Z.nnE nn	0.51E+03
3	Fw.d	F5.2	WRITE(---)R2	aa.nn	18.10
4	Iw	I5	WRITE(---)I1	aaaan	bbb506
5	Iw	I2	WRITE(---)I1	an	**
6	Ow	O5	WRITE(---)I2	nnnnn	00010
7	Gw.d	G8.2	WRITE(---)D2	Z.nnD nn	- .50D+02
8	Gw.d	G8.2	WRITE(---)R3	Z.nnE nn	0.51E+06
9	Gw.d	G8.2	WRITE(---)R2	aa.nn	bbb18.10
10	Gw	G5	WRITE(---)I1	aaaan	bbb506

where:

- a. n represents a numeric character.

- b. Z represents either a - or 0. (Note that if n-d>6, a negative number cannot be output.)

- c. a represents a digit, leading blank (b) or a minus sign depending on the numeric output.

### Notes:

1. In Item 1, the value D1 has only two significant digits and d=2, so no rounding will occur on input.
2. In Item 2, since R1 has 3 significant digits, it is rounded to fit into the specified field.
3. In Item 5, the width (w) part of a format descriptor specifies an exact field that permits no rounding of its contents. If the w specification is too small for the datum to be transferred, asterisks are output to indicate that the transfer was not made.
4. In Item 6, Integer 8 = Octal 10.
5. In Items 8 and 9, the relationship between G and fixed and floating real data is discussed in Paragraph 13.2.3.
6. In Items 1, 2, 3, 7, and 8, the D and E exponent prefixes are optional in the external form of the floating point constants. For example, 1.1E+3 may be written as 1.1+3.

Table 13-3 summarizes the internal and external forms of the data specified by the numeric format conversion code.

## FORMAT STATEMENT

Table 13-3  
Numeric Field Codes

Internal Form	Conversion Code	External Form
Binary floating-point double-precision	D	Decimal floating-point with D exponent
Binary floating-point	E	Decimal floating-point with E exponent
Binary floating-point	F	Decimal fixed-point
Binary integer	I	Decimal integer
Binary word	O	Octal value
One of the following: single-precision binary floating-point, binary integer, binary logical, or binary complex	G	Single-precision decimal floating-point, decimal integer, logical (T or F), or complex (two decimal floating-point numbers), depending upon the internal form

Complex quantities transfer as two independent real quantities. The format specification for complex quantities consists of either two successive real field descriptors or one repeated real field descriptor. For example, the statement

`FORMAT(2E15.4,2(F8.3,F8.5))`

may transfer up to three complex quantities.

The equivalent of the foregoing statement is

`FORMAT(E15.4,E15.4,F8.3,F8.5,F8.3,F8.5)`

### 13.2.2 Interaction of Field Descriptors With I/O Variables

The execution of an I/O statement that specifies a formatted data transfer operation initiates format control. The actions performed by format control depend on information provided by the elements of the I/O statement's list of variables and the field descriptors that comprise the referenced FORMAT statement's format specifications.

In processing each FORMAT controlled I/O statement that has an I/O list, FORTRAN-10 scans the contents of the list and the format specifications in step. Each time another variable or array element name is obtained from the list, the next field specification is obtained from the format specification. If the end of the format specification is reached and more items remain in the list, a new line or record is established and the scan process is restarted, either at the first item in the format specification or, if parenthesized, sets of format specifications exist within the format specification, with the last set within the format specification.

## FORMAT STATEMENT

When the I/O list is exhausted, control proceeds to the next statement in the program, but not before the FORMAT statement is scanned either to its end or to the next variable transfer format descriptor. (That is, the FORMAT statement is scanned past slashes, literal constants, Hollerith field descriptors, and spacing descriptors, but not past data field descriptors.)

A record is terminated by one of the following:

1. a slash in the FORMAT specification
2. the delimiting right parentheses, ), of the FORMAT statement
3. a lack of items in the I/O list
4. a lack of Hollerith or literal field descriptors in the FORMAT statement

On input, an additional record is read only when a single slash, /, is encountered in the FORMAT statement. A record is skipped when two slashes, //, are encountered or a slash is followed by the end of the FORMAT statement. If the FORMAT statement finishes a record by a slash or the end of the FORMAT statement, any data left in the input record is ignored. If the input record is exhausted before the data transfers are completed, the remainder of the transfer is completed as if the record were extended with blanks.

On output, an additional record is written only when a slash, /, is encountered in the FORMAT statement. If a pair of consecutive slashes, //, or a single slash followed by the end of the FORMAT statement is encountered, an empty record is written.

### 13.2.3 G, General Numeric Conversion Code

You may use the G conversion code in field descriptors for the format control of real, double-precision, integer, logical, or complex data.

With the exception of real and double-precision data, the type of conversion performed by a type G field descriptor depends on the type of its corresponding I/O list variable. In the case of real and double-precision data, the kind of conversion performed is a function of the external magnitude of the datum being transferred. Table 13-4 illustrates the conversion performed for various ranges of magnitude (external form) of real and double-precision data.

### 13.2.4 Numeric Fields with Scale Factors

You may add scale factors to D, E, F, and G conversion codes in field descriptors. The scale factor has the form

nP

where n is a signed integer (+ is optional) and P identifies the operation. When used, a scale factor is added as a prefix to field descriptors.

## FORMAT STATEMENT

### Examples

```
-2PF10.5
1PE8.2
```

When you add a scale factor to an type F field descriptor (or type G if the external field is a fixed point decimal) a power of 10 is specified so that

External Form of Number = (Internal Form)\*10\*\* (scale factor)

For example, assuming the data involved to be the real number 26.451, the field descriptor

F8.3

produces the external field

26.451

**Table 13-4**  
Descriptor Conversion of Real and Double-Precision  
Data According to Magnitude

Magnitude of Data in External Form (M)	Equivalent Method of Conversion Performed
0.1 M≤1	F(w-4).d,4X
1 M≤10	F(w-4).(d-1),4X
.	.
.	.
.	.
10d-2 M≤10d-1	F(w-4).1,4X
10d-1 M≤10d	F(w-4).0,4X
ALL OTHERS	Ew.d
NOTE	
<p>In all numeric field conversions, the field width (w) you specify should be large enough to include the decimal point, sign, and exponent character in addition to the number of digits. If the specified width is too small to accommodate the converted number, the field will be filled with asterisks (*). If the number converted occupies fewer character positions than specified by w, it will be right-justified in the field and leading blanks will be used to fill the field.</p>	

## FORMAT STATEMENT

The addition of the scale factor of -1P

-1PF8.3

produces the external field

b002.645

When you add a scale factor to D, E, and G (external field not a decimal fixed-point) type field descriptors, it multiplies the number by the specified power of ten and the exponent is changed accordingly.

In input operations, type F (and type G, if the external field is decimal fixed-point) conversions are the only ones affected by scale factors.

When you specify no scale factor, it is understood to be zero. Once you specify a scale factor, however, it holds for all subsequent types D, E, F, and G field descriptors within the same format specification unless another scale factor is specified. A scale factor is reset to zero when you specify a scale factor of zero. Scale factors have no effect on I and O type field descriptors.

When you add a scale factor to a D or E field descriptor, it specifies a power of 10 so that the external form of the number has its mantissa multiplied by the specified power of 10; its exponent is adjusted accordingly.

For example, assuming the data involved to be the real number 12.493, the field descriptor

E11.3

produces the external field

b00.125E+02

The addition of the scale factor 2P

2PE11.3

produces the external field

bb12.49E+00

With a scale factor of zero, the number of significant digits printed by a format of the form

Ew.d

or

Dw.d

is the number of digits to the right of the decimal point.

For a negative scale factor nP, for  $d < n < 0$ , there will be  $ABS(n)$  leading zeros and  $d-ABS(n)$  significant digits after the decimal point, for a total of d digits after the decimal point. If  $n = d$ , there will be d insignificant digits (zeros) to the right of the decimal point.

If the scale factor nP is positive, for  $0 < n < d+2$  there will be n significant digits to the left of the decimal point and  $d-n+1$  significant digits to the right of the decimal point (for a total of

## FORMAT STATEMENT

$d+1$  significant digits). If  $n \geq d+2$ , there will be  $d+1$  significant digits and  $n-d-1$  insignificant trailing zeros on the left of the decimal point.

If the data to be printed is 12.493, these formats produce results as follows:

FORMAT	OUTPUT	SIGNIFICANT DIGITS	REASON
E15.3	bbbbbb0.125E+02	3	$n=0$
1PE15.3	bbbbbb1.249E+01	4	$n < d+2$
-1PE15.3	bbbbbb.012E+03	3	$-d < n$
2PE15.3	bbbbbb12.49E+00	4	$n < d+2$
-3PE15.3	bbbbbb0.000E+05	0	$n - d$
4PE15.3	bbbbbb1249.E-02	4	$n < d+2$
6PE15.3	bbbb124900.E-04	4	$n + d+2$

### 13.2.5 Logical Field Descriptors

You may transfer logical data under format control in a manner similar to numeric data transfer by use of the field descriptor

Lw

where L is the control character and w is an integer specifying the field width. The data is transmitted as the value of a corresponding logical variable in the associated input/output list.

On input, the first non-blank character in the logical data field must be T or F, the value of the logical variable is stored in the list variable as true or false, respectively. If the entire input data field is blank or empty, a value of false is stored.

On output, w minus 1 blanks followed by T or F will be output if the value of the logical variable is true or false, respectively.

### 13.2.6 Variable Numeric Field Widths

Several of the conversion codes are acceptable in FORMAT statements without field width specifications, the w.d portion of the specification so that can be omitted(1).

On input, the conversion codes D, E, F, G, I, L, and O are acceptable without field width specifications. The field begins with the first non-blank character encountered and ends with the first illegal character in the given field. (Blanks and tabs also terminate a field.) Note that for conversion code L (logical data), all consecutive alphabets following a T (true) or an F (false) are considered part of the field and are ignored. In succeeding fields the input stream is scanned until a non-blank character is encountered. If the character is a comma (,), the next field is skipped, and the following input field begins with the character following the comma. Any character other than a comma is assumed to be the first character in the next input field. Null fields are

---

1. If d is given, w must also be specified.

## FORMAT STATEMENT

denoted by successive commas optionally separated by blanks or tabs. A null field is equivalent to a fixed-field input of blanks. For example, the source code

```
READ 1, X, Y, Z, L, I, J  
1 FORMAT (3F, L, I, A3)
```

with data as follows

```
,1.0E+5,,TRUEXXX1,ABC
```

results in

```
X = 0.0  
Y = 1.0E+5  
Z = 0.0  
L = TRUE  
I = 1  
J = 'ABC'
```

Note that if a comma is included in the input data after the XXX1 and before the blanks, i.e., the data is

```
,1.0E+5 , , TRUEXXX1,ABC
```

then J = ' '

On output, the format codes A, D, E, F, G, I, L, O, and R are acceptable without field width specifications. The following defaults are assumed:

Format Code	Assumed Default for KA10	Assumed Default for KI10, KL10
A single-precision	A5	A5
A double-precision	A10	A10
D	D25.16	D25.18
E	E15.7	E15.7
F	F15.7	F15.7
G single-precision	G15.7	G15.7
G double-precision	G25.16	G25.18
I	I15	I15
L	L15	L15
O	O15	O15
R single-precision	R5	R5
R double-precision	R10	R10

### 13.2.7 Alphanumeric Field Descriptors

You may accomplish the formatted transfer of alphanumeric data in a manner similar to the formatted transfer of numeric data by use of the field descriptors Aw and Rw, where A and R are the control characters and w is the number of characters in the field.

The A and R descriptors both transfer alphanumeric data into or from a variable in an input/output list depending on the I/O operation. A list variable may be of any type. For example,

```
READ (6,5) V  
5 FORMAT (A4)
```

## FORMAT STATEMENT

causes four alphanumeric characters to be read from unit 6 and stored in the variable V.

The A descriptor deals with variables containing left-justified, blank-filled characters; the R descriptor deals with variables containing right-justified, zero-filled characters. The following paragraphs summarize the result of alphanumeric data transfer (both internal and external representations) using the A and R descriptors. These paragraphs assume that w represents the field width and m represents the total number of characters possible in the variable. Double precision variables contain 10 characters ( $m=10$ ); all other variables contain 5 ( $m=5$ ).

### A Descriptor

1. INPUT, where  $w \geq m$  -- The rightmost m characters of the field are read in and stored left-justified and blank-filled in the associated variable.
2. INPUT, where  $w < m$  -- All w characters are read in and stored left-justified and blank-filled in the associated variable.
3. OUTPUT, where  $w \geq m$  -- m characters are output and right-justified in the field. The remainder of the field is blank-filled.
4. OUTPUT, where  $w < m$  -- The left most w characters of the associated variable are output.

### R Descriptor

1. INPUT, where  $w \geq m$  -- The right most m characters of the field are read in and stored right-justified, zero-filled in the associated variable.
2. INPUT, where  $w < m$  -- All w characters are read in and stored right-justified, zero-filled in the associated variable.
3. OUTPUT, where  $w \geq m$  -- m characters are output and right justified in the field. The remainder of the field is blank filled.
4. OUTPUT, where  $w < m$  -- The right most w characters of the associated variable are output.

### 13.2.8 Transferring Alphanumeric Data

You may transmit alphanumeric data directly into or from the FORMAT statement by two different methods: H-conversion, or the use of single quotes, i.e., a literal field descriptor.

In H-conversion, the alphanumeric string is specified in the form nH, where H is the control character and n is the total number of characters (including blanks) in the string. For example, you may use the following statement sequence to print the words PROGRAM COMPLETE on the device LPT:

```
PRINT 101
101 FORMAT (17H\PROGRAM\COMPLETE)
```

## FORMAT STATEMENT

Read and write operations of this type are initiated by I/O statements that reference a format statement and a logical device, but do not contain an I/O list (see preceding example).

Write transfers from a FORMAT statement cause the contents of the statement field descriptor to be output to a specified logical device. The contents of the field descriptor, however, remain unchanged.

Read transfers with a FORMAT statement cause the contents of the field descriptors involved to be replaced by the characters input from the specified logical device.

Alphanumeric data is stored in a field descriptor left-justified. If the data input into a field has fewer characters than the field, trailing blanks are added to fill the field. If the data input is larger than the field of the descriptor, the excess rightmost characters are lost.

### Examples

```
WRITE (1,101)
101 FORMAT (17HPROGRAMCOMPLETE)
```

cause the string PROGRAM COMPLETE to be output to the file on device 1.

Assuming the string START on device 1, the sequence

```
READ (1,101)
101 FORMAT (17HPROGRAMCOMPLETE)
```

would change the contents of statement 101 to

```
101 FORMAT (17HSTARTXXXXXXXXXX)
```

The foregoing functions may also be accomplished by a literal field descriptor consisting of the desired character string enclosed within apostrophes, i.e., 'string'. For example, you may use the descriptors

```
101 FORMAT (17HPROGRAMCOMPLETE)
```

and

```
101 FORMAT ('PROGRAMCOMPLETE')
```

in the same manner.

The result of literal conversion is the same as H-conversion. On input, the characters between the apostrophes are replaced by input characters, and on output, the characters between the apostrophes (including blanks) are written as part of the output data.

An apostrophe character within a literal field should be represented by two successive apostrophe marks; otherwise, the statement containing the field will not compile. For example, the statement sequence

```
50 FORMAT ('DON''T')
PRINT 50
```

will compile and will cause the word DON'T to be output on the line printer. The statement

```
50 FORMAT ('DON'T')
```

however, will cause a compile error.

## FORMAT STATEMENT

### 13.2.9 Mixed Numeric and Alphanumeric Fields

You may place an alphanumeric field descriptor among other fields of the format. For example, you may use the statement:

```
FORMAT (I4,7HFORCE=F10.5)
```

to output the line:

```
17.68901
```

You may omit the separating comma after an alphanumeric format field, as shown in the foregoing statement.

When you omit a comma delimiter from a format specification, format control associates as much information as possible with the leftmost of the two field descriptors.

### 13.2.10 Multiple Record Specifications

To handle a group of input/output records where different records have different field descriptors, use a slash to indicate a new record. For example, the statement

```
FORMAT (308/I5,2F8.4)
```

is equivalent to

```
FORMAT (308)
```

for the first record, and

```
FORMAT (I5,2F8.4)
```

for the second record.


You may omit separating commas when you use a slash. When n slashes appear at the end or beginning of a format, n blank records will be written on output or skipped on input. When n slashes appear in the middle of a format, n-1 blank records are written on output or n-1 records skipped on input.

Both the slash and the closing parenthesis at the end of the format indicate the termination of a record. If the list of an input/output statement dictates that the transmission of data is to continue after the closing parenthesis of the format is reached, the format is repeated, starting with:

1. that group repeat specification terminated by the last right parenthesis of the next lower level group, or
2. level zero if no higher level group exists.

Thus, the statement

```
FORMAT (F7.2,(2(E15.5,E15.4),I7))
```



## FORMAT STATEMENT

causes the format

2(E15.5,E15.4),I7

to be used after the first record.

As a further example, consider the statement

FORMAT (F7.2/(2(E15.5,E15.4),I7))

The first record has the format

F7.2

and the next 5 records have the format

2(E15.5,E15.4),I7

### 13.2.11 Record Formatting Field Descriptors

You may use two field descriptors, Tw and nx, to position data within a record.

You may use the field descriptor Tw to specify the character position (external form) in which a record begins. In the Tw field descriptor, the letter T is the control character, and w is an unsigned integer constant that specifies the character position, in a FORTRAN-10 record, where the transfer of data is to begin. When the output is printed, w corresponds to the (w-1)th print position, since the first character of the output buffer is a forms control character and is not printed. It is recommended that the first field specification of the output format be 1X, except where a forms control character is used.

#### NOTE

Two successive T field specifications will result in the second field overwriting the first field.

#### Examples

The statement sequence

```
PRINT 2
2 FORMAT (T50,'BLACK',T30,'WHITE')
```

causes the following line to be printed

WHITE  
↑  
(print position 29)                    BLACK  
↑  
(print position 49)

The statement sequence

```
1 FORMAT (T35,'MONTH')
READ (2,1)
```

## FORMAT STATEMENT

causes the first 34 characters of the input data associated with logical unit 2 to be skipped, and the next five characters to replace the characters M, O, N, T, and H in storage. If an input record containing

ABC~~123~~XYZ

is read with the format specification

10 FORMAT (T7,A3,T1,A3)

then the characters XYZ and ABC are read in that order.

You may use the field descriptor nX to introduce blanks into output records or to skip characters of input records. The letter X specifies the operation, and n is a positive integer that specifies the number of character positions to be either made blanks (output) or skipped (input).

Example

The statement

FORMAT (5H~~1~~STEP,I5,10X,2HY=,F7.3)

may be used to print the line

STEP~~123~~28~~123~~~~123~~~~123~~~~123~~~~123~~Y=-3.872

### 13.2.12 \$ Format Descriptor

A \$ format descriptor at the end of an output FORMAT is used to suppress the carriage return at the end of the current record. It is mainly used on terminal output but will work on non-terminal devices. A \$ format descriptor is ignored in input FORMATS and has no effect if embedded in an output FORMAT. The \$ format descriptor must be the next format descriptor to be processed when the corresponding output list is exhausted for the \$ descriptor to have the defined effect.

### 13.3 CARRIAGE CONTROL CHARACTERS FOR PRINTING ASCII RECORDS

You may use the first character of an ASCII record to control the spacing operations of the line printer or Teletype terminal printer unit on which the record is being printed. Specify the control character desired by beginning the FORMAT field specification for the ASCII record to be output with 1Ha.., where a is the desired control character. Table 13-5 describes the control characters permitted in FORTRAN-10 and the effect each has on the printing device.

## FORMAT STATEMENT

Table 13-5  
FORTRAN-10 Print Control Characters

FORTRAN Character	Printer Character	Octal Value	Effect
space	LF	012	Skip to next line with form feed after 60 lines
0 zero	LF,LF	012	Skip a line
1 one	FF	014	Form feed - go to top of next page
+ plus			Suppress skipping - overprint the line
* asterisk	DC3	023	Skip to next line with no form feed
- minus	LF,LF,LF	012	Skip two lines
2 two	DLE	020	Space 1/2 of a page
3 three	VT	013	Space 1/3 of a page
/ slash	DC4	024	Space 1/6 of a page
. period	DC2	022	Triple space with a form feed after every 20 lines printed
, comma	DC1	021	Double space with a form feed after every 30 lines printed
NOTE			
Printer control characters DLE, DC1, DC2, DC3, and DC4 affect only the line printer.			



## CHAPTER 14

### DEVICE CONTROL STATEMENTS

#### 14.1 INTRODUCTION

You may use the following device control statements in FORTRAN-10 source programs:

1. REWIND
2. UNLOAD
3. BACKSPACE(1)
4. ENDFILE
5. SKIPRECORD(1)
6. SKIPFILE
7. BACKFILE

The general form of the foregoing device control statements is

keyword u  
keyword (u)

where

keyword is the statement name  
u is the FORTRAN-10 logical device number (Chapter 10,  
Table 10-1)

The operations performed by the device control statement are normally used only for magnetic tape devices (MTA). In FORTRAN-10, however, the device control operations are simulated for disk devices.

The following paragraphs describe the form and use of the device control statements.

#### 14.2 REWIND STATEMENT

Form: REWIND u

Use: Move the file contained by device u to its initial (load) point. If the medium is already at its load point, this statement has no effect. Subsequent READ

---

1. The results of these commands are unpredictable when used on list-directed and NAMELIST-controlled data.

## DEVICE CONTROL STATEMENTS

or WRITE statements that reference device u will transfer data to or from the first record located on the medium mounted on device u.

Example: REWIND 16

### 14.3 UNLOAD STATEMENT

Form: UNLOAD u

Use: Move the medium contained on device u past its load point until it has been completely rewound onto the source reel.

Example: UNLOAD 16

### 14.4 BACKSPACE STATEMENT

Form: BACKSPACE u

Use: Move the medium contained on device u to the start of the record that precedes the current record. If the preceding record prior to execution of this statement was an endfile record, the endfile record becomes the next record after execution. If the current record is the first record of the file, this statement has no effect.

#### NOTE

You cannot use this statement for files set up for random access, list-directed, or NAMELIST-controlled I/O operations.

Example: BACKSPACE 16

### 14.5 END FILE STATEMENT

Form: END FILE u

Use: Write an endfile record in the file located on device u. The endfile record defines the end of the file that contains it. If an endfile record is reached during an I/O operation initiated by a statement that does not contain an END= option, the operation of the current program is terminated.

Example: END FILE 16

## DEVICE CONTROL STATEMENTS

### 14.6 SKIP RECORD STATEMENT

Form: SKIP RECORD u

Use: In accessing the file located on device u, skip the record immediately following the current (last accessed) record.

#### NOTE

You cannot use this statement for files set up for random access, list-directed, or NAMELIST-controlled I/O operations.

Example: SKIP RECORD 16

### 14.7 SKIP FILE STATEMENT

Form: SKIP FILE u

Use: In accessing the medium located on unit u, skip the file immediately following the current (last accessed) file. If the number of SKIP FILE operations specified exceeds the number of following files available, an error will occur.

Example: SKIP FILE 01

### 14.8 BACKFILE STATEMENT

Form: BACKFILE u

Use: Move the medium mounted on device u to the start of the file that precedes the current (last accessed) file.

If the number of BACKFILE operations performed exceeds the number of preceding files, completion of the last operation will move the medium to the start of the first file on the medium.

Example: BACKFILE 20

### 14.9 SUMMARY OF DEVICE CONTROL STATEMENTS

Table 14-1 summarizes the form and use of the FORTRAN-10 device control statements

## DEVICE CONTROL STATEMENTS

Table 14-1  
Summary of FORTRAN-10 Device Control Statements

Statement Form	Use
REWIND u	Rewind medium to its load point
UNLOAD u	Rewind medium onto its source reel
END FILE u	Write an endfile record into the current file
SKIP RECORD u	Skip the next record
SKIP FILE u	Skip the next file
BACKFILE u	Move medium backwards one file
BACKSPACE u	Move medium back one record

## CHAPTER 15

### SUBPROGRAM STATEMENTS

#### 15.1 INTRODUCTION

Procedures you use repeatedly in a program may be written once and then referenced each time you need the procedure. Procedures that may be referenced are either internal (written and contained within the program in which they are referenced) or external (self-contained executable procedures that may be compiled separately). The kinds of FORTRAN-10 procedures that may be referenced are:

1. statement functions,
2. intrinsic functions (FORTRAN-10 defined functions),
3. external functions, and
4. subroutines.

The first three of the foregoing categories are referred to collectively as functions or function procedures; procedures of the last category are referred to as subroutines or subroutine procedures.

#### 15.1.1 Dummy and Actual Arguments

Since you may reference subprograms at more than one point throughout a program, many of the values used by the subprogram may be changed each time it is used. Dummy arguments in subprograms represent the actual values to be used, which are passed to the subprogram when it is called.

Functions and subroutines use dummy arguments to indicate the type of the actual arguments they represent and whether the actual arguments are variables, array elements, arrays, subroutine names, or the names of external functions. Each dummy argument must be used within a function or subroutine as if it were a variable, array, array element, subroutine, or external function identifier. Dummy arguments are given in an argument list associated with the identifier assigned to the subprogram; actual arguments are normally given in an argument list associated with a call made to the desired subprogram. (Examples of argument lists are given in the following paragraphs.)

The position, number, and type of each dummy argument in a subprogram list must agree with the position, number, and type of each argument list of the subprogram reference.

## SUBPROGRAM STATEMENTS

Dummy arguments may be:

1. variables,
2. array names,
3. subroutine identifiers,
4. function identifiers, or
5. statement label identifiers that are denoted by the symbol "\*", "\$", or "&".

When you reference a subprogram, its dummy arguments are replaced by the corresponding actual arguments supplied in the reference. All appearances of a dummy argument within a function or subroutine are related to the given actual arguments. Except for subroutine identifiers and literal constants, a valid association between dummy and actual arguments occurs only if both are of the same type; otherwise, the results of the subprogram computations will be unpredictable. Argument association may be carried through more than one level of subprogram reference if a valid association is maintained through each level. The dummy/actual argument associations established when a subprogram is referenced are terminated when the desired subprogram operations are completed.

The following rules govern the use and form of dummy arguments:

1. The number and type of the dummy arguments of a procedure must be the same as the number and type of the actual arguments given each time the procedure is referenced.
2. Dummy argument names may not appear in EQUIVALENCE, DATA, or COMMON statements.
3. A variable dummy argument should have a variable, an array element identifier, an expression, or a constant as its corresponding argument.
4. An array dummy argument should have either an array name or an array element identifier as its corresponding actual argument. If the actual argument is an array, the length of the dummy array should be less than or equal to that of the actual array. Each element of a dummy array is associated directly with the corresponding elements of the actual array.
5. A dummy argument representing a subroutine identifier should have a subroutine name as its actual argument.
6. A dummy argument representing an external function must have an external function as its actual argument.
7. A dummy argument may be defined or redefined in a referenced subprogram only if its corresponding actual argument is a variable. If dummy arguments are array names, then elements of the array may be redefined.

Additional information regarding the use of dummy and actual arguments is given in the description of how subprograms are defined and referenced.

## SUBPROGRAM STATEMENTS

### 15.2 STATEMENT FUNCTIONS

Statement functions define an internal subprogram in a single statement. The general form of a statement function is:

name(arg1,arg2,...,argn)=E

where

name           is a name you assign that consists of one to six characters. The name you use must conform to the rules for symbolic names given in Section 3.3.

The type of a statement function is determined either by the first character of its name or by it being explicitly declared in a type statement.

(arg1...argn) represents a list of dummy arguments.

E               is an arbitrary expression.

The expression E of a statement function may be any legitimate arithmetic expression that may use the given dummy arguments and indicates how they are combined to obtain the desired value. You may use the dummy arguments as variables or indirect function references; but you cannot use them as arrays. The dummy argument names bear no relation to their use outside the context of the statement function except for their data type. The expression may reference FORTRAN-10 defined functions (Paragraph 15.3) or any other defined statement function, or call an external function. It may not reference any function that directly or indirectly references the given statement function or any subprogram in the chain of references. That is, recursive references are not allowed. Statement functions produce only one value, the result of the expression that it contains. A statement function cannot reference itself.

You must define all statement functions within a program unit before the first executable statement of the program unit. When used, the statement function name must be followed by an actual argument list enclosed within parentheses and may appear in any arithmetic or logical expression.

Examples:

```
SSQR(K)=(K*(K+1)*2*K+1)/6
ACOSH(X)=(EXP(X/A)+EXP(-X/A))/2.0
```

### 15.3 INTRINSIC FUNCTIONS (FORTRAN-10 DEFINED FUNCTIONS)

Intrinsic functions are subprograms that are defined and supplied by FORTRAN-10. You can reference an intrinsic function by using its assigned name as an operand in an arithmetic or logical expression. Table 15-1 describes the names of the FORTRAN-10 intrinsic functions, the type of the arguments that each accepts, and the function it performs. These names always refer to the intrinsic function unless they are preceded by an asterisk (\*) or ampersand (&) in an EXTERNAL statement, declared in a conflicting explicit type statement, or are specified as a routine dummy parameter.

## SUBPROGRAM STATEMENTS

## NOTE

Octal constants may only be used as actual input to an intrinsic function when the function expects octal arguments.

Table 15-1  
Intrinsic Functions (FORTRAN-10 Defined Functions)

Function	Mnemonic	Definition	Number of Arguments	Type of Function	
				Argument	Type of Function
Absolute value: Real Integer Double-precision Complex to real	ABS* TABS* DABS* CABS	arg arg arg $c = (x^{**} 2 + y^{**} 2)^{**} (1/2)$	1 1 1 1	Real Integer Double Complex	Real Integer Double Real
Conversion: Integer to real Real to integer	FLOAT** IFIX**	Sign of arg * largest integer $\leqslant \text{larg}$	1 1	Integer Real	Real Integer
Double to real Real to double	SNGL DBLE*		1 1	Double Real	Real Double

\* In line functions.

\*\* In line functions on K110 and KL10 only.

## SUBPROGRAM STATEMENTS

Table 15-1 (Cont.)  
Intrinsic Functions (FORTRAN-10 Defined Functions)

Function	Mnemonic	Definition	Number of Arguments	Type of Function
			Argument	
Integer to double Complex to real (obtain real part) Complex to real (obtain imaginary (part) Real to complex	DFLOAT REAL*		1 1 1	Double Real Real
	AIMAG			Complex
	Cmplx*	c=Arg + i*Arg	2	Real Complex
Truncation: Real to real	AINT	Sign of arg* largest integer $\leq  arg $	1	Real Real
Real to integer Double to integer	INT* IDINT		1 1	Integer Integer
Remaindering: Real Integer Double - precision	AMOD MOD* DMOD	{The remainder when Arg 1 is divided by Arg 2}	2 2 2	Real Integer Double
Maximum value:	AMAX0 AMAX1* MAX0* MAX1 DMAX1	{Max (Arg1, Arg2, ...)}	>1 >1 >1 >1	Integer Real Integer Real Double

\* In line functions.

## SUBPROGRAM STATEMENTS

Table 15-1 (Cont.)  
Intrinsic Functions (FORTRAN-10 Defined Functions)

Function	Mnemonic	Definition	Number of Arguments	Type of Function	
				Argument	
Minimum Value:	AMIN0 AMIN1* MIN0* MIN1 DMIN1	{Min(Arg1,Arg2,...)}	>1	Integer Real Integer Real Double	Real Real Integer Integer Double
Transfer of Sign:	SIGN* ISIGN DSIGN	{Sgn(Arg2) *  Arg1 }	>1	Real Integer Double	Real Integer Double
Positive Difference:	DIM* IDIM	{Arg1-Min(Arg1,Arg2)}	2	Real Integer	Real Integer

\* In line functions.

15.4 EXTERNAL FUNCTIONS

External functions are function subprograms that consist of a FUNCTION statement followed by a sequence of FORTRAN-10 statements that define one or more desired operations; subprograms of this type may contain one or more RETURN statements and must be terminated by an END statement. Function subprograms are independent programs that may be referenced by other programs.

The FUNCTION statement that identifies an external function has the form:

```
type FUNCTION name (arg1,arg2,...,argn)
```

where

type	is an optional type specification as described in Section 6.3. These include INTEGER, REAL, DOUBLE PRECISION, COMPLEX or LOGICAL (plus the optional size modifier, *n, for compatibility with other manufacturers.)
name	is the name you assign to the function. The name may consist of from one to six characters, the first of which must be alphabetic. You may include the optional size modifier (*n) with the name if the type is specified. (Refer to Section 6.3.)
(arg1,...,argn)	is a list of dummy arguments.

If you omit type in the FUNCTION statement, the type of the function may be assigned, by default, according to the first character of its name, or may be specified by an IMPLICIT statement or by an explicit statement given with the subprogram itself.

Note that if you want to use the same name for a user-defined function as the name of a FORTRAN-10 defined function (library basic external function), the desired name must be declared in an EXTERNAL statement and prefixed by an asterisk (\*) or ampersand (&) in the referencing routine. (Refer to Section 6.7 for a description of the EXTERNAL statement.)

The following rules govern the structuring of a FUNCTION subprogram:

1. You must use the symbolic name assigned a FUNCTION subprogram as a variable name in the subprogram. During each execution of the subprogram, this variable must be defined and, once defined, may be referenced or redefined. The value of the variable at the time of execution on any RETURN statement is the value of the subprogram.

## NOTE

A RETURN statement returns control to the calling statement that initiated the execution of the subprogram. See Section 15.6 for a description of this statement.

## SUBPROGRAM STATEMENTS

2. You may not use the symbolic name of a FUNCTION subprogram in any nonexecutable statement in the subprogram except in the initial FUNCTION statement or a type statement.
3. Dummy argument names may not appear in any EQUIVALENCE, COMMON, or DATA statement used within the subprogram.
4. The function subprogram may define or redefine one or more of its arguments so as to effectively return results in addition to the value of the function.
5. The function subprogram may contain any FORTRAN-10 statement except BLOCK DATA, SUBROUTINE PROGRAM, another FUNCTION statement, or any statement that directly or indirectly references the function being defined or any subprogram in the chain of subprograms leading to this function.
6. The function subprogram should contain at least one RETURN statement and must be terminated by an END statement. The RETURN statement signifies a logical conclusion of the computation made by the subprogram and returns the computed function value and control to the calling program. A subprogram may have more than one RETURN statement.

The END statement specifies the physical end of the subprogram and implies a return.

### 15.4.1 Basic External Functions (FORTRAN-10 Defined Functions)

FORTRAN-10 contains a group of predefined external functions that are called basic functions. Table 15-2 describes each basic function, its name, and its use. These names always refer to the basic external functions unless declared in an EXTERNAL or conflicting explicit type statement.

### 15.4.2 Generic Function Names

The compiler generates a call to the proper FORTRAN-10 defined function, depending on the type of the arguments, for the following generic function names:

ABS  
AMAX1  
AMIN1  
ATAN  
ATAN2  
COS  
INT  
MOD  
SIGN  
SIN  
SQRT  
EXP  
 ALOG  
 ALOG10

In the following example

K=ABS(I)

## SUBPROGRAM STATEMENTS

the type of I determines which function is called. If I is an integer, the compiler generates a call to the function IABS. If I is real, the compiler generates a call to the function ABS. If I is double precision, the compiler generates a call to the function DABS.

The function name loses its generic properties if it appears in an explicit type statement, if it is specified as a dummy routine parameter, or if it is prefixed by "\*" or "&" in an EXTERNAL statement. When a generic function name that was specified unprefixed in an EXTERNAL statement is used as a routine parameter, it is assumed to reference a FORTRAN-10 defined function of the same name, or if none exists, a user-defined function. Note that IMPLICIT statements have no effect upon the data type of generic function names unless the name has been removed from its class by use of an EXTERNAL statement.

### 15.5 SUBROUTINE SUBPROGRAMS

A subroutine is an external computational procedure that is identified by a SUBROUTINE statement and may or may not return values to the calling program. The SUBROUTINE statement used to identify a subprogram of this type has the form:

```
SUBROUTINE name(arg1,arg2,...,argn)
```

where

name               is the symbolic name of the subroutine to be defined.

(arg1,...,argn)   is an optional list of dummy arguments.

**SUBPROGRAM STATEMENTS**

Table 15-2  
Basic External Functions (FORTRAN-10 Defined Functions)

Function	Mnemonic	Definition	Number of Arguments	Type of Argument	Type of Function
Exponential:					
Real	EXP	{ Arg }	1	Real	Real
Double	DEXP		1	Double	Double
Complex	CEXP		1	Complex	Complex
Logarithm:					
Real	ALOG	ln (Arg)	1	Real	Real
Double	ALOG10	log (Arg)	1	Real	Real
Complex	DLOG	ln (Arg)	1	Double	Double
	DLOG10	log (Arg)	1	Double	Double
	CLOG	ln (Arg)	1	Complex	Complex
Square Root:					
Real	SQRT*	(Arg) ** 1/2	1	Real	Real
Double	DSQRT	(Arg) ** 1/2	1	Double	Double
Complex	CSQRT	(Arg) ** 1/2	1	Complex	Complex
Sine:					
Real (radians)	SIN*		1	Real	Real

\*Generic functions

**SUBPROGRAM STATEMENTS**

Table 15-2 (Cont.)  
Basic External Functions (FORTRAN-10 Defined Functions)

Function	Mnemonic	Definition	Number of Arguments	Type of Function
			Argument	
Real (degrees) Double (radians) Complex	SIND DSIN CSIN	{sin(Arg)}	1 1 1	Real Double Complex
Cosine: Real (radians) Real (degrees) Double (radians) Complex	COS* COSD DCOS CCOS	{cos(Arg)}	1 1 1	Real Real Double Complex
Hyperbolic: Sine Cosine Tangent	SINH COSH TANH	sinh(Arg) cosh(Arg) tanh(Arg)	1 1 1	Real Real Real
Arc sine	ASIN	asin(Arg)	1	Real
Arc cosine	ACOS	acos(Arg)	1	Real
Arc tangent	ATAN*	atan(Arg)	1	Real
Real Double Two REAL arguments	DATAN ATAN2*	datan(Arg) atan(Arg1/Arg2)	1 2	Double Real
* Generic functions				

**SUBPROGRAM STATEMENTS**

Table 15-2 (Cont.)  
Basic External Functions (FORTRAN-1C Defined Functions)

Function	Mnemonic	Definition	Number of Arguments	Type of Argument	Type of Function
Two DOUBLE arguments Complex Conjugate	DATAN2	atan(Arg1/Arg 2) Arg=X+iY, CONJG=X-iY	2	Double	Double
	CONJG		1	Complex	Complex
Random Number	RAN	Result is a random number in the range of 0 to 1.0	1 Dummy Argument	Integer, Real, Double, or	Real
Remainder of time limit	TIM2GO	Remainder of time limit for job in seconds	1 Dummy Argument	Integer, Real, Double, or Complex	Real

## SUBPROGRAM STATEMENTS

The following rules control the structuring of a subroutine subprogram:

1. You may not use the symbolic name of the subprogram in any statement within the defined subprogram except the SUBROUTINE statement itself.
2. You may not use the given dummy arguments in an EQUIVALENCE, COMMON, or DATA statement within the subprogram.
3. The subroutine subprogram may define or redefine one or more of its arguments so as to effectively return results.
4. The subroutine subprogram may contain any FORTRAN-10 statement except BLOCK DATA, FUNCTION, another SUBROUTINE statement, or any statement that either directly or indirectly references the subroutine being defined or any of the subprograms in the chain of subprogram references leading to this subroutine.
5. Dummy arguments that represent statement labels may be either an \*, \$, or &.
6. The subprogram should contain at least one RETURN statement and must be terminated by an END statement. The RETURN statements indicate the logical end of a computational routine; the END statement signifies the physical end of the subroutine.
7. Subroutine subprograms may have as many entry points as desired (see description of ENTRY statement given in Section 15.7).

### 15.5.1 Referencing Subroutines (CALL Statement)

You must reference subroutine subprograms by using a CALL statement of the following form:

CALL name(arg1,arg2,...,argn)

where

name is the symbolic name of the desired subroutine subprogram.

(arg1,...,argn) is an optional list of actual arguments. If the list is included, the given actual arguments must agree in order, number, and type with the corresponding dummy arguments given in the defining SUBROUTINE statement.

The use of literal constants is an exception to the rule requiring agreement of type between dummy and actual arguments. An actual argument in a CALL statement may be:

1. a constant
2. a variable name

## SUBPROGRAM STATEMENTS

3. an array element identifier
4. an array name
5. an expression
6. the name of an external subroutine, or
7. a statement label.

Example:

The subroutine

```
SUBROUTINE MATRIX(I,J,K,M,*)
.
.
.
END
```

may be referenced by

```
CALL MATRIX(10,20,30,40,$101)
```

### 15.5.2 FORTRAN-10 Supplied Subroutines

FORTRAN-10 provides you with an extensive group of predefined subroutines. Table 15-3 gives the descriptions and names of these predefined subroutines.

### 15.6 RETURN STATEMENT AND MULTIPLE RETURNS

The RETURN statement causes control to be returned from a subprogram to the calling program unit. This statement has the form:

```
RETURN (standard return)
```

or

```
RETURN e (multiple returns)
```

where e represents an integer constant, variable, or expression. The execution of this statement in the first of the foregoing forms (i.e., standard return) causes control to be returned to the statement of the calling program that follows the statement that called the subprogram.

The multiple returns form of this statement, i.e., RETURN e, enables you to select any labeled statement of the calling program as a return point. When the multiple returns form of this statement is executed, the assigned or calculated value of e specifies that the return is to be made to the eth statement label in the argument list of the calling statement. The value of e should be a positive integer that is equal to or less than the number of statement labels given in the argument list of the calling statement. If e is less than 1 or is larger than the number of available statement labels, a standard return operation is performed.

## SUBPROGRAM STATEMENTS

### NOTE

A dummy argument for a statement label  
must be either a \*, \$, or & symbol.

You may use any number of RETURN (standard return) statements in any subprogram. The use of the multiple returns form of the RETURN statement, however, is restricted to subroutine subprograms. The execution of a RETURN statement in a main program will terminate the program.

#### Example

Assume the following statement sequence in a main program:

•  
•  
•  
•  
CALL EXAMP(1,\$10,K,\$15,M,\$20)  
GO TO 101

•  
•  
•  
•  
10 .....  
•  
•  
•  
•

15 .....  
•  
•  
•  
•

20 .....  
•  
•  
•  
•

## SUBPROGRAM STATEMENTS

Assume the following statement sequence in the called SUBROUTINE subprogram:

SUBROUTINE EXAMP (L, \*, M, \*, N, \*)

•  
•  
•  
•  
•  
RETURN

•  
•  
•  
•  
RETURN

•  
•  
•  
•  
RETURN (C/D)

•  
•  
END

Each occurrence of RETURN returns control to the statement GO TO 101 in the calling program.

If, on the execution of the RETURN(C/D) statement, the value of (C/D) is:

Less than or equal to:

0	a standard return to the GO TO 101 statement is made
1	the return is made to statement 10
2	the return is made to statement 15
3	the return is made to statement 20

The following is performed:

Greater than or equal to:

4	The following is performed: a standard return to the GO TO 101 statement is made.
---	--

### 15.6.1 Referencing External FUNCTION Subprogram

Reference an external function subprogram by using its assigned name as an operand in an arithmetic or logical expression in the calling program unit. The name must be followed by an actual argument list. The actual arguments in an external function reference may be:

1. a variable name,
2. an array element identifier,
3. an array name,
4. an expression,
5. a statement number, or

## SUBPROGRAM STATEMENTS

6. the name of another external procedure FUNCTION or SUBROUTINE).

### NOTE

Any subprogram name to be used as an argument to another subprogram must first appear in an EXTERNAL statement (Chapter 6) in the calling program unit.

#### Example

The subprogram defined as:

```
INTEGER FUNCTION ICALC(IX,IY,IZ)
.
.
.
RETURN
END
```

may be referenced in the following manner:

```
.
.
.
TOTAL=ICALC(IAA,IAB,IAC)+500
```

### 15.7 MULTIPLE SUBPROGRAM ENTRY POINTS (ENTRY STATEMENT)

FORTRAN-10 provides an ENTRY statement that enables you to specify additional entry points into an external subprogram. This statement used in conjunction with a RETURN statement enables you to employ only one computational routine of a subprogram that contains several such routines. The form of the ENTRY statement is:

```
ENTRY name(arg1,arg2,...,argn)
```

where

name                   is the symbolic name to be assigned the desired entry point

(arg1,...,argn)       is an optional list of dummy arguments. This list may contain

1. variable names,

2. array declarators,

## SUBPROGRAM STATEMENTS

3. the name of an external procedure (SUBROUTINE or FUNCTION), or
4. statement label identifiers that are denoted by either a \*, \$, or & symbol.

The rules for the use of an ENTRY statement follow:

1. The ENTRY statement allows entry into a subprogram at a place other than that defined by the subroutine or function statement. You may include any number of ENTRY statements in an external subprogram.
2. Execution is begun at the first executable statement following the ENTRY statement.
3. Appearance of an ENTRY statement in a subprogram does not negate the rule that statement functions in subprograms must precede the first executable statement.
4. Entry statements are nonexecutable and do not affect the execution flow of a subprogram.
5. You may not use an ENTRY statement in a main program or have a subprogram reference itself through its entry points.
6. You may not use an ENTRY statement in the range of a DO or an extended DO statement construction.
7. The dummy arguments in the ENTRY statement need not agree in order, number, or type with the dummy arguments in SUBROUTINE or FUNCTION statements of any other ENTRY statement in the subprogram. However, the arguments for each call or function reference must agree with the dummy arguments in the SUBROUTINE, FUNCTION, or ENTRY statement that is referenced.
8. Entry into a subprogram initializes only the dummy arguments of the referenced ENTRY statement.
9. You may not reference a dummy argument unless it appears in the dummy list of an ENTRY, SUBROUTINE, or FUNCTION statement by which the subprogram is entered.
10. The source subprogram must be ordered such that references to dummy arguments in executable statements follow the appearance of the dummy argument in the dummy list of a SUBROUTINE, FUNCTION, or ENTRY statement.
11. Dummy arguments that were defined for a subprogram by some previous reference to the subprogram are undefined for subsequent entry into the subprogram.
12. The value of the function must be returned by use of the current entry name.

## SUBPROGRAM STATEMENTS

Table 15-3  
FORTRAN-10 Library Subroutines

Subroutine Name	Effect
AXIS	<p>CALL AXIS(X,Y,ASC,NASC,S,THETA,XMIN,DX)</p> <p>AXIS causes an axis with tick marks and scale values at 1-inch increments to be drawn. An identifying label may also be plotted along the axis. Parameters X and Y specify the start of the axis. The axis is plotted, starting at X, Y, at an angle of THETA degrees for a distance of S inches. The angle THETA is usually either 0 (X axis) or 90.0 (Y axis). Characters ASC of array ASC are plotted as a label for the axis drawn. If NASC is positive, the tic marks, label, and scale values are placed on the counterclockwise side of the axis; if NASC is negative, the foregoing items are placed on the clockwise side of the axis.</p> <p>Parameter XMIN is the value of the scale at the beginning of the axis; parameter DX is the change in scale for a 1-inch increment. The values of XMIN and DX may be determined by subroutine SCALE.</p>
DATE	<p>CALL DATE (array)</p> <p>This subroutine places today's date as left-justified ASCII characters into a dimensioned 2-word array. The date is in the form:</p> <p style="text-align: center;">dd-mmm-yy</p> <p>where dd is a 2-digit day (if the first digit is 0, it is converted to a blank), mmm is a 3-letter month abbreviation, e.g., Mar, and yy is a 2-digit year. The data is stored in ASCII code, left-justified, in the two words.</p>
DEFINE FILE	<p>CALL DEFINE FILE (u,s,v,f,pj,pg)</p> <p>The arguments of this subroutine are defined as follows:</p> <p>u = logical FORTRAN-10 device numbers.</p> <p>s = the size of the records comprising the file being defined. The argument s may be an integer constant or variable.</p> <p>v = an associated variable. The associated variable is an integer variable that is set to a value that points to the record that immediately follows the last record transferred. This variable is used by the FIND statement (Chapter 10). At the end of each FIND operation, the variable is set to a value that points to the record found. The variable v cannot appear in the I/O list of any I/O statement that accesses the file set up by the DEFINE FILE statement.</p>

## SUBPROGRAM STATEMENTS

Table 15-3 (Cont.)  
FORTRAN-10 Library Subroutines

Subroutine Name	Effect
	<p>f = filename to be given the file being defined.</p> <p>pj = your project number.</p> <p>pg = your programmer's number.</p>
NOTE	
Numbers pj and pg identify your File Directory.	
Example	
The statement	
CALL DEFINE FILE (1,10,ASCVAR,'FORTFL.DAT',0,0)	
<p>establishes a file named FORTFL.DAT on device 01, a disk, which contains ten word records. The associated variable is ASCVAR, and the file is in your area.</p>	
<p>A DEFINE FILE call can be used to establish and define the structure of each file to be used for random access I/O operations.</p>	
NOTE	
<p>the OPEN statement may be used to perform the same functions as DEFINE FILE.</p>	
DUMP	<p style="text-align: center;">CALL DUMP (L(1),U(1),F(1),...,L(n),U(n),F(n))</p> <p>DUMP causes particular portions of core to be dumped. L(1) and U(1) are the variable names that give the limits of core memory to be dumped. Either L(1) or U(1) may be upper or lower limits. F(1) is a number indicating the format in which the dump is to be performed: 0 = octal, 1 = real, 2 = integer, and 3 = ASCII.</p> <p>If F is not 0, 1, 2, 3, the dump is in octal. If F(n) is missing, the last section is dumped in octal. If U(n) and F(n) are missing, an octal dump is made from L to the end of the job area. If L(n), U(n), and F(n) are missing, the entire job area is dumped in octal.</p> <p>The dump is terminated by a call to EXIT.</p>

## SUBPROGRAM STATEMENTS

Table 15-3 (Cont.)  
FORTRAN-10 Library Subroutines

Subroutine Name	Effect
ERRSET	<p>CALL ERRSET(N)</p> <p>ERRSET allows you to control the typeout of execution-time arithmetic error messages. ERRSET is called with one integer argument.</p> <p>Typeout of all arithmetic and library error messages is suppressed after N occurrences of these error messages. If ERRSET is not called, the default value of N is 2.</p>
ERRSNS	<p>CALL ERRSNS(I,J)</p> <p>ERRSNS allows you to determine the exact nature of an error on READ, WRITE, OPEN, or CLOSE that was trapped with the "ERR= statement label" option. ERRSNS returns one or two integer values that describe the status of the last I/O operation performed by FOROTS. (The second integer value is optional.)</p> <p>CALL ERRSNS(I,J)</p> <p>returns a FORTRAN-standardized number in I and a processor-dependent number in J to describe the last I/O operation. See Appendix H and Table H-1 for more information and a detailed description of the values returned.</p>
EXIT	<p>EXIT</p> <p>EXIT returns control to the Monitor and, therefore, terminates the execution of the program.</p>
ILL	<p>CALL ILL</p> <p>ILL sets the ILLEG flag. If the flag is set and an illegal character is encountered in floating-point/double- precision input, the corresponding word is set to zero.</p>
LEGAL	<p>CALL LEGAL</p> <p>LEGAL clears the ILLEG flag. If the flag is set and an illegal character is encountered in the floating-point/double- precision input, the corresponding word is set to zero.</p>
LINE	<p>CALL LINE (X,Y,N,K)</p> <p>LINE causes a line to be drawn through the N points specified by (X(1),Y(1)),(X(2),Y(2))...(X(N),Y(N)) where the elements of X and Y are spaced K words apart in storage.</p>

## SUBPROGRAM STATEMENTS

Table 15-3 (Cont.)  
FORTRAN-10 Library Subroutines

Subroutine Name	Effect
MKTBL	<pre>CALL MKTBL(I,J)</pre> <p>MKTBL specifies a special character set where I is the number to be assigned the set and J contains the starting address of a character table of 200(8) consecutive words. In each character table word, the left half contains the number of strokes in the character (0 if nothing is to be plotted for the word) and the right half contains the address of the table of strokes for the character.</p>
NUMBER	<pre>CALL NUMBER(X,Y,SIZE,FNUM,THETA,NDIGIT)</pre> <p>NUMBER causes a floating-point number to be plotted as text. Parameters X, Y, SIZE, and THETA have the same meanings as for the SYMBOL call. Parameter NDIGIT is the number of digits plotted to the right of the decimal point. If NDIGIT is a negative value, only the integer part of the number is plotted. FNUM specifies the number to be plotted.</p>
PDUMP	<pre>CALL PDUMP(L(1),U(1),F(1),...,L(n),U(n),F(n))</pre> <p>The arguments of PDUMP are the same as those of DUMP. PDUMP is the same as DUMP except that control returns to the calling program after the dump has been executed.</p>
PLOT	<pre>CALL PLOT(X,Y,IPEN)</pre> <p>PLOT moves the pen in a straight line from its current position to the position specified by X,Y. If IPEN=3, the pen is raised before the movement; if IPEN=2 the pen is lowered before movement; if IPEN=1 the pen is left unchanged from its previous state. If the value of IPEN is negative (-1, -2 or -3) the pen action is the same as for the corresponding positive values except that on completion of the indicated motion, the new pen position is taken as a new origin and the output buffer is sent to the plotter.</p> <p>The plotter is not released on completion of the specified movement.</p>
PLOTS	<pre>CALL PLOTS (I)</pre> <p>PLOTS is the plotter setup routine. If the plotter is not available, I is set to -1; if it is available, I is set to 0. This call must be the first plotter routine called.</p>

## SUBPROGRAM STATEMENTS

Table 15-3 (Cont.)  
FORTRAN-10 Library Subroutines

Subroutine Name	Effect
RELEASES	CALL RELEASES(unit)
	RELEASES closes out I/O on a device initialized by the FORTRAN Operating System and returns it to the uninitialized state. RELEASES should be the last call referencing that device.
SAVRAN	CALL SAVRAN(I)
	SAVRAN is called with one integer argument. SAVRAN sets its argument to the last random number (interpreted as an integer) that has been generated by the function RAN.
SCALE	CALL SCALE(X,N,S,XMIN,DX)
	SCALE selects scale values for an AXIS call where X and N specify a 1-dimensional array X with the length N. Parameter S specifies the length of the desired axis, SCALE determines a value of DX that allows X to be plotted in S inches. XMIN is selected as the smallest element of the array X, and is truncated to be a multiple of DX.
SETABL	CALL SETABL(I,J)
	SETABL specifies a character set where I is an integer that gives the number of the desired character set. If a character set has been defined by I, the value of J is set to 0; if not, J is set to -1. The standard ASCII character set is defined as 1.
SETRAN	CALL SETRAN (I)
	SETRAN has one argument, which must be a non-negative integer <2(31). The starting value of the function RAN is set to the value of this argument, unless the argument is zero. In this case, RAN uses its normal starting value.
SLITE	CALL SLITE(I)
	SLITE turns sense lights on or off. I is an integer expression. For $1 \leq I \leq 36$ , sense light I will be turned on. If I=0, all sense lights will be turned off.
SLITET	CALL SLITET(I,J)
	SLITET checks the status of sense light I, sets the variable J accordingly, and turns off sense light I. If i is on, j is set to 1; and if i is off, j is set to 2.

## SUBPROGRAM STATEMENTS

Table 15-3 (Cont.)  
FORTRAN-10 Library Subroutines

Subroutine Name	Effect
SORT	<pre>CALL SORT ('OUTPUT/SWS=INPUT/SWS,INPUT/SWS')</pre> <p>SORT sorts one or more files using the SORT program. The argument is an ASCII string that represents (version 3 or later) the standard SORT command string. Its components are:</p> <p>OUTPUT = file specification of the output file.      INPUT = file specification of the input file(s).      SWS = one or more switches for the output file, the input file(s), the sorting process, and sometimes SCAN. The switches not allowed in the FORTRAN call are:/BLOCK, /COMP3, /EBCDIC, /INDUSTRY, /LABEL, /SIXBIT, and /VERSION.</p> <p>Wild card format is not allowed in the FORTRAN call.</p> <p>For information about using the SORT program, see the SORT USER'S GUIDE (AA-0997C-TB). Example:</p> <pre>CALL SORT('SRTFIL.SRT=INSTRT/REC:80/KEY:1:2')</pre>
SSWTCH	<pre>SSWTCH(I,J)</pre> <p>SSWTCH checks the status of data switch i (<math>0 \leq i \leq 35</math>) and sets the variable J accordingly. If I is set OFF, J is set to 1; and, if I is ON, J is set to 2.</p>
SYMBOL	<pre>CALL SYMBOL(X,Y,SIZE,ASC,THETA,NASC)</pre> <p>SYMBOL raises the plotter pen and moves it to position specified by X and Y. Lower pen and plot characters found in array ASC. Parameter SIZE specifies the height of the characters plotted in inches (floating-point values); THETA specifies the direction of the base line on which the text of array ASC is to be plotted, and NASC specifies the number of characters in array ASC.</p>
TIME	<pre>CALL TIME(X) or CALL TIME(X,Y)</pre> <p>TIME returns the current time in its argument(s) in left-justified ASCII characters. If TIME is called with one argument,</p> <pre>CALL TIME(X)</pre> <p>the time is in the form</p> <pre>hh:mm</pre> <p>where hh is the hours (24-hour time) and mm is the minutes. If a second argument is requested,</p> <pre>CALL TIME(X,Y)</pre>

## SUBPROGRAM STATEMENTS

Table 15-3 (Cont.)  
FORTRAN-10 Library Subroutines

Subroutine Name	Effect
	<p>the first argument is returned in the same form as the one-argument call, and the second has the form</p> <p>bss.t</p> <p>where b is a blank, ss is in seconds, and t is in tenths of a second.</p>
WHERE	<p>CALL WHERE(X,Y)</p> <p>Variables X and Y are set to the values which identify the current position of the pen.</p>



CHAPTER 16  
BLOCK DATA SUBPROGRAMS

16.1 INTRODUCTION

Use block data subprograms to initialize data to be stored in any common areas. You may use only specification and DATA statements, i.e., DATA, COMMON, DIMENSION, EQUIVALENCE, and TYPE, in BLOCK DATA subprograms. A subprogram of this type must start with a BLOCK DATA statement.

You may enter initial values into more than one labeled common block in a single subprogram of this type.

An executable program may contain more than one block data subprogram.

16.2 BLOCK DATA STATEMENT

The form of the BLOCK DATA statement is:

BLOCK DATA name

where


name           is a symbolic name given to identify the subprogram.



APPENDIX A  
ASCII-1968 CHARACTER CODE SET

The character code set defined in the X3.4-1968 Version of the American National Standard for Information Interchange (ASCII) is given in the following matrix.

1st 2 octal digits	Last octal digit							
	0	1	2	3	4	5	6	7
00x	NUL	SOH	STX	ETX	EOT	ENQ	ACK	BEL
01x	BS	HT	LF	VT	FF	CR	SO	SI
02x	DLE	DC1	DC2	DC3	DC4	NAK	SYN	ETB
03x	CAN	EM	SUB	ESC	FS	GS	RS	US
04x	¤	!	"	#	\$	%	&	,
05x	(	)	*	+	,	-	.	/
06x	0	1	2	3	4	5	6	7
07x	8	9	:	;	<	=	>	?
10x	@	A	B	C	D	E	F	G
11x	H	I	J	K	L	M	N	O
12x	P	Q	R	S	T	U	V	W
13x	X	Y	Z	[	\	]	^ (↑)	~ (←)
14x	grave	a	b	c	d	e	f	g
15x	h	i	j	k	l	m	n	o
16x	p	q	r	s	t	u	v	w
17x	x	y	z	{	}		~(ESC)	DEL



The diagram shows a vertical rectangle representing the range of graphic subsets from 64 to 95. Four arrows point downwards from the top edge of the rectangle to the bottom edge. The number '64' is at the top left, and '95' is at the top right. The bottom edge has two downward-pointing arrowheads.

Characters inside parentheses are ASCII-1963 Standard.

NUL	Null	DLE	Data Link Escape
SOH	Start of Heading	DC1	Device Control 1
STX	Start of Text	DC2	Device Control 2
ETX	End of Text	DC3	Device Control 3
EOT	End of Transmission	DC4	Device Control 4
ENQ	Enquiry	NAK	Negative Acknowledge
ACK	Acknowledge	SYN	Synchronous Idle
BEL	Bell	ETB	End of Transmission Block
BS	Backspace	CAN	Cancel
HT	Horizontal Tabulation	EM	End of Medium
LF	Line Feed	SUB	Substitute
VT	Vertical Tabulation	ESC	Escape
FF	Form Feed	FS	File Separator
CR	Carriage Return	GS	Group Separator
SO	Shift Out	RS	Record Separator
SI	Shift In	US	Unit Separator
		DEL	Delete (Rubout)



## APPENDIX B

### USING THE COMPILER

This appendix explains how to access FORTRAN-10 and how to make use of the information it provides. You should be familiar with the FORTRAN-10 language and the DECsystem-10 TOPS-10 monitor.

#### B.1 RUNNING THE COMPILER

The command to run FORTRAN-10 is:

```
.R FORTRA
```

The compiler responds with an asterisk (\*) and is then ready to accept a command string. A command is of the general form:

```
object filename, listing filename=source filename(s)
```

You are given the following options:

1. The filenames can be fully specified SFD paths.
2. You may specify more than one input file in the compilation command string. These files will be logically concatenated by the compiler and treated as one source file.
3. Program units need not be terminated at file boundaries and may consist of more than one file.
4. If no object filename is specified, no relocatable binary file is generated.
5. If no listing filename is specified, no listing is generated.
6. If no extension is given, the defaults are .LST (listing), .REL (relocatable binary), and .FOR (source) for their respective files.

#### B.1.1 Switches Available with FORTRAN-10

Switches to FORTRAN-10 are accepted anywhere in the command string. They are totally position- and file-independent. Table B-1 lists the switches.

## USING THE COMPILER

Table B-1  
FORTRAN-10 Compiler Switches

Switch	Meaning	Defaults
CROSSREF	Generates a file that can be input to the CREF program	OFF
DEBUG	(See Section B.1.1.1.)	OFF
EXPAND	Includes the octal-formatted version of the object file in the listing.	OFF
INCLUDE	Compiles a D in card column 1 as as space.	OFF
KA10	Compiles code to run on a KA10 processor.	Compilation processor
KI10	Compiles code to run on a KI10 processor.	Compilation processor
LNMAP	Produces a line number/octal location map in the listing only if /MACROCODE was not specified.	OFF
MACROCODE	Adds the mnemonic translation of the object code to the listing file.	OFF
NOERRORS	Does not print error messages on the terminal.	OFF
NOWARNINGS	Does not output warning messages.	OFF
OPTIMIZE	Performs global optimization.	OFF
SYNTAX	Performs syntax check only.	OFF

Each switch must be preceded by a slash (/). Switch names need only contain those letters that are required to make the switch name unique. You are encouraged to use at least three letters to prevent conflict with switches in future implementations.

## Example

```
.R FORTRA
*OFILE,LFILE=SFILE/MAC,S2FILE
```

The /MAC switch will cause the MACRO code equivalent of SFILE and S2FILE to appear in LFILE.LST.

If you do not specify a processor (KA10 or KI10 switch), the code will be compiled for the processor type on which the compilation occurs. The processor type of the code in the object file and all switches, used or implied, are printed at the top of each listing page.

## USING THE COMPILER

B.1.1.1 The /DEBUG Switch - The /DEBUG switch tells FORTRAN-10 to compile a series of debugging features into your program. Several of these features are specifically designed to be used with FORDDT. Refer to Appendix E for more information. By adding the modifiers listed in Table B-2, you can include specific debugging features.

**Table B-2**  
Modifiers to /DEBUG Switch

Modifiers	Meaning
:DIMENSIONS	Generates dimension information in .REL file for FORDDT.
:TRACE	Generates references to FORDDT required for its trace features (automatically activates :LABELS).
:LABELS	Generates a label for each statement of the form "line-number L." (This option may be used without FORDDT.)
:INDEX	Forces DO LOOP indices to be stored at the beginning of each iteration rather than held in a register for the duration of the loop.
:BOUNDS	Generates the bounds checking code for all array references. Bounds violations will produce run-time error messages. Note that the technique of specifying dimensions of 1 for subroutine arrays will cause bounds check errors. (You may use this option without FORDDT.)
:NONE	Do not include any debug features.
:ALL	Enable all debugging aids.

The format of the /DEBUG switch and its modifiers is as follows:

/DEBUG:modifier

or

/DEBUG:(modifier list)

Options available with the /DEBUG modifiers are:

1. No debug features - Either do not specify the /DEBUG switch or include /DEBUG:NONE.
2. All debug features - Either /DEBUG or /DEBUG:ALL.
3. Selected features - Either a series of modified switches; i.e.,

/DEBUG:BOU/DEBUG:LAB

or a list of modifiers

/DEBUG:(BOU,LAB,...)

## USING THE COMPILER

4. Exclusion of features (if you wish all but one or two modifiers and do not wish to list them all, you may use the prefix "NO" before the switch you wish to exclude). The exclusion of one or more features implicitly includes all the others, i.e., /DEBUG:NOBOU is the same as /DEBUG:(DIM,TRA,LAB,IND).

If you include more than one statement on a single line, only the first statement will receive a label (/DEBUG:LABELS) or FORDDT reference (/DEBUG:TRACE). (The /DEBUG option and the /OPTIMIZE option cannot be used at the same time.)

### NOTE

If a source file contains line sequence numbers that occur more than once in the same subprogram, the /DEBUG option cannot be used.

The following formulas may be used to determine the increases in program size that will occur as a result of the addition of various /DEBUG options.

:DIMENSIONS	For each array, $3+3*N$ words where N is the number of dimensions, and up to three constants for each dimension.
:TRACE	One instruction per executable statement.
:LABELS	No increase.
:INDEX	One instruction per inner loop plus one instruction for some of the references to the index of the loop.
:BOUNDS	For each array, the formula is the same as DIMENSIONS.:.  For each reference to an array element, use $5+N$ words where N is the number of dimensions in the array. If you do not specify :BOUNDS, approximately $1+3*(N-1)$ words will be used.

### B.1.2 COMPIL-Class Commands

You can invoke FORTRAN-10 by using COMPIL-class commands. These commands cause the monitor to run the COMPIL program, which interprets the command and constructs new command strings for the system program actually processing the command. When both FORTRAN-10 and F40 are present in your DECsystem-10 system, you can specify which compiler is to be used by adding the switches /F10 or /F40 to the following commands:

COMPILE  
LOAD  
EXECUTE  
DEBUG

## USING THE COMPILER

### Example

```
.EXEC ROTOR/F10
```

The compiler switches KA, KI, OPT, CREF, and DEBUG may be specified directly in COMPIL-class commands and may be used globally or locally.

### Example

```
.EXECUTE/CREF/KA/F10 P1.FOR,P2.FOR/DEBUG:NOBOU
```

The other compiler switches must be passed in parentheses for each specific source file.

### Example

```
.EXECUTE P1.FOR(M,I)
```

Refer to the DECsystem-10 Operating System Commands Manual for further information.

## B.2 READING A FORTRAN-10 LISTING

When you request a listing from the FORTRAN-10 compiler, it contains the following information:

1. A printout of the source program plus an internal sequence number assigned to each line by the compiler. This internal sequence number is referenced in any error or warning messages generated during the compilation. If the input file is line-sequenced, the number from the file is used. If code is added via the INCLUDE statement, all INCLUDED lines will have an asterisk (\*) appended to their line-sequence number.
2. A summary of the names and relative program locations (in octal) of scalars and arrays in the source program plus compiler generated variables.
3. All COMMON blocks and the relative locations (in octal) of the variables in each COMMON block.
4. A listing of all equivalenced variables or arrays and their relative locations.
5. A listing of the subprograms referenced (both user defined and FORTRAN-10 defined library functions).
6. A summary of temporary locations generated by the compiler.
7. A heading on each page of the listing containing the program unit name (MAIN., program, subroutine or function, principal entry), the input filename, the list of compiler switches, and the date and time of compilation. Whether a specific processor switch (/KA10, /KI10) was used and the processor for which the code was generated is also at the top of the listing page.
8. If you used the /MACRO switch, a mnemonic printout of the generated code (in a format similar to MACRO-10) is appended to the listing. This section has four fields:

## USING THE COMPILER

LINE: This column contains the internal sequence number of the line corresponding to the mnemonic code. It appears on the first of the code sequence associated with that internal sequence number. An asterisk indicates a compiler inserted line.

LOC: The relative location in the object program of the instruction.

LABEL: Any program or compiler generated label. Program labels have the letter "P" appended. Labels generated by the compiler are followed by the letter "M". Labels generated by the compiler and associated with the /DEBUG:LABELS switch consist of the internal sequence number followed by an "L".

GENERATED CODE: The MACRO-10 mnemonic code.

If you used the /LNMAP switch and did NOT use the /MACRO switch, a line number/octal location map is appended to the listing. This section lists the line numbers in increments of 10 on subsequent lines and each number from 0 through 9 for each line in adjacent columns. The numbers appearing inside the matrix are the relative octal locations of the statements in the FORTRAN program unit. For example, to find the relative octal location of line number 001043, find the row marked 001040 and then column 3 on that line. The number in that place is the desired relative location. This listing can be very large and sparse for line-numbered files with large increments, such as those produced by SOS.

### NOTE

One FORTRAN line can produce multiple octal locations. In this case the line number map lists only the first location.

9. A list of all argument blocks generated by the compiler. A zero argument appears first followed by argument blocks for subroutine calls and function references (in order of their appearance in the program). Argument blocks for all I/O operations follow this.
10. Format statement listings.
11. A summary of errors detected or warning messages issued during compilations.

#### B.2.1 Compiler Generated Variables

In certain situations the compiler will generate internal variables. Knowing what these variables represent can help you read the macro expansion. The variables are of the form:

.letter digit digit digit digit

i.e., .S0001

## USING THE COMPILER

where:

Letter	Function of Variable
A	Register save area.
F	Arithmetic statement function formal parameters.
I	Result of a DO LOOP initial value expression or parameter of an adjustably dimensioned array.
O	Result of a common subexpression (see Section C.2.1.1) or constant computation (C.2.1.3).
Q	Temporary storage for expression values.
R	Result of reduced operator strength expression (C.2.1.2).
S	Result of the DO LOOP step size expression or computed iteration count for a loop.

You may find these variables on the listing under SCALARS and ARRAYS.

The following example shows a listing where all these features are pointed out.

## USING THE COMPILER

Name of Program	Name of Source File	Compiler Version			
MAIN.	TIM1.FOR	FORTRAN V.5(515)	/KI/M	19-NOV-76	15:00 PAGE 1

Macro code equivalent included  
code was compiled for a KI processor

```

00001      IMPLICIT INTEGER (A-Z)
00002      DIMENSION A(100,200),B(100,200)
00003      SUM1=0
00004      SUM2=0
00005      DO 100 J=1,200
00006      DO 100 I=1,100
00007      K1=I*J
00008      IF (K1 .LT. 500 .OR. K1 .GT. 1500) K1=0
00009      A(I,J)=K1
00010      K2=I+J
00011      IF (K2 .EQ. 100 .OR. K2 .EQ. 200 .OR. K2.EQ.300) K2=K2+1
00012      B(I,J)=K2
00013      SUM1=SUM1+K1
00014      SUM2=SUM2+K2
00015      100      CONTINUE
00016      C
00017      TYPE 10,SUM1,SUM2
00018      FORMAT(7H SUM1= ,I9,1CH    SUM2= ,I9)
00019      END

```

## SUBPROGRAMS CALLED

The relative address of each variable is given

SCALARS AND ARRAYS [ "\*" NO EXPLICIT DEFINITION - "%" NO REFERENCED ]

\*K1      1      E      2      \*J      47042      A      47043      .S0001      116103  
.S0000 116104 \*SUM2 116105 \*I 116106 \*K2 116107 \*SUM1 116110

Internal sequence number on first instruction that goes with this line  
octal displacement of instruction

LINE	LOC	LABEL	GENERATED CODE
0		JFCL	0,0
1		JSP	16,RESET.
2	3	SETZB	0,0
3	4	MOVEM	2,SUM1
4	5	MOVE	2,SUM2
5	6	HLREM	2,[777470000001]
6	10	HRRZM	2,J
7	11	3M:	MOVE 2,[777634000001]
8	12	4M:	MOVE 3,J
	13	IMULI	3,0(2)
	14	MOVEM	3,K1
	15	CAIL	3,764
		CAILE	3,2734

USING THE COMPILER

<pre> 16      JRST    0,6M 17      JRST    0,5M 8       20      SETZB   4,K1           6M:----- compiler generated label </pre>	<pre> MAIN.   TIM1.FOR      FORTRAN V.5(515) /KI/M   19-NOV-76           15:00   PAGE 1-1 </pre>	
<pre> 9      21      5M:           22      MOVEI   3,144           23      IMUL   3,J           24      ADDI   3,0(2)           25      MOVE   4,K1           26      MOVEM  4,A-145(3)           27      MOVE   3,J           28      ADDI   3,0(2)           29      MOVEM  3,K2           30      MOVE   5,K2           31      CAIE   5,144           32      CAIN   5,310           33      JRST   0,8M           34      9M:           35      CAIN   5,454           36      8M:           37      7M:           38      AOS    3,K2           39      MOVEI   3,144           40      IMUL   3,J           41      ADDI   3,0(2)           42      MOVE   5,K2           43      MOVEM  5,B-145(3)           44      ADDM   4,SUM1           45      ADDM   5,SUM2           46      10CP:----- program label           47      AOBIN  2,4M           48      AOS    2,J           49      AGSCE  0,S00000           50      JRST   0,3M           51 </pre>		

## USING THE COMPILER

ARGUMENT BLOCKS:

```

17      52      MOVEI   16,10M
           PUSHJ   17,OUT.
           MOVEI   16,11M
           PUSHJ   17,IOLST.
           MOVEI   16,1M
           PUSHJ   17,EXIT.
19      53      MOVEI   16,10M
           PUSHJ   17,OUT.
           MOVEI   16,11M
           PUSHJ   17,IOLST.
           MOVEI   16,1M
           PUSHJ   17,EXIT.

```

function and subroutine argument blocks

```

60      0      0,,0
61      1M:   0,,0
62      62    777773,,0
63      10M:  0,,777777
64      64    0,,0
65      65    0,,0
66      66    340,,10P
67      67    0,,7
70      70    0,,0
71      71    1100,,SUM1
72      72    1100,,SUM2
73      73    4000,,0

```

MAIN. TIM1.FOR FORTRAN V.5(515) /KI/M 19-NOV-76 15:00 PAGE 1-2

FORMAT STATEMENTS ( IN LOW SEGMENT ) :

```

18      116111  10P:   (7H S
           116112           UM1=
           116113           'I9,1
           116114           OH
           116115           SUM2
           116116           = ,I9
           116117           )

```

MAIN. [ NO ERRORS DETECTED ] summary of detected errors

MAIN.      TIM1.FOR      FORTRAN V.5(515) /KI      19-NOV-76      15:01      PAGE 1

```

00001      IMPLICIT INTEGER (A-Z)
00002      DIMENSION A(100,200),B(100,200)
00003      SUM1=0
00004      SUM2=0
00005      DO 100 J=1,200
00006      DC 100 I=1,100
00007      K1=I*J
00008      IF (K1 .LT. 500 .OR. K1 .GT. 1500) K1=0
00009      A(I,J)=K1
00010      K2=I+J
00011      IF (K2 .EQ. 100 .OR. K2 .EQ. 200 .OR. K2.EQ.300) K2=K2+1
00012      B(I,J)=K2
00013      SUM1=SUM1+K1
00014      SUM2=SUM2+K2
00015      CONTINUE
00016      C
00017      TYPE 10,SUM1,SUM2
00018      FORMAT(7H SUM1= ,I9,10H      SUM2= ,I9)
00019      END

```

#### SUBPROGRAMS CALLED

SCALARS AND ARRAYS [ "\*" NO EXPLICIT DEFINITION - "8" NOT REFERENCED ]

*K1	1	B	2	*J	47042	A	47043	.S0001	116103
.S0000	116104	*SUM2	116105	*I	116106	*K2	116107	*SUM1	116110

LINE NUMBER/OCTAL LOCATION MAP

line number may request with /LNMAP switch

## USING THE COMPILER

	0	1	2	3	4	5	6	7	8	9
00000	.	.	.	.	.	.	.	.	.	.
00010	:	26	31	37	44	45	46	52	56	21

MAIN. [ NO ERRORS DETECTED ]

line number 11 starts at octal location 31 (from the previous listing, notice that line 11 uses locations 31 through 36 but only the first location is shown here)

```

MAIN.      TIME1.FOR      FORTRAN V.5(515) /KI/OPT/M 19-NOV-76      15:00      PAGE 1

00001      IMPLICIT INTEGER (A-Z)
00002      DIMENSION A(100,200),B(100,200)
00003      SUM1=0
00004      SUM2=0
00005      DO 100 J=1,200
00006      DO 100 I=1,100
00007      K1=I*J
00008      IF (K1 .LT. 500 .OR. K1 .GT. 1500) K1=0
00009      A(I,J)=K1
00010      K2=I+J
00011      IF (K2 .EQ. 100 .OR. K2 .EQ. 200 .OR. K2.EQ.300) K2=K2+1
00012      B(I,J)=K2
00013      SUM1=SUM1+K1
00014      SUM2=SUM2+K2
00015      CONTINUE
00016      C
00017      TYPE 10,SUM1,SUM2
00018      FORMAT(7H SUM1= .19,10H      SUM2= ,19)
00019      END

```

## SUBPROGRAMS CALLED

SCALARS AND ARRAYS [ "\*" NO EXPLICIT DEFINITION " %" NOT REFERENCED ]

optimizer created variables

```
* K1      1          E          2          *R0001 47042      *R0000 47043      *J      47044
A      47045      *S0001 116105      *S0000 116106      *SUM2 116107      *I      116110
.O00001 116111      *K2      116112      *SUM1 116113
```

optimizer created variables

LINE LOC LABEL GENERATED CODE

0		JFCL	0,0
1		JSP	16,RESET.
2			0,0
4	3	SETZB	10,11
*	4	MOVEI	12,144
5	5	MOVEM	12,.R0001
5	6	MOVNI	7,1
7	7	MOVEI	7,1
10		MOVEM	12,.S0000

optimizer created statement

*	11	4M:	MOVE	6,7
*	12		MOVE	2,[777634000001]
6	13	5M:	MOVEI	4,0(2)
*			ADD	4,.R0001
14			MOVE	5,6
7	15		CALL	5,764
8	16		CAILE	5,2734
	17			

## USING THE COMPILER

		MAIN.	TIM1.FOR	FORTRAN V.5(515) /KI/OPT/M 19-NOV-76	15:00	PAGE 1-1
8						
20				JRST 0,7M		
21				JRST 0,6M		
22		7M:				
				MOVEI 5,0		
9	23	6M:		MOVEM 5,A-145(4)		
10	24			MOVE 3,7		
	25			ADDI 3,0(2)		
11	26			CAIE 3,144		
	27			CAIN 3,310		
	30			JRST 0,9M		
	31	10M:				
11	32	9M:		CAIN 3,454		
	33	8M:		ADDI 3,1		
12	34			MOVEM 3,B-145(4)		
13	35			ADD 11,5		
14	36			ADD 10,3		
*	37	100P:		ADD 6,7		
15				AOBJN 2,5M		
*	40			MOVEI 12,144		
*	41			ADDM 12,.R0001		
*	42	1M:				
				ADDI 7,1		
				AOSGE 0,S0000		
43				JRST 0,4M		
44				MOVEM 11,SUM1		
*	45			MOVEM 10,SUM2		
*	46			MOVEM 5,K1		
*	47			MOVEM 3,K2		
*	50			MOVEI 16,11M		
17	51			PUSHJ 17,OUT.		
52						

# USING THE COMPILER

```

*      53          MOVEI   16,12M
         54          PUSHJ   17,IOLST.
19      55:        2M:     MOVEI   16,3M
         56          PUSHJ   17,EXIT.

```

### ARGUMENT BLOCKS:

```

57          0,,0
60          3M:    0,,0
61          11M:   777773,,0
62          0,,77777
63          0,,0
64          0,,0
65          340,,10P
66          0,,7
67          0,,0
70          12M:   1100,,SUM1
71          1100,,SUM2
72          4000,,0

```

MAIN.	TIME1.FOR	FORTRAN V.5 (515) /KI/OPT/M 19-NOV-76	15:00	PAGE 1-2
FORMAT STATEMENTS (IN LOW SEGMENT) :				
18	116114 10P:	(7H S		
	116115	UM1=		
	116116	,19,1		
	116117	0H		
	116120	SUM2		
	116121	= ,19		
	116122	)		
MAIN. [ NO ERRORS DETECTED ]				

**B.3 ERROR REPORTING**

If an error occurs during the initial pass of the compiler (while the actual source code is being read and processed), an error message is printed on the listing immediately following the line in which the error occurred. Each error references the internal sequence number of the incorrect line. The error messages along with the statement in error are output to the user terminal. For example:

```
.EXECUTE DAY.FOR
FORTRAN:DAY
01300                               K1
?FTNNRNC LINE:01300      STATEMENT NOT RECOGNIZED
01500 100                           CONTINE
?FTNMSP LINE:01500      STATEMENT NAME MISSPELLED
01600 ?
?FTNICL LINE:01600      ILLEGAL CHARACTER C IN LABEL FIELD

?FTNFTL MAIN.                      3 FATAL ERRORS AND NO WARNINGS
LINK: LOADING
[LNKNSA NO START ADDRESS]

EXIT
.
```

If errors are detected after the initial pass of the compiler, they appear in the list file after the end of the source listing. They are output to your terminal without the statement in error, but they may reference its internal sequence number.

**B.3.1 Fatal Errors and Warning Messages**

There are two levels of messages, warning and fatal error. Warning messages are preceded by "%" and indicate a possible problem. The compilation will continue, and the object program will probably be correct. Fatal errors are preceded by a "?". If a fatal error is encountered in any pass of the compiler, the remaining passes will not be called. Additional errors that would be detected in later compiler passes may not become apparent until the first errors are corrected. It is not possible to generate a correct object program for a source program containing a fatal error.

The format of messages is

```
?FTNXXX LINE:n text
```

or

```
%FTNXXX LINE:n text
```

where:

?	= fatal
%	= warning
FTN	= FORTRAN mnemonic
XXX	= 3-letter mnemonic for the error message
LINE:n	= line number where error occurred
text	= explanation of error

## USING THE COMPILER

The printing of fatal errors and warning messages on your terminal can be suppressed by the use of the /NOERRORS switch; however, messages will still appear on the listing. The /NOWARNINGS switch will suppress warning messages on both user terminal and listing.

### B.3.2 Message Summary

At the end of the listing file and on the terminal, a message summary is printed after each program unit is compiled. This message has two forms:

1. when one or more messages were issued

```
{?FTNFTL}  
{?FTNWRN} name NO/number FATAL ERRORS AND NO/number WARNINGS
```

or

2. when no messages were issued

```
name [NO ERRORS DETECTED]
```

where name is the program or subprogram name. ([NO ERRORS DETECTED] appears on the listing only.) Appendix G is a complete list of fatal errors and warning messages.

### B.4 CREATING A REENTRANT FORTRAN PROGRAM WITH LINK-10

To produce a sharable program from the .REL file, such as MAIN.REL, give either one of the following commands to LINK-10:

1. /SEG:DEFAULT MAIN/G
2. /OTS:NONSHAR MAIN/G

The resulting core image can be SAVED or the /SSAVE switch can be used to produce a .SHR file.

## APPENDIX C

### WRITING USER PROGRAMS

This appendix is a guide for writing effective programs with FORTRAN-10. It contains techniques for optimization, interaction with non-FORTRAN programs, mixing of FORTRAN-10 and F40 object programs, and other useful programming hints.

#### C.1 GENERAL PROGRAMMING CONSIDERATIONS

The following paragraphs describe programming considerations you should observe when preparing a FORTRAN program to be compiled by FORTRAN-10.

##### C.1.1 Accuracy and Range of Double-precision Numbers

Floating-point and real numbers may consist of up to 16 digits in a double-precision mode. Their range is specified in Chapter 3, Section 3.2 of this manual. You must be careful when testing the value of a number within the specified range since, although numbers up to  $10^{**38}$  may be represented, FORTRAN-10 can only test numbers of up to eight significant digits (REAL precision) and 16 significant digits (DOUBLE precision).

You must also be careful when testing the floating-point computation for a result of 0. In most cases the anticipated result, i.e., 0 will be obtained; however, in some cases the result may be a very small number that approximates 0. Such an approximation of 0 will cause tests within statements, i.e., an arithmetic IF, to fail.

##### C.1.2 Writing FORTRAN-10 Programs for Execution On Non-DEC Machines

If you prepare a program to run on both a DECsysten-10 computer and a non-DIGITAL machine, you should:

1. Avoid using the non-ANSI standard features of FORTRAN-10, and
2. Consider the accuracy and size of the numbers that the non-DIGITAL machine is capable of handling.

C.1.3 Using Floating-Point DO Loops

FORTRAN-10 permits you to employ non-integer single- or double-precision numbers as the parameter variables in a DO statement. This enables you to generate a wider range of values for the DO loop index variables, which may, in turn, be used inside the loop for computations. Be sure to consider the loss of precision that may occur.

C.1.4 Computation of DO Loop Iterations

The number of times through a DO loop is computed outside the loop and is not affected by any changes to the DO index parameters within the loop. The formula for the number of times a DO loop is executed is:

```
DO 10 I=M1,M2,M3
      MAX  (1,((M2-M1)/M3)+1)=Number of cycles
```

The values of the parameters M1, M2, M3 may be of any type; however, you must consider the foregoing formula, particularly when using logicals. One pass through each DO loop is always performed EVEN IF THE RESULT OF THE FOREGOING CALCULATION IS LESS THAN OR EQUAL TO ZERO.

C.1.5 Subroutines - Programming Considerations

Consider the following items when preparing and executing subroutines:

1. During execution, no check is made to see if the proper number of parameters was passed.
2. If the number of actual arguments passed to a subroutine is less than the number of dummy arguments specified, the values of the unspecified arguments are undefined.
3. If the number of actual arguments passed to a subroutine is greater than the number of dummy arguments given, the excess arguments are ignored.
4. If an actual parameter is a constant and its corresponding dummy argument is set to another value, all references made to the constant in the calling program may be changed to the value of the dummy argument.
5. No check is made to see if the parameters passed are of the same type as the dummy parameters. If an actual parameter is a constant and the corresponding dummy is of type real, be sure to include the decimal point with the constant. If the dummy is double-precision, be sure to specify the constant with a "D".

#### Examples

If the function F(A) is called by inputting F(2) and A is type real, F interprets the integer 2 as an unnormalized floating-point number. In this instance, F(A) should be called with F(2.0).

Similarly, if the function F1(D) is called by inputting F1(2.5) and D is double-precision, F1 assumes that its

parameters have been specified with two words of precision and picks up whatever follows the constant 2.5 in core. The proper method is to use F1(2.5D00).

## NOTE

You are given no notice if any of the situations described in items 1,2,3,4, and 5 occur.

C.1.6 Reordering of Computations

Computations that are not enclosed within parentheses may be reordered by the compiler. Sometimes it is necessary to use parentheses to ensure proper results from a specific computation.

For example, assuming that

1. RL1 represents a large number such that RL1\*RL2 will cause an overflow condition, and
2. RS1 is a very small number, i.e., less than 1, the program sequence

.

.

.

```
A=RS1*RL1*RL2
B=RS2*RL2*RL1
```

.

.

.

will not produce an overflow when evaluated left to right, since the first computation in each expression, i.e., RS1\*RL1 and RS2\*RL2, will produce an interim result that is smaller than either large number (RL1 or RL2).

However, the compiler will recognize RL1\*RL2 as a common subexpression (see Section C.2.1.1) and generate the following sequence:

```
temp = RL1*RL2
A    = RS1*temp
B    = RS2*temp
```

The computation of temp will cause an overflow.

You should write the program as follows to ensure that the desired results are obtained:

```
.
.
A=(RS1*RL1)*RL2
B=(RS2*RL2)*RL1
```

Computations may be reordered even when global optimization is not selected.

C.1.7 Dimensioning of Formal Arrays

When you specify an array as a formal parameter to a subprogram unit, you must indicate to the compiler that the parameter is an array. Dimension the array in a specification statement. This is the only way the compiler is able to distinguish a reference to such an array from a function reference. Designating the array with a dimension of 1 is a common practice.

Example

```
SUBROUTINE SUB1(A,B)
DIMENSION A(1)
```

There are disadvantages to using the above technique because the dimension information provided is not adequate in some cases, specifically:

1. Reading or writing the array by name

```
DIMENSION ARRAY (10)
READ (1) ARRAY
```

The above is a binary read that will read ten words into ARRAY.

```
SUBROUTINE SUB1(A)
DIMENSION A(1)
READ(1)A
```

This binary read will cause one word to be read into A.

2. Reading the array as a format

```
SUBROUTINE SUB2 (FMT)
DIMENSION FMT(1)
READ (1,FMT)
```

This will cause one word of the array FMT to be written over with the characters read from the record on unit 1.

When you use the /DEBUG:BOUNDS compilation switch, the dimension information used is that which is specified in the array declaration.

```
SUBROUTINE DO_IT(A)
DIMENSION A(1)
A(2)=0
```

The reference to A(2) will cause the out-of-bounds warning message to be generated.

C.2 FORTRAN-10 GLOBAL OPTIMIZATION

You have the option of invoking the global optimizer during compilation. The optimizer treats groups of statements in the source program as a single entity. The purpose of the global optimizer is to prepare a more efficient object program that produces the same results as the original unoptimized program, but takes significantly less execution time. The output of the lexical and syntactic analysis phase of the compiler is developed into an optimized source program equivalent (in results) to the original. The optimized program is then processed by the standard compiler code generation phase.

### C.2.1 Optimization Techniques

C.2.1.1 Elimination of Redundant Computations - Often the same subexpression will appear in more than one computation throughout a program. If the values of the operands of such a common expression are not changed between computations, the subexpression may be written as a separate arithmetic expression, and the variable representing its resultant may then be substituted where the subexpression appears. This eliminates unnecessary recomputation of the subexpression. For example, the instruction sequence:

```
A=B*C+E*F
.
.
.
H=A+G-B*C
.
.
.
IF((B*C)-H) 10,20,30
```

contains the subexpression  $B*C$  three times when it really needs to be computed only once. Rewriting the foregoing sequence as:

```
T=B*C
A=T+E*F
.
.
.
H=A+G-T
.
.
.
DIF((T)-H) 10,20,30
```

eliminates two computations of the subexpression  $B*C$  from the overall sequence.

Decreasing the number of arithmetic operations performed in a source program by the elimination of common subexpressions shortens the execution time of the resulting object program.

C.2.1.2 Reduction of Operator Strength - The time required to execute arithmetic operations will vary according to the operator(s) involved. The hierarchy of arithmetic operations according to the amount of execution time required is:

MOST TIME	OPERATOR
	**
	/
	*
LEAST TIME	+,-

During program optimization, the global optimizer replaces, where possible (1), some arithmetic operations that require the most time with operations that require less time. For example, consider the following DO loop that is used to create a table for the conversion of from 1 to 20 miles to their equivalents in feet.

```
DO 10 MILES=1,20
10 IFEET(MILES)=5280*MILES
```

---

1. Numerical analysis considerations severely limit the number of cases where this is possible.

## WRITING USER PROGRAMS

The execution time of the foregoing loop would be shorter if the time-consuming multiply operation, i.e.,  $5280 * \text{MILES}$ , could be replaced by a faster operation. Since you increment `MILES` on each pass, you can replace the multiply operation by an add and total operation.

In its optimized form, the foregoing loop would be replaced by a sequence equivalent to:

```
K=5280
DO 10 MILES=1,20
  IFEET(MILES)=K
10  K=K+5280
```

In the optimized form of the loop, the value of `K` is set to 5280 for the first iteration of the loop and is increased by 5280 for each succeeding iteration of the loop.

This foregoing situation occurs frequently in subscript calculations that implicitly contain multiplications whenever the size is two or greater.

**C.2.1.3 Removal of Constant Computation From Loops** - The speed with which a given algorithm may be executed can be increased if instructions and/or computations are moved out of frequently traversed program sequences into less frequently traversed program sequences. Movement of code is possible only if none of the arguments in the items to be moved are redefined within the code sequences from which they are to be taken. Computations within a loop consisting of variables or constants that are not changed in value within the loop may be moved outside the loop. Decreasing the number of computations made within a loop greatly decreases the execution time required by the loop.

For example, in the sequence:

```
DO 10 I=1,100
10 F=2.0*Q*A(I)+F
```

the value of the computation  $2.0 * Q$ , once calculated on the first iterations, will remain unchanged during the remaining 99 iterations of the loop. Reforming the foregoing sequence to:

```
QQ=2.0*Q
DO 10 I=1,100
10 F=QQ*A(I)+F
```

moves the calculation  $2.0 * Q$  outside the scope of the loop. This movement of code eliminates 99 multiply operations.

In addition, it is possible to remove entire assignment statements from loops. This action can be easily detected from the macro expanded listings. The internal sequence number remains with the statement and appears out of order in the leftmost column of the macro expanded listing (LINE).

C.2.1.4 Constant Folding and Propagation - In this method of optimization, expressions containing determinate constant values are detected and the constants are replaced, at compile time, by their defined or calculated value. For example, assume that the constant PI is defined and used in the following manner:

```

.
.
.
PI=3.14159
.
.
.
X=2*PI*Y
.
.
.
```

At compile time, the optimizer will have used the defined value of PI to calculate the value of the subexpression 2\*PI. The optimized sequence would then be:

```

.
.
.
PI=3.14159
.
.
.
X=6.28318*Y
.
.
```

thereby eliminating a multiply operation from the object code program.

The computation of determinate constant values at compile time is termed "folding"; the use of the defined value of a constant for replacement purposes throughout a program sequence is termed "propagation of the constants." The execution time saved by the foregoing type of compile time optimization is particularly important when the modified instruction occurs in a loop.

C.2.1.5 Removal of Inaccessible Code - The optimizer detects and eliminates any code within the source program that cannot be accessed. In general, this will not happen since programmers do not normally include such code in their programs; however, inaccessible code may appear in a program during the debugging process. The removal of inaccessible code by the optimizer will reduce the size of the object program. A warning message is generated for each inaccessible line removed.

C.2.1.6 Global Register Allocation - During the compilation of a source program, the optimizer controls the allocation of registers to minimize computation time in the optimized object program. The allocation process is designed to minimize the number of MOVE and MOVEM machine instructions that will appear in the most frequently executed portions of the code.

## WRITING USER PROGRAMS

C.2.1.7 I/O Optimization - Every effort is made to minimize the number of required calls to the FOROTS system. This is done primarily through extensive analysis of implied DO loop constructs on READ, WRITE, ENCODE, DECODE, and REREAD statements. The formats of these special blocks are described in Appendix E. These optimizations reduce the size of the program (argument code plus argument block size is reduced) and greatly improve the performance of programs that use implied DO loop I/O statements.

C.2.1.8 Uninitialized Variable Detection - A warning message is generated when a scalar variable is referenced before it has received a value.

C.2.1.9 Test Replacement - If the only use of a DO loop index is to reduce operator strength (D.2.1.2) and the loop does not contain exits (GO TOs out of the loop), the DO loop index is not needed and can be replaced by the reduced variable.

For example:

```
DO 10 I=1,10
K=K+7*I
10 CONTINUE
```

Reduction of operator strength and test replacement together transform this loop into

```
DO 10 I=7,70,7
K=K+I
10 CONTINUE
```

This occurs frequently in subscript computation.

### C.2.2 Improper Function References

Consider this statement:

```
P = F(X) + Q(Y)
```

If:

1. the evaluation of F(X) defines or changes the variables A, B, and C, and
2. the evaluation of Q(Y) defines or changes the values of B, C, and D,

then it is possible that different values of P could result, depending on which function is evaluated first. Let's see how this works. Let's assign some values (to begin with) to A, B, C, and D and define the functions F(X) and Q(Y):

Let:

F(X) :	Q(Y) :
A = 2.	A = 6.
B = 3.	B = 7.
C = 4.	C = 8.
D = 5.	F = D + 9.
	B = 10.
	C = 11.
	D = 12.
	Q = A + 13.

Now play computer and evaluate P, calling first F(X), then Q(Y). Now re-evaluate P, calling Q(Y) first, then F(X). Notice that you got different values for P because the variables A, B, C, and D changed value depending on the order in which the functions were called. (Our answers were 33 when F(X) was called first and 36 when Q(Y) was called first.)

The ANSI FORTRAN standard prohibits this kind of situation. But the compiler won't catch it unless you mention the affected variables in the function call itself. The compiler depends on strict adherence to this rule. There's a strong possibility that you won't get the results you want if you don't look for situations of this type and avoid them. Your best bet is to define your variables OUTSIDE the function and not change them in the course of the evaluation of the function itself.

### C.2.3 Programming Techniques for Effective Optimization

Observe the following recommendations during the coding of a FORTRAN source program. They will improve the effectiveness of the optimizer.

1. Do not use DO loops with an extended range.
2. Specify label lists when using assigned GO TOs.
3. Nest loops so that the innermost index is the one with the largest range of values.
4. Avoid the use of associated input/output variables.
5. Avoid unnecessary use of COMMON and EQUIVALENCE.

## C.3 INTERACTING WITH NON-FORTRAN-10 PROGRAMS AND FILES

### C.3.1 Calling Sequences

The following paragraphs describe the standard procedures for writing DECsystem-10 subroutine calls.

1. Procedure
  - a. The calling program must load the right half of accumulator (AC) 16 with the address of the first argument in the argument list.
  - b. The left half of AC 16 must be set to zero.
  - c. The subroutine is then called by a PUSHJ instruction to AC 17.
  - d. The return will be made to the instruction immediately after the PUSHJ 17 instruction.
  - e. If you use the /DEBUG:BOUNDS option of the FOROTS trace facility, the calling sequence must be

```
MOVEI 16,AP
PUSHJ 17,F
```

## WRITING USER PROGRAMS

where AP is the pointer to the argument list. If you use the trace facility, the word preceding the first word of an entry point should have its name in SIXBIT.

### 2. Restrictions

- a. Skip returns are not permitted.
- b. The contents of the pushdown stack located before the address specified by AC 17 belong to the calling program; they cannot be read by the called subprogram.
- c. FOROTS assumes that it has control of the stack; therefore, you must not create your own stack. The FOROTS stack is initialized by:

JSP 16,RESET.

or the library routine

CALL RESET.

### C.3.2 Accumulator Usage

The specific functions performed by accumulators (AC) 17,16,0, and 1 are as follows:

1. Pushdown Pointer - AC 17 is always maintained as a pushdown pointer. Its right half points to the last location in use on the stack, and its left half contains the negative of the number of (words-1) allocated to the unused remainder of the stack. (A trap occurs when something is pushed into the next to last location. The trap instruction may itself be a PUSHJ on the KI10 processor, which uses the last location.) A positive left half is not permitted.
2. Argument List Pointer - AC 16 is used as the argument pointer. The called subprogram does not need to preserve its contents. The calling program cannot depend on getting back the address of the argument list passed to the callee. AC 16 cannot point to the ACs or to the stack.
3. Temporary and Value Return Registers - AC 0 and 1 are used as temporary registers and for returning values. The called subprogram does not need to preserve the contents of AC 0 or 1 (even if not returning a value). The calling program must never depend on getting back the original contents of the data passed to the called subprogram.
4. Returning Values - At the option of the designer of a called subprogram, a subroutine may pass back results by modifying the arguments, returning a single-precision value in AC 0 or a double-precision or complex value in AC 0 and 1. A combination of the above may be used. However, two single-precision values cannot be returned in AC 0 and 1, since FORTRAN would not be able to handle it.

5. Preserved ACs - FORTRAN-10 FUNCTION subprograms preserve ACs 2 through 15; subroutine subprograms do not.

The design of the called subprogram cannot depend on the contents of any of the ACs being set up by the calling subprogram, except for ACs 16 and 17. Passing information must be done explicitly by the argument list mechanism. Otherwise, the called subprograms cannot be written in either FORTRAN-10 or COBOL.

### C.3.3 Argument Lists

The format of the argument list is as follows:

```
Arg count word
Arg list addr.---First arg entry
                Second arg entry
                .
                .
                .
                Last arg entry
```

The format of the arg count word is:

bits 0-17	These contain -n, where n is the number of arg entries.
bits 18-35	These are reserved and must be 0.

The format of an arg entry is as follows (each entry is a single word):

bits 0-8	Reserved for future DEC development (set to 0 for now).
bits 9-12	Arg type code.
bit 13	Indirect bit if desired.
bits 14-17	Index field, must be 0 for present.
bits 18-35	Address of the argument.

The following restrictions should be observed:

1. Neither the argument list nor the arguments themselves can be on the stack. This restriction is imposed so that the stack can be moved. The same restriction applies to any indirect argument pointers.
2. The called program may not modify the argument list itself. The argument list may be in a write-protected segment.

Note that the arg count word is at position -1 with respect to the contents of AC 16. This word is always required even if the subroutine does not handle a variable number of arguments. A subroutine that has no arguments must still provide an argument list consisting of two words, i.e., the argument count word with a 0 in it and a zero argument word.

## Example

```

MOVEI 16,AP      ;SET UP ARG POINTER
PUSHJ 17,SUB    ;CALL SUBROUTINE
...
.
.
;
;ARGUMENT LIST
-3,,0
AP:  A
     B
     C

;SUBROUTINE TO SET THIRD ARG TO SUM OF FIRST TWO ARGS

SUB:   MOVE      T,@0(16)      ;GET FIRST ARG
       ADD       T,@1(16)      ;ADD SECOND ARG
       MOVEM    T,@2(16)      ;SET THIRD ARG
       POPJ      17,           ;RETURN TO CALLER

```

C.3.4 Argument Types

Table C-1  
Argument Types and Type Codes

Type Code	Description	
	FORTRAN Use	COBOL Use
0	Unspecified	Unspecified
1	FORTRAN Logical	Not applicable
2	Integer	1-word COMP
3	Reserved	Reserved
4	Real	COMP-1
5	Reserved	Reserved
6	Octal	Reserved
7	Label	Procedure address
10	Double real	Not applicable
11	Not applicable	2-word COMP
12	Double Octal	Reserved
13	Reserved	Reserved
14	Complex	Not applicable
15	Not applicable	Byte string descriptor
16	Reserved	Reserved
17	ASCIIZ string	Not applicable

Literal arguments are permitted, but they must reside in a writable segment. This is because the FORTRAN-10 compiler makes a local of all non-array elements and copies all formals back to the caller's arguments. All unused type codes are reserved for future DIGITAL development.

**C.3.5 Description of Arguments**

The types of the arguments that may be passed are:

1. Type 0 - Unspecified

The calling program has not specified the type. The called subprograms should assume that the argument is of the correct type if it is checking types. If several types are possible, the called subprogram should assume a default as part of its specification. If none of the above conditions is true, the called subprogram should handle the argument as an integer (type 2).

2. Type 1 - FORTRAN logical

A 36-bit binary value containing 0 or positive to specify .FALSE. and negative to specify .TRUE..

3. Type 2 - Integer and 1-word-COMP

A 36-bit 2's complement signed binary integer.

4. Type 4 - Real and COMP-1

A 36-bit DECsystem-10 format floating-point number.

bit 0	sign
bits 1-8	excess 128 exponent
bits 9-35	mantissa

5. Type 6 - Octal

A 36-bit unsigned binary value.

6. Type 7 - Label and procedure address

A 23-bit memory address.

bits 0-12	always 0
bit 13	indirect flag
bits 14-17	0
bits 18-35	the address

7. Type 10 - Double real

A double-precision floating-point number for the CPU on which code is being executed, i.e., KA format on a KA10 processor and KI format on a KI10 processor.

8. Type 11 - 2-word COMP

A 2-word (72-bit) 2's complement signed binary integer.

word 1, bit 0	sign
word 1, bits 1-35	high order
word 2, bit 0	same as word 1, bit 0
word 2, bits 1-35	low order

9. Type 12 - Double octal

A 72-bit unsigned binary value.

## WRITING USER PROGRAMS

### 10. Type 14 - Complex

A complex number represented as an ordered pair of 36-bit floating-point numbers. The first represents the real part, and the second represents the imaginary part.

### 11. Type 15 - Byte String Descriptor

The format of the byte string descriptor is:

word 1: ILDB-type pointer, i.e., aimed at the byte preceding the first byte of the string  
word 2: EXP byte count

The byte descriptor may not be modified by the called program. The byte string itself must consist of a string of contiguous bytes of uniform size. The byte size may be any number of bits from 1 to 36. The byte count must be large enough to encompass 256K words of storage, i.e., 24 bits for 1-bit bytes. (See COBOL Program Reference Manual.)

### 12. Type 17 - ASCIZ string

A string of contiguous 7-bit ASCII bytes left justified on the word boundary of the first word and terminated by a null byte in the last word. The length of the string may be from 1 to 256K words.

#### C.3.6 Converting Existing MACRO-10 Libraries for use with FORTRAN-10

The following simple example illustrates the FORTRAN-10 calling sequence.

MAIN. EX1.FOR FORTRAN V.5(515) /KI/M 4-NOV-76 12:19 PAGE 1

```

00001      C      AN EXAMPLE OF A CALL TO A SUBROUTINE WITH A VARIETY OF ARGUMENTS
00002
00003      DOUBLE PRECISION DP
00004      DIMENSION B(10)
00005
00006      C      THE ARGUMENTS ARE:
00007      C      1. A REAL VARIABLE
00008      C      2. AN ARRAY NAME
00009      C      3. AN ARRAY ELEMENT
00010      C      4. AN INTEGER VARIABLE
00011      C      5. A DOUBLE PRECISION VARIABLE
00012      C      6. AN OCTAL CONSTANT
00013      C      7. A LITERAL
00014      CALL SUB1 (A, B, B(I), K, DP, "777, 'ABC'")
00015
00016
00017      END

```

## SUBPROGRAMS CALLED

SUB1

SCALARS AND ARRAYS [ "\*" NO EXPLICIT DEFINITION - "g" NOT REFERENCED ]

DP 1 \*K 3 B 4 \*A 16 \*I 17

TEMPORARIES

•Q00000 20

WRITING USER PROGRAMS

LINE	LOC	LABEL	GENERATED CODE		
15	0		JFCL 0,0		
	1		JSP 16,RESET.		
	2		MOVE 0,0		
	3	4	MOVEI 2,I		
	4		MOVEM 2,B-1(2)		
	5		MOVEI 2,Q0000		
	6		MOVEI 16,2M		
	7		PUSHJ 17,SUB1		
	10	11	MOVEI 16,1M		
			PUSHJ 17,EXIT.		
	<b>ARGUMENT BLOCKS:</b>				
		12		0,,0	
		13	1M:	0,,0	
		14		777771,,0	
		15	2M:	200,,A	
MAIN.		EX1.FOR FORTRAN V.5(512)	/KI/M 4-NOV-76	12:19 PAGE 1-1	
	16		200,,B		
	17		220,,Q0000		
	20		100,,K		
	21		400,,DP		
	22		300,,[000000000777]		
	23		740,,[406050320100]		
MAIN.		[ NO ERRORS DETECTED ]			
MAIN.		EX1.FOR FORTRAN V.5(512)	/KI/M 4-NOV-76	12:19 PAGE 1	
00001		SUBROUTINE SUB1 (REAL1, ARYNAM, ARYELM, INT1, DBLPRC, OCT, LIT)			
00002					
00003		DOUBLE PRECISION DBLPRC			

```

00004      DIMENSION ARYNAM (10)
00005
00006      C   AN EXAMPLE OF THE USE AND MODIFICATION OF FORMAL PARAMETERS
00007
00008      X1 = REAL1
00009      X2 = ARYNAM (J)
00010      X3 = ARYELM
00011      I1 = INT1
00012      X4 = DBLPRC
00013      I2 = OCT
00014      I3 = LIT
00015
00016      REAL1 = X1
00017      ARYNAM (J) = X2
00018      ARYELM = X3
00019      INT1 = I1
00020      DBLPRC = CMPLX (X4, 0.0)
00021      OCT = "55"
00022      LIT = 'ZYXW'
00023
00024      RETURN
00025      END

```

SUBPROGRAMS CALLED  
COMPLX.

SCALARS AND ARRAYS [ "*" NO EXPLICIT DEFINITION - "%" NOT REFERENCED ]									
* LIT	1	* OCT	2	* X4	3	* ARYELM	4	* X3	5
DBLPRC	6	* I3	10	* REAL1	11	* J	12	* X2	13
* INT1	14	* I2	15	* X1	16	* I1	17	ARYNAM	20

TEMPORARIES

.A0016 21

WRITING USER PROGRAMS

LINE	LOC	LABEL	GENERATED CODE	
	0		636542,,210000	
		SUB1:		
2	0		MOVE M 16,.A0016	
	1		MOVE 0,@0,(16)	
	2		MOVE M 0,REAL1	
	3		MOVE I 1,@1(16)	
	4		MOVE M 1,ARYNAM	
	5		MOVE 1,@2(16)	
		SUB1	EX1.FOR FORTRAN V.5(512) /KI/M 4-NOV-76	12:19 PAGE 1-1
	6		MOVE M 1,ARYELM	
	7		MOVE 2,@3(16)	
	10		MOVE M 2,INT1	
	11		DMOVE 4,@4(16)	
	12		DMOVE M 4,DBLPRC	
	13		MOVE 3,@5(16)	
	14		MOVE M 3,OCT	
	15		MOVE 6,@6(16)	
	16		MOVE M 6,LIT	
	8	17	3M:	
	9	20	MOVE M 0,X1	
		21	MOVE 7,J	
		22	ADD 7,ARYNAM	
		23	MOVE 7,777777(7)	
10	24		MOVE M 7,X2	
11	25		MOVE M 1,X3	
	26		MOVE M 2,I1	
	27		PUSH J 17,SNG.4	
	30		MOVE M 4,X4	
	31		FIX 3,3	
	32		MOVE M 3,I2	
	33		MOVE M 6,I3	
			MOVE M 0,REAL1	

WRITING USER PROGRAMS

17	34		MOVE 3,J
	35		ADD 3,ARYNAM
	36		MOVEM 7,777777(3)
18	37		MOVEM 1,ARYELM
19	40		MOVEM 2,INT1
20	41		MOVEI 5,0
	42		MOVEI 5,0
	43		DMOVEM 4,DBLPRC
	44		MOVEI 2,55
21	45		MOVEM 2,OCT
22	46		MOVE 2,[552633053500]
	47		MOVEM 2,LIT
25	50	2M:	MOVE 16,A0016
	51		MOVE 0,REAL1
	52		MOVEM 0,@0(16)
	53		MOVE 0,ARYELM
	54		MOVEM 0,@2(16)
	55		MOVE 0,INT1
	56		MOVEM 0,@3(16)
	57		DMOVE 0,DBLPRC
	60		DMOVEM 0,@4(16)
	61		MOVE 0,OCT
	62		MOVEM 0,@5(16)
	63		MOVE 0,LIT
	64		MOVEM 0,@6(16)
	65		POPJ 17,0

ARGUMENT BLOCKS:

SUB1	66	67	1M:	0,,0
		[ NO ERRORS DETECTED ]		0,,0

## WRITING USER PROGRAMS

To convert existing MACRO-10 programs conveniently so that they will still load and execute correctly when called from F40 or FORTRAN-10:

1. Transfer the initial entry sequence for a routine to

```
entry:    CAIA
          PUSH 17,CEXIT.##
```

2. Change all returns to POPJ 17,0

These are the functions performed by the HELLO and GOODBY macros. These macros (available in the file FORPRM.MAC, part of the FOROTS release) were successfully used to convert the library routines to run with both F40 and FORTRAN-10.

In addition, since the FORTRAN-10 compiler uses the indirect bits on argument lists (note that this permits shared, pure code argument lists), it is essential for code that accesses parameters to take this into account. Specifically, sequences that obtained the values of parameters through use of operations such as

```
HRRZ R,1(16)
```

to pick up the address of the second argument should be changed to

```
MOVEI R,@1(16)
```

The latter operation will work when interfacing with either F40 or FORTRAN-10.

Refer to the previous example, which illustrates the code generated by the FORTRAN-10 compiler, for specific details of how each argument is accessed. Note that in the case of the formal array, it is the address of the array that is accessed.

### C.3.7 Mixing FORTRAN-10 and F40 Compiled Programs

Starting with Version 1A of LINK-10, use of the switch /MIXFOR will permit loading FORTRAN-10 and F40 programs. This is achieved by modifying the code while it is loaded.

This introduces extra code that results in a degradation of the execution of programs so loaded. This feature is provided as a convenience for conversion. It is not intended to be used for other than conversion assistance.

### C.3.8 Interaction with COBOL-10

The FORTRAN-10 programmer may call COBOL-10 programs as subprograms, and, conversely, the COBOL programmers may call FORTRAN-10 programs as subprograms.

In either of the foregoing cases, I/O operation must not be performed in the called subprogram.

C.3.8.1 Calling FORTRAN-10 Subprograms from COBOL-10 Programs - COBOL programmers may write subprograms in FORTRAN-10 to use the conveniences and facilities provided by this language. The COBOL verb ENTER is used to call FORTRAN-10 subroutines. The form of ENTER is as follows:

ENTER FORTRAN program name  $\left[ \begin{array}{c} \text{USING } \left\{ \begin{array}{l} \text{identifier1} \\ \text{literal1} \\ \text{procedure name1} \end{array} \right\} \\ , \left\{ \begin{array}{l} \text{identifier2} \\ \text{literal2} \\ \text{procedure2} \end{array} \right\} \\ \dots \end{array} \right]$

The USING clause of the foregoing forms names the data within the COBOL program that is to be passed to the called FORTRAN-10 subprogram. The passed data must be in a form acceptable to FORTRAN-10.

The calling sequence used by COBOL in calling a FORTRAN-10 subprogram is:

```
MOVEI 16, address of first entry in argument list
PUSHJ 17, subprogram address
```

If the USING clause appears in the ENTER statement, the compiler creates an argument list that contains an entry for each identifier or literal in the order of appearance in the USING clause. It is preceded by a word containing, in its left half, the negative number of the number of entries in the list. If no USING clause is present, the argument list contains an empty word, and the preceding word is set to 0. Each entry in the list is one 36-bit word at the form:

0-8	9-12	13-35
0	type	address

Bits 0-8 are always 0.

Bits 9-12 contain a type code that indicates the USAGE of the argument.

Bits 13-35 contain the address of the argument of the first word of the argument; the address can be indexed or indirect.

Following is a description of the types, their codes, how the codes appear in the argument list, and the locations specified by the addresses.

#### 1. For 1-word COMPUTATIONAL items

CODE:	2
IN ARGUMENT LIST:	XWD 100, address
ADDRESS:	that of the argument itself

#### 2. For 2-word COMPUTATIONAL items

CODE:	11
IN ARGUMENT LIST:	XWD 440, address
ADDRESS:	that of the high-order word of the argument

#### 3. For COMPUTATIONAL-1 items

CODE:	4
IN ARGUMENT LIST:	XWD 200, address
ADDRESS:	that of the argument itself

## WRITING USER PROGRAMS

### 4. For DISPLAY-6 and DISPLAY-7 items

CODE: 15  
IN ARGUMENT LIST: XWD 640, address  
ADDRESS: that of a 2-word descriptor for the argument  
WORD1: a byte pointer to the identifier or literal  
WORD2: bit 0 is 1 if the item is numeric  
bit 1 is 1 if the item is signed  
bit 2 is 1 if the item is a figurative constant (including ALL)  
bit 3 is 1 if the item is a literal  
bits 4 through 11 are reserved for expansion  
bit 12 is 1 if the item has a PICTURE with one or more Ps just before the decimal point, e.g., 99PPV.  
bits 13 through 17 are the number of decimal places. If bit 12 is 1, this is the number of Ps.  
bits 18 through 35 contain the size of the item in bytes.

### 5. For procedure names (which cannot be used for calls to COBOL subprograms)

CODE: 7  
IN ARGUMENT LIST: XWD 340, address  
ADDRESS: that of the procedure

The return from a subprogram (via POPJ 17,) is to the statement after the call.

C.3.8.2 Calling COBOL-10 Subroutines from FORTRAN-10 Programs - To call COBOL subroutines use the standard subroutine calling mechanism:

CALL COBOLS (args...) subroutine call  
X=COBOLS (args...) function call

You must have compiled the COBOL subroutine using the COBOL compiler described in the DECsystem-10 COBOL Programmer's Reference Manual.

### C.3.9 LINK-10 Overlay Facilities

LINK-10 provides several routines that are accessible directly from a FORTRAN-10 program. These routines are presented here briefly, together with the FORTRAN-10 specification of their parameters. In general, LINK-10 performs these functions automatically. These routines are available only for your convenience. Full details of the use of the overlay facilities can be found in the LINK-10 Reference Manual.

C.3.9.1 Conventions - The following terms are used to describe the parameters to LINK-10 overlay routines.

File spec	A literal constant consisting of device: filename.ext [directory]
Name	A LINK name or number that is a literal constant or variable.
List of link names	A sequence of name items separated by commas.

The routines available are:

INIOVL	(File spec) Used to specify the overlay file to be found if the load time specification is to be overridden.
GETOVL	(List of link names) Used to change the overlay structure in core.
RUNOVL	(Name) Loads the specified LINK and transfers to that LINK.
REMOVL	(List of link names) Removes the specified LINKs from core.
LOGOVL	(File spec) Used to specify where the log file is to be written. If no arguments are given, the log file is closed.

For a full description of these routines, refer to the LINK-10 Reference Manual.

#### C.3.10 FOROTS/FORSE Compatibility

The information presented in Sections C.3.10.1 and C.3.10.2 is intended only for those users who have programs and data files that were developed using the F40 FORTRAN compiler and the FORSE object time system. The following sections describe the manner in which both upward and downward compatibility between the FORTRAN-10, FOROTS and F40, FORSE FORTRAN systems may be achieved.

C.3.10.1 FORTRAN-10/F40 Data File Compatibility - Table C-2 describes upward compatibility of data files (FORSE TO FOROTS). Table C-3 describes downward compatibility of data files (FOROTS TO FORSE).

## WRITING USER PROGRAMS

Table C-2  
Upward Compatibility (FORSE TO FOROTS)

FORSE File Type	May Be read By FOROTS	In The Following Manner:
1. Sequential ASCII	Yes	May be read directly; record positioning operations, e.g., BACKSPACE, SKIP RECORD, may be used.
2. Sequential Binary	Yes	May be read directly in a forward fashion only; record positioning operations are not permitted.
3. Sequential Mixed files	Yes	May be read directly in a forward fashion only; record positioning operations not permitted.
4. Random Access ASCII Files	No {	NOTE: We suggest that a random access file be read (using FORSE) and be rewritten as a sequential file that can be accepted by FOROTS.
5. Random Access Binary Files	No }	

C.3.10.2 Converting FOROTS Data Files to FORSE-Acceptable Form - The following paragraphs describe procedures that may be used to convert FOROTS sequential mixed, random access ASCII, and random access binary data files into a form that can be read by FORSE.

Conversion of FOROTS Sequential Mixed Files - We suggest the following procedure to convert a FOROTS sequential mixed file into either a sequential ASCII or sequential binary file acceptable to FORSE.

1. Prepare and run a FORTRAN-10 I/O program that will produce either a sequential ASCII or a sequential binary output file.
2. If a sequential ASCII file is produced, it must be line-blocked before it can be read by FORSE. Line-blocking is accomplished by copying the file using either the system COPY command (with an A switch) or PIP. The copy will be line blocked and will be acceptable to FORSE. The following is an example of the command sequence needed to line-block the data file FOROT.DAT:

```
.COPY FOROT.DAT=FOROT.DATA/A
```

3. If a sequential binary file is produced, it must be record-blocked before it can be read by FORSE. Record-blocking is accomplished using the /K feature of the program BAKWDS. The following is an example of the command sequence needed to record-block the data file FOROT.DAT:

```
.R BAKWDS  
*FOROT.DAT=FOROT.DAT/K
```

## WRITING USER PROGRAMS

Table C-3  
Downward Compatibility (FOROTS TO FORSE)

FOROTS File Type	May Be Read By FORSE	In The Following Manner:
1. Sequential ASCII File	Yes	<p>This operation is permitted if the file is line-blocked. This may be accomplished by making a copy of the file using either the system copy command (with an A switch) or the PIP program. The resulting copy will be line-blocked.</p> <p>An example of the command sequence needed to line block a FOROTS file, using PIP, follows:</p> <pre>.R PIP *FOROTS.DAT=FOROTS.DAT/A</pre>
2. Sequential Binary File	Yes	<p>This operation is permitted if the file is record-blocked. This type of blocking is accomplished by using the /K option of the program BAKWDS. The following is an example of a command sequence which record-blocks a file.</p> <pre>.R BAKWDS *FORSE.DAT=FOROTS.DAT/K</pre>
3. Sequential Mixed File	No	<p>(See Section C.3.10.2 for suggested conversion procedure.)</p>
4. Random Access ASCII File	No	<p>(See Section C.3.10.2 for suggested conversion procedure.)</p>
5. Random Access Binary File	No	<p>(See Section C.3.10.2 for suggested conversion procedure.)</p>

## WRITING USER PROGRAMS

Conversion of FOROTS Random Access ASCII Files - We suggest the following procedure to convert a FOROTS random access ASCII file into a form acceptable to FORSE.

1. Prepare and run a FORTRAN-10 I/O program that will create a sequential ASCII file consisting of the records of the random access file.
2. Line-block the sequential ASCII file using either the system COPY command (with an A switch) or the PIP program. The following is an example of the COPY command:

```
.COPY LNBLK.DAT=SEQFL.DAT/A
```

The foregoing command would produce a line-blocked copy (LNBLK.DAT) of the sequential file SEQFL.DAT.

3. Prepare and run an F40 I/O program that will read the file produced in step 2 and will rewrite the file as a FORSE generated random access file.

Conversion of FOROTS Random Access Binary Files - We suggest the following procedure to convert a FOROTS random access binary file into a form acceptable to FORSE.

1. Prepare and run a FORTRAN-10 I/O program that will create a sequential binary file consisting of the records of the random access file.
2. Record-block the sequential file. This is accomplished by using the /K feature of the program BAKWDS. The following example illustrates the command sequence required to convert the file FOROTS.DAT into the record-blocked file FORBLK.DAT.

```
.R BAKWDS  
*FORBLK.DAT=FOROTS.DAT/K
```

3. An F40 I/O program may then be written to convert the sequential record-blocked file into a FORSE generated random access file.

C.3.10.3 General Restrictions - Observe the following restriction during the preparation of FORTRAN-10 programs and data files:

CHAIN functions (as implemented for the F40 compiler) are not implemented in FORTRAN-10. An overlay capability that is greatly superior to CHAIN is available with LINK-10 version 2.



APPENDIX D  
FOROTS

This appendix describes the facilities that FOROTS provides for the FORTRAN user. FOROTS implements all standard FORTRAN I/O operations as set forth in the "American National Standard FORTRAN, ANSI X3.9-1966." In addition it provides the user with capabilities and programming features beyond those defined in the ANSI standard.

The primary function of FOROTS is to act as a direct interface between user object programs and the DECSYSTEM-10 monitor during input and output operations. Other capabilities include:

1. Job initialization
2. Channel and core management
3. Error handling and reporting
4. File management
5. Formatting of data
6. Mathematical library
7. User library (non-mathematical)
8. Specialized applications packages
9. Overlay facilities
10. F40 compatibility

D.1 HARDWARE AND SOFTWARE REQUIREMENTS

You can run FOROTS on a DECSYSTEM-10 KA10, KI10, or KL10 processor. FOROTS may interface with all DECSYSTEM-10 peripheral devices. In addition to monitor or user program requirements, a minimum of 14 pages of user core is needed to run FOROTS.

## FOROTS

The software required with FOROTS is the 5.06 monitor or a later version. Other software items that can be associated with FOROTS include:

1. The MACRO-10 assembler (version 47 or later)
2. The LINK-10 loader (version 1A or later)
3. The system program COMPILE (version 22 or later) and
4. The FORTRAN-10 compiler (version 1 or later)

### D.2 FEATURES OF FOROTS

The following list briefly describes many specific features; more detailed information concerning the implementation of these features is given later in this appendix.

1. Your program may run in either batch or timesharing mode without requiring a program change. All differences between batch mode and timesharing mode operations are resolved by FOROTS.
2. Your programs may access both directory and non-directory devices in the same manner.
3. FOROTS helps provide complete data file compatibility between all DECsysten-10 devices.
4. FOROTS does not require line-blocking (a requirement that each output buffer must contain only an integral number of lines).
5. Up to 15 data files may be accessed simultaneously. Any number or all of the open data files may be accessed randomly.
6. FOROTS treats devices located at remote stations similarly to local devices.
7. Programs written for magnetic tape operations will run correctly on disk under FOROTS supervision. FOROTS simulates the commands needed for magnetic tape operations.
8. You may change or specify object program device and file specifications via a FOROTS interactive dialogue mode.
9. Non-FORTRAN binary data files may be read in image mode by FOROTS.
10. FOROTS provides interactive program/operating system error processing routines. These routines permit you to route the execution of the program to specific error processing routines whenever designated types of errors are detected.
11. An error traceback facility for fatal errors provides a history of all subprogram calls made back to the main program at the address of the point where the error occurred.

12. FOROTS provides a trap handling system for arithmetic functions, including default values and error reports.
13. You may mix ASCII and binary records in the same file, and both may be accessed in either sequential or random access mode.
14. FOROTS permits your program to switch from READ to WRITE on the same I/O device without loss of data or buffering.
15. Although primarily designed for use with the FORTRAN-10 compiler, you may also use FOROTS as an independent I/O system, as an I/O system for MACRO-10 object programs, and for FORTRAN-10 and F40 object programs.

#### D.3 ERROR PROCESSING

Whenever a run-time error is detected, the FOROTS error processing system takes control of program execution. This system determines the class of the error and either outputs an appropriate message at the controlling terminal or branches the program to a predesignated processing routine.

#### D.4 INPUT/OUTPUT FACILITIES

FOROTS uses monitor-buffered I/O during all modes of access except DUMP mode. Display devices are supported in dump mode; formatted text is handled in ASCII line mode; unformatted files are accessed as FORTRAN binary files. (Refer to DECsystem-10 Monitor Calls Manual.)

The following paragraphs describe I/O data channel and access modes.

##### D.4.1 Input/Output Channels Used Internally by FOROTS

Fifteen software channels (1 through 15) are available in I/O operations. Software channel 0 is reserved for the following system functions:

1. The printing of error messages, and
2. The loading and initialization of FOROTS (GETSEG UUO operations)

Software channels 1 through 15 are available for user program data transfer operations. When a request is made for a data channel, a table is scanned until a free channel is found. The first free channel is assigned to the requesting program; on completion of the assigned transfer, control of the software channel is returned to FOROTS.

D.4.2 File Access Modes

Data may be transferred between processor storage and peripheral devices in two major modes - sequential and random.

D.4.2.1 Sequential Transfer Mode - In sequential data transfer operations, the records involved are transferred in the same order as they appear in the source file. Each I/O statement executed in this mode transfers the record immediately following the last record transferred from the accessed source file. A special version of the sequential mode (referred to as APPEND) is available for output (write) operations. The special APPEND mode permits you to write a record immediately after the last logical record of the accessed file. During the APPEND operation, the records already in the accessed file remain unchanged; the only function performed is the appending of the transferred records to the end of the file.

You must specify transfer modes (other than SEQINOUT) by setting the ACCESS option of a FORTRAN-10 OPEN statement to one of several possible arguments. For the sequential mode, the arguments are

```
ACCESS='SEQIN' (sequential read-only mode)
ACCESS='SEQOUT' (sequential write-only mode)
ACCESS='SEQINOUT' (sequential read followed by a sequential
                   write)
ACCESS='APPEND' (sequential Append mode)
```

D.4.2.2 Random Access Mode - This transfer mode permits records to be accessed and transferred from a source file in any desired order. Random access transfers must be made between processor core and a device (disk) that permits random addressing operations to files that have been set up for random access. Files for random access must contain a specified number of identically sized records that may be individually accessed by a record number.

You may accomplish random access transfers in either a read/write mode or a special read-only mode. You must specify random transfer modes by setting the ACCESS option of an OPEN statement to one of several possible arguments.

```
ACCESS='RANDOM' (random read/write mode)
ACCESS='RANDIN' (random special read-only mode)
```

D.5 ACCEPTABLE TYPES OF DATA FILES AND THEIR FORMATS

The following paragraphs describe the types of data files that are acceptable to FOROTS.

D.5.1 ASCII Data Files

Each record within an ASCII data file consists of a set of contiguous 7-bit characters. A vertical paper-motion character, such as, a Form Feed, a Vertical Tab, or a Line Feed, terminates each set. All ASCII records start on a word boundary; the last word in a record is padded with nulls, if necessary, to ensure that the record also ends on a word boundary. Logical records may be split across physical blocks. There is no implied maximum length for logical records.

## NOTE

On sequential input, FOROTS does not require conformation to word boundaries; it reads what it sees. Therefore, any file that is written by FOROTS will conform to the foregoing format requirements.

D.5.2 FORTRAN Binary Data Files

Each logical record in a FORTRAN binary data file contains data that the executing program may reference with either a READ or WRITE statement. A logical record is preceded by a control word and may have one or more control words embedded within it. In FORTRAN binary data files, there is no relationship between logical records and physical device block sizes. There is no implied maximum length for logical records.

D.5.2.1 Format of Binary Files - A FOROTS binary file may contain three forms of Logical Segment Control Words (LSCW). These LSCWs give FOROTS the ability to distinguish ASCII files from binary files.

LSCW	
START	001+ the number of words in the segment (exclusive of any "END" LSCWs)
CONTINUE	002 indicates that the segment of a disk block boundary continues
END	003+ number of words in the preceding segment including LSCWs.

If the access you specify for a file (through the OPEN statement ACCESS = parameter) is 'SEQIN', 'SEQOUT', or 'SEQINOUT', all three LSCWs may appear in a record. If the access you specify is 'RANDIN', or 'RANDOM', all records are of the same length, and there are no CONTINUE LSCWs.

The following examples illustrate the LSCW. The random access binary file contains only 001 and 003 LSCWs.

```
C      LOOK AT A BINARY FILE AND SEE THE LOGICAL SEGMENT
C      CONTROL WORDS.

OPEN(UNIT=1,ACCESS='RANDOM',MODE='BINARY',
     1      RECORD=100)

I=5
WRITE(1'1) (I, J=1,100)

J=7
WRITE(1'2) (J,K=1,100)
END
```

## FOROTS

000000	001000	000145	← Number of words in record counting	000064	000000	000005
002001	000000	000005	END LSCW or the number of words following this word to the END LSCW.	000065	000000	000005
002002	000000	000005		000066	000000	000005
002003	000000	000005		000067	000000	000005
002004	000000	000005		000070	000000	000005
002005	000000	000005		000071	000000	000005
002006	000000	000005		000072	000000	000005
002007	000000	000005		000073	000000	000005
002010	000000	000005		000074	000000	000005
002011	000000	000005		000075	000000	000005
002012	000000	000005		000076	000000	000005
002013	000000	000005		000077	000000	000005
002014	000000	000005		000100	000000	000005
002015	000000	000005		000101	000000	000005
002016	000000	000005		000102	000000	000005
002017	000000	000005		002103	000000	000005
002020	000000	000005		000104	000000	000005
002021	000000	000005		002105	000000	000005
002022	000000	000005		002106	000000	000005
002023	000000	000005		000107	000000	000005
002024	000000	000005		000110	000000	000005
002025	000000	000005		000111	000000	000005
002026	000000	000005		000112	000000	000005
002027	000000	000005		000113	000000	000005
002030	000000	000005		000114	000000	000005
002031	000000	000005		000115	000000	000005
002032	000000	000005		000116	000000	000005
002033	000000	000005		000117	000000	000005
002034	000000	000005		000120	000000	000005
002035	000000	000005		000121	000000	000005
002036	000000	000005		000122	000000	000005
002037	000000	000005		000123	000000	000005
002040	000000	000005		000124	000000	000005
002041	000000	000005		000125	000000	000005
002042	000000	000005		000126	000000	000005
002043	000000	000005		000127	000000	000005
002044	000000	000005		000130	000000	000005
002045	000000	000005		000131	000000	000005
002046	000000	000005		000132	000000	000005
002047	000000	000005		000133	000000	000005
002050	000000	000005		000134	000000	000005
002051	000000	000005		000135	000000	000005
002052	000000	000005		000136	000000	000005
002053	000000	000005		000137	000000	000005
002054	000000	000005		000140	000000	000005
002055	000000	000005		000141	000000	000005
002056	000000	000005		000142	000000	000005
002057	000000	000005		000143	000000	000005
002060	000000	000005		000144	000000	000005
002061	000000	000005		000145	003000	000146 ← END LSCW Containing the number of words in the record including LSCW's.
002062	000000	000005		000146	001000	000145
002063	000000	000005		000147	000000	000007
				000150	000000	000007

## FOROTS

000151	000000	000007	000233	000000	000007
000152	000000	000007	000234	000000	000007
000153	000000	000007	000235	000000	000007
000154	000000	000007	000236	000000	000007
000155	000000	000007	000237	000000	000007
000156	000000	000007	000240	000000	000007
000157	000000	000007	000241	000000	000007
000160	000000	000007	000242	000000	000007
000161	000000	000007	000243	000000	000007
000162	000000	000007	000244	000000	000007
000163	000000	000007	000245	000000	000007
000164	000000	000007	000246	000000	000007
000165	000000	000007	000247	000000	000007
000166	000000	000007	000250	000000	000007
000167	000000	000007	000251	000000	000007
000170	000000	000007	000252	000000	000007
000171	000000	000007	000253	000000	000007
000172	000000	000007	000254	000000	000007
000173	000000	000007	000255	000000	000007
000174	000000	000007	000256	000000	000007
000175	000000	000007	000257	000000	000007
000176	000000	000007	000260	000000	000007
000177	000000	000007	000261	000000	000007
000200	000000	000007	000262	000000	000007
000201	000000	000007	000263	000000	000007
000202	000000	000007	000264	000000	000007
000203	000000	000007	000265	000000	000007
000204	000000	000007	000266	000000	000007
000205	000000	000007	000267	000000	000007
000206	000000	000007	000270	000000	000007
000207	000000	000007	000271	000000	000007
000210	000000	000007	000272	000000	000007
000211	000000	000007	000273	000000	000007
000212	000000	000007	000274	000000	000007
000213	000000	000007	000275	000000	000007
000214	000000	000007	000276	000000	000007
000215	000000	000007	000277	000000	000007
000216	000000	000007	000300	000000	000007
000217	000000	000007	000301	000000	000007
000220	000000	000007	000302	000000	000007
000221	000000	000007	000303	000000	000007
000222	000000	000007	000304	000000	000007
000223	000000	000007	000305	000000	000007
000224	000000	000007	000306	000000	000007
000225	000000	000007	000307	000000	000007
000226	000000	000007	000310	000000	000007
000227	000000	000007	000311	000000	000007
000230	000000	000007	000312	000000	000007
000231	000000	000007	000313	003000	000146
000232	000000	000007			

In the sequential access binary file, the second record crosses the 128-word disk boundary and contains a 002 (CONTINUE) LSCW.

```
C      LOOK AT A BINARY FILE AND SEE THE LOGICAL SEGMENT
C      CONTROL WORDS.

OPEN(UNIT=1,MODE='BINARY')

I=5
WRITE(1) (I, J=1,100)

J=7
WRITE(1) (J,K=1,100)
END
```

00:0000	001000	000145	00:0043	000000	000005
00:0001	000000	000005	00:0044	000000	000005
00:0002	000000	000005	00:0045	000000	000005
00:0003	000000	000005	00:0046	000000	000005
00:0004	000000	000005	00:0047	000000	000005
00:0005	000000	000005	00:0050	000000	000005
00:0006	000000	000005	00:0051	000000	000005
00:0007	000000	000005	00:0052	000000	000005
00:0010	000000	000005	00:0053	000000	000005
00:0011	000000	000005	00:0054	000000	000005
00:0012	000000	000005	00:0055	000000	000005
00:0013	000000	000005	00:0056	000000	000005
00:0014	000000	000005	00:0057	000000	000005
00:0015	000000	000005	00:0060	000000	000005
00:0016	000000	000005	00:0061	000000	000005
00:0017	000000	000005	00:0062	000000	000005
00:0020	000000	000005	00:0063	000000	000005
00:0021	000000	000005	00:0064	000000	000005
00:0022	000000	000005	00:0065	000000	000005
00:0023	000000	000005	00:0066	000000	000005
00:0024	000000	000005	00:0067	000000	000005
00:0025	000000	000005	00:0070	000000	000005
00:0026	000000	000005	00:0071	000000	000005
00:0027	000000	000005	00:0072	000000	000005
00:0030	000000	000005	00:0073	000000	000005
00:0031	000000	000005	00:0074	000000	000005
00:0032	000000	000005	00:0075	000000	000005
00:0033	000000	000005	00:0076	000000	000005
00:0034	000000	000005	00:0077	000000	000005
00:0035	000000	000005	00:0100	000000	000005
00:0036	000000	000005	00:0101	000000	000005
00:0037	000000	000005	00:0102	000000	000005
00:0040	000000	000005	00:0103	000000	000005
00:0041	000000	000005	00:0104	000000	000005
00:0042	000000	000005	00:0105	000000	000005

## FOROTS

000106	000000	000005	000173	000000	000007	
000107	000000	000005	000174	000000	000007	
000110	000000	000005	000175	000000	000007	
000111	000000	000005	000176	000000	000007	
000112	000000	000005	000177	000000	000007	
000113	000000	000005	000200	000000	000114 ← Continue LSCW.	
000114	000000	000005	000201	000000	000007	
000115	000000	000005	000202	000000	000007	
000116	000000	000005	000203	000000	000007	
000117	000000	000005	000204	000000	000007	
000120	000000	000005	000205	000000	000007	
000121	000000	000005	000206	000000	000007	
000122	000000	000005	000207	000000	000007	
000123	000000	000005	000210	000000	000007	
000124	000000	000005	000211	000000	000007	
000125	000000	000005	000212	000000	000007	
000126	000000	000005	000213	000000	000007	
000127	000000	000005	000214	000000	000007	
000130	000000	000005	000215	000000	000007	
000131	000000	000005	000216	000000	000007	
000132	000000	000005	000217	000000	000007	
000133	000000	000005	000220	000000	000007	
000134	000000	000005	000221	000000	000007	
000135	000000	000005	000222	000000	000007	
000136	000000	000005	000223	000000	000007	
000137	000000	000005	000224	000000	000007	
000140	000000	000005	000225	000000	000007	
000141	000000	000005	000226	000000	000007	
000142	000000	000005	000227	000000	000007	
000143	000000	000005	000230	000000	000007	
000144	000000	000005	000231	000000	000007	
000145	003000	00146	000232	000000	000007	
000146	001000	00032	← Number of words to next LSCW.	000233	000000	000007
000147	000000	00007	000234	000000	000007	
000150	000000	00007	000235	000000	000007	
000151	000000	00007	000236	000000	000007	
000152	000000	00007	000237	000000	000007	
000153	000000	00007	000240	000000	000007	
000154	000000	00007	000241	000000	000007	
000155	000000	00007	000242	000000	000007	
000156	000000	00007	000243	000000	000007	
000157	000000	00007	000244	000000	000007	
000160	000000	00007	000245	000000	000007	
000161	000000	00007	000246	000000	000007	
000162	000000	00007	000247	000000	000007	
000163	000000	00007	000250	000000	000007	
000164	000000	00007	000251	000000	000007	
000165	000000	00007	000252	000000	000007	
000166	000000	00007	000253	000000	000007	
000167	000000	00007	000254	000000	000007	
000170	000000	00007	000255	000000	000007	
000171	000000	00007	000256	000000	000007	
000172	000000	00007	000257	000000	000007	

## FOROTS

00260	000000	000007	00277	000000	000007
00261	000000	000007	00280	000000	000007
00262	000000	000007	00281	000000	000007
00263	000000	000007	00282	000000	000007
00264	000000	000007	00283	000000	000007
00265	000000	000007	00284	000000	000007
00266	000000	000007	00285	000000	000007
00267	000000	000007	00286	000000	000007
00270	000000	000007	00287	000000	000007
00271	000000	000007	00288	000000	000007
00272	000000	000007	00289	000000	000007
00273	000000	000007	00290	000000	000007
00274	000000	000007	00291	000000	000007
00275	000000	000007	00292	000000	000007
00276	000000	000007	00293	000000	000147

Image mode files contain no LSCWs. You cannot backspace this file.

C        LOOK AT AN IMAGE MODE FILE AND SEE NO LOGICAL SEGMENT  
C        CONTROL WORDS.

```
OPEN(UNIT=1,MODE='IMAGE')

I=5
WRITE(1) (I, J=1,100)

J=7
WRITE(1) (J,K=1,100)
END
```

002000	000000	000005	002024	000000	000005
002001	000000	000005	002025	000000	000005
002002	000000	000005	002026	000000	000005
002003	000000	000005	002027	000000	000005
002004	000000	000005	002028	000000	000005
002005	000000	000005	002029	000000	000005
002006	000000	000005	002030	000000	000005
002007	000000	000005	002031	000000	000005
002010	000000	000005	002032	000000	000005
002011	000000	000005	002033	000000	000005
002012	000000	000005	002034	000000	000005
002013	000000	000005	002035	000000	000005
002014	000000	000005	002036	000000	000005
002015	000000	000005	002037	000000	000005
002016	000000	000005	002040	000000	000005
002017	000000	000005	002041	000000	000005
002020	000000	000005	002042	000000	000005
002021	000000	000005	002043	000000	000005
002022	000000	000005	002044	000000	000005
002023	000000	000005	002045	000000	000005
			002046	000000	000005
			002047	000000	000005

## FOROTS

000050	000000	000005	000135	000000	000005
000051	000000	000005	000136	000000	000005
000052	000000	000005	000137	000000	000005
000053	000000	000005	000140	000000	000005
000054	000000	000005	000141	000000	000005
000055	000000	000005	000142	000000	000005
000056	000000	000005	000143	000000	000005
000057	000000	000005	000144	000000	000007
000060	000000	000005	000145	000000	000007
000061	000000	000005	000146	000000	000007
000062	000000	000005	000147	000000	000007
000063	000000	000005	000150	000000	000007
000064	000000	000005	000151	000000	000007
000065	000000	000005	000152	000000	000007
000066	000000	000005	000153	000000	000007
000067	000000	000005	000154	000000	000007
000070	000000	000005	000155	000000	000007
000071	000000	000005	000156	000000	000007
000072	000000	000005	000157	000000	000007
000073	000000	000005	000160	000000	000007
000074	000000	000005	000161	000000	000007
000075	000000	000005	000162	000000	000007
000076	000000	000005	000163	000000	000007
000077	000000	000005	000164	000000	000007
000100	000000	000005	000165	000000	000007
000101	000000	000005	000166	000000	000007
000102	000000	000005	000167	000000	000007
000103	000000	000005	000170	000000	000007
000104	000000	000005	000171	000000	000007
000105	000000	000005	000172	000000	000007
000106	000000	000005	000173	000000	000007
000107	000000	000005	000174	000000	000007
000110	000000	000005	000175	000000	000007
000111	000000	000005	000176	000000	000007
000112	000000	000005	000177	000000	000007
000113	000000	000005	000200	000000	000007
000114	000000	000005	000201	000000	000007
000115	000000	000005	000202	000000	000007
000116	000000	000005	000203	000000	000007
000117	000000	000005	000204	000000	000007
000120	000000	000005	000205	000000	000007
000121	000000	000005	000206	000000	000007
000122	000000	000005	000207	000000	000007
000123	000000	000005	000210	000000	000007
000124	000000	000005	000211	000000	000007
000125	000000	000005	000212	000000	000007
000126	000000	000005	000213	000000	000007
000127	000000	000005	000214	000000	000007
000130	000000	000005	000215	000000	000007
000131	000000	000005	000216	000000	000007
000132	000000	000005	000217	000000	000007
000133	000000	000005	000220	000000	000007
000134	000000	000005	000221	000000	000007

000222	000000	000007	002255	000000	000007
000223	000000	000007	002256	000000	000007
000224	000000	000007	002257	000000	000007
000225	000000	000007	002260	000000	000007
000226	000000	000007	002261	000000	000007
000227	000000	000007	002262	000000	000007
000230	000000	000007	002263	000000	000007
000231	000000	000007	002264	000000	000007
000232	000000	000007	002265	000000	000007
000233	000000	000007	002266	000000	000007
000234	000000	000007	002267	000000	000007
000235	000000	000007	002270	000000	000007
000236	000000	000007	002271	000000	000007
000237	000000	000007	002272	000000	000007
000240	000000	000007	002273	000000	000007
000241	000000	000007	002274	000000	000007
000242	000000	000007	002275	000000	000007
000243	000000	000007	002276	000000	000007
000244	000000	000007	002277	000000	000007
000245	000000	000007	002300	000000	000007
000246	000000	000007	002301	000000	000007
000247	000000	000007	002302	000000	000007
000250	000000	000007	002303	000000	000007
000251	000000	000007	002304	000000	000007
000252	000000	000007	002305	000000	000007
000253	000000	000007	002306	000000	000007
000254	000000	000007	002307	000000	000007

#### D.5.3 Mixed Mode Data Files

FOROTS permits files containing both ASCII and binary data records to be read. Mixed files may be accessed in either sequential or random access mode. Logical ASCII and binary records have the same format as described in the preceding paragraphs. In random access mode, the record size must be large enough to contain the largest record, either ASCII or binary.

**D.5.4 Image Files**

The image data transfer mode is a buffered mode in which data is transferred in a blocked format consisting of a word count located in the right half of the first data word of the buffer followed by the number of 36-bit data words. The devices that permit image data transfers and the form in which the data is read or written are:

Device	Data Forms
Card Punch	In image mode, each buffer contains three 12-bit bytes. Each byte corresponds to one card column. Since there is room for 81 columns in the buffer ( $3 \times 27$ ) and there are only 80 columns on a card, the last word contains only 2 bytes of data; the third byte is thrown away. Image mode causes exactly one card to be punched for each output. The CLOSE punches the last partial card and then punches an EOF card.
Card Reader	All 12 punches in all 80 columns are packed into the buffer as 12-bit bytes. The first 12-bit byte contains column 1. The last word of the buffer contains columns 79 and 80 as the left and middle bytes, respectively. Cards are not split between two buffers.
Disk	Data is written on the disk exactly as it appears in the buffer. Data consists of 36-bit words.
Magnetic Tape	Data appears on magnetic tape exactly as it appears in the buffer. No processing or checksumming of any kind is performed by the service routine. The parity checking of the magnetic tape system is sufficient assurance that the data is correct. All data, both binary and ASCII, is written with odd parity and at 800 bits per inch unless changed by the installation.
Paper Tape Punch	Binary words taken from the output buffer are split into six 6-bit bytes and punched with the eighth hole punched in each frame. No format control or checksumming is performed by the I/O routine. Data punched in this mode is read back by the paper tape reader in the same mode.
Paper Tape Reader	Characters not having the eighth hole punched are ignored. Characters are truncated to six bits and packed six to the word without further processing. This mode is useful for reading binary tapes having arbitrary blocking format.
Plotter	Six 6-bit characters per word are transmitted to the plotter exactly as they appear in the buffer.

**D.6 USING FOROTS**

FOROTS has been designed to lend itself for use as an I/O system for programs written in languages other than FORTRAN. Currently, MACRO programmers may employ FOROTS as a general I/O system by writing

## FOROTS

simple MACRO calls that simulate the calls made to FOROTS by a FORTRAN compiler. The calls made to FOROTS are to routines that implement FORTRAN I/O statements such as READ, WRITE, OPEN, CLOSE, RELEASE, etc.

FOROTS will provide automatic memory allocation, data conversion, I/O buffering, and device interface operations to the MACRO user.

### D.6.1 FOROTS Entry Points

FOROTS provides the following entry points for calls from either a FORTRAN compiler or a non-FORTRAN program:

Entry Point	Function
ALCHN.	Allocate software channels
ALCOR.	Allocate dynamic core blocks
CLOSE.	Close a file
DBMS.	DBMS interface
DEC.	DECODE routine
DECHN.	De-allocate software channels
DECOR.	De-allocate dynamic core blocks
ENC.	ENCODE routine
EXIT.	Terminate program execution
FIN.	Input/Output list termination routine
FIND.	Position to the next record (RANDOM ACCESS)
FORER.	Error processor
FUNCT.	Overlay interface
IN.	Formatted input routine
IOLST.	Input/Output list routine
MTOP.	File utility processing routine
NLI.	NAMELIST input routine
NLO.	NAMELIST output routine
OPEN.	Open a file
OUT.	Formatted output routine
RELEA.	Release a device (CLOSE implied)
RESET.	Job initialization entry
RTB.	Binary input routine
TRACE.	Trace subroutine calls
WTB.	Binary output routine

### D.6.2 Calling Sequences

You must use the following general form for all calls made to FOROTS:

```
MOVEI 16,ARGBLK  
PUSHJ 17,Entry Point  
(control is returned here)
```

where:

1. ARGBLK is the address of a specifically formatted argument block that contains information needed by FOROTS to accomplish the desired operation.
2. Entry Point is an entry point identifier (see list given in Paragraph D.6.1) that specifies the entry point of the desired FOROTS routine.

With three exceptions, all returns from FOROTS will be made to the program instruction immediately following the call (PUSHJ 17, entry point instruction). The exceptions are:

1. An error return to a specified statement number, i.e., READ or WRITE statement ERR=option,
2. An end-of-file return to a statement number, i.e., READ or WRITE statement END=option,
3. A fatal error that returns to the monitor or to a debug package.

Paragraphs D.6.3.1 through D.6.3.11 give the MACRO calls and required argument block formats needed to initialize FOROTS and FOROTS I/O operations.

Argument blocks conform to the subprogram calling convention described in Appendix C. However, there is one exception in dealing with the first word of an I/O initialization call, i.e., WTB., ENC., RTW., etc., for a FORTRAN logical unit number. In previous versions of FOROTS and FORTRAN-10, if the indirect bit was not set, the argument was immediate; if it was set to 1 (one), the argument was the address of the variable. The type field was always 0 (zero).

With Version 4 of FORTRAN-10 and Version 4 of FOROTS this convention has been changed. If the type field of the first word of an I/O initialization call for the FORTRAN logical unit number is 0 (zero), the argument is an immediate mode (18 bit) constant wherever possible. If the type field is integer, the argument is indirect (see Appendix C, Table C-1, Type 2).

This exception should not cause any upward compatibility problems, since all previously working programs will still function. An added feature with this convention is that it permits the following construct to be correctly implemented:

```
N=-4           !SET FOR TERMINALS
      READ (N,100) I,J
100   FORMAT(2I5)
```

### D.6.3 MACRO Calls for FOROTS Functions

The following paragraphs describe the forms of the MACRO calls to FOROTS that are made by the FORTRAN-10 compiler. The calls described are identified according to the language statement that they implement. The following terms and abbreviations may be used in the description of the argument block (ARGBLK) of each call:

- = pointer to the second word in the argument block. (This is the address pointed to by the argument ARGBLK in the calling sequence.)
- n = count of ASCII characters,
- f = FORMAT statement address,
- v = the name of an array containing ASCII characters,
- list = an Input/Output list,

c = the statement to which control is transferred on an "END OF FILE" condition,  
d = the statement to which control is transferred on an "ERROR" condition,  
name = a NAMELIST name,  
R = a variable specifying the logical record number for random access mode,  
\* = list directed I/O; the FORMAT statement is not used,  
type = type specification of a variable or constant,

where ARGBLK is

0-8	9-12	13	14-17	18-35	
-6				0	
→ Reserved	type	I	X	n	
	7	I	X	c	
	7	I	X	d	
	type	I	X	f	
	type	I	X	Format Size (in words)	
↓ Reserved	type	I	X	v	

D.6.3.1 I/O Statements, Sequential Access Calling Sequences - The READ and WRITE statements for formatted sequential data transfer operations and their calling sequences are:

```
READ(u,f,END=c, ERR=d) list
MOVEI 16, ARGBLK
PUSHJ 17, IN.
```

and

```
WRITE(u,f,END=c, ERR=d) list
MOVEI 16, ARGBLK
PUSHJ 17, OUT.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
-5				0
→ Reserved	type	I	X	u
	7	I	X	c
	7	I	X	d
	type	I	X	f
↓ Reserved	type	I	X	Format Size (in words)

The READ and WRITE statements for unformatted sequential data transfer operations and their calling sequences are:

```
READ(u,END=c, ERR=d) list
MOVEI 16, ARGBLK
PUSHJ 17, RTB.
```

and

```
WRITE(u,END=c, ERR=d) list
MOVEI 16, ARGBLK
PUSHJ 17, WTB.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
-3				0
→ Reserved	type	I	X	u
	7	I	X	c
↓ Reserved	7	I	X	d

D.6.3.2 NAMELIST I/O, Sequential Access Calling Sequences - The READ and WRITE statements for NAMELIST-directed sequential data transfer operations and their calling sequences are:

```
READ (u,name)
READ (u, name, END=c, ERR=d)

MOVEI 16, ARGBLK
PUSHJ 17, NLI.
```

and

```
WRITE (u, name)
WRITE (u, name, END=c, ERR=d)

MOVEI 16, ARGBLK
PUSHJ 17, NLO.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
-4				0
→ Reserved	type	I	X	u
	7	I	X	c
	7	I	X	d
Reserved	type	I	X	NAMELIST table address

The NAMELIST table is generated from the FORTRAN NAMELIST. The first word of the table is the NAMELIST name; following that are a number of 2-word entries for scalar variables, and a number of (N+3)-word entries for array variables, where N is the dimensionality of the array.

The names you specify in the NAMELIST statement are stored, in SIXBIT form, first in the table. Each name is followed by a list of arguments associated with the name; this argument list may be of any length and is terminated by a zero entry. The name argument list may be in either a scalar or an array form (refer to the following diagrams).

D.6.3.3 Array Offsets and Factoring - Address calculations used to reference a given array element involve factors and offsets. For example:

Array A is dimensioned

DIMENSION A (L1/U1,L2/U2,L3/U3,...Ln/Un)

The size of each dimension is represented by

```
S1 = U1-L1+1
S2 = U2-L2+1
etc.
```

In order to calculate the address of an element referenced by

A (I1,I2,I3,...In)

the following formula is used:

$A + (I1-L1) + (I2-L2)*S1 + (I3-L3)*S2*S1 + \dots + (In-Ln)*S[n-1]*\dots*S2*S1$

The terms are factored out depending on the dimensions of the array and not on the element referenced to arrive at the formula

$A + (-L-L2*S1-L3*S2*S1\dots) + I1+I2*S1+I3*S2*S1\dots$

The parenthesized part of this formula is the offset for a single precision array and it is referred to as the Array Offset.

## FOROTS

For each dimension of a given array, there is a corresponding factor by which a subscript in that position will be multiplied. From the last expression, one can determine the factor for dimension n to be

$$S[n-1]*S[n-2]*...*S2*S1$$

For double-precision and complex arrays, the expression becomes

$$A+2*(I1-L1)+2*(I2-L2)*S1+2*(I3-L3)*S2+S1+...$$

Therefore, the array offset for a double-precision array is

$$2*(-L1-L2*S1-L3*S2*S1...)$$

and the factor for the nth dimension is

$$2*S[n-1]*S[n-2]*...*S2*S1$$

The factor for the first dimension of a double-precision array is always 2. The factor for the first dimension of a single-precision array is always 1.

SCALAR ENTRY in a NAMELIST Table

0 . . . 8	9 . . . 11	12 . . . 14	15 . . . 17	18 . . . 35
SIXBIT/SCALAR NAME/				
0	0	I	X	Scalar addr

ARRAY ENTRY in a NAMELIST Table

0-8	9-11	12-14	15-17	18-35
SIXBIT/ARRAY NAME/				
#DIMS	type	I	X	
ARRAY SIZE		I	X	OFFSET
		I	X	Factor 1
		I	X	Factor 2
		I	X	Factor 3
		I	X	.
		I	X	.
		I	X	Factor n

D.6.3.4 I/O Statements, Random Access Calling Sequences - The READ and WRITE statements for random access data transfer operations and their calling sequences are:

```
READ (u#R,f,END=c, ERR=d) list
READ (u#R,END=c, ERR=d) list
MOVEI 16, ARGBLK
PUSHJ 17, RTB.
```

and

```
WRITE (u#R,f,END=c, ERR=d) list
WRITE (u#R,END=c, ERR=d) list
MOVEI 16, ARGBLK
PUSHJ 17, WTB.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
-6				0
→ Reserved				u
	type	I	X	c
	7	I	X	d
	7	I	X	f
	type	I	X	format size (in words)
	type	I	X	address of Record Number
↓ Reserved	2	I	X	

f and the format size in words are 0 if the I/O statement is unformatted.

D.6.3.5 Calling Sequences for Statements That Use Default Devices - The FORTRAN-10 statements that require the use of a reserved system default device and their calling sequences are:

#### Default Device

```
ACCEPT f, list      UNIT=-4      (TTY)
READ f, list        UNIT=-5      (CDR)
REREAD f, list      UNIT=-6      (REREAD)

MOVEI 16, ARGBLK
PUSHJ 17, IN.
```

FOROTS

where ARGBLK is

0-8	9-12	13	14-17	18-35
-5				0
→ Reserved	2	I	X	u
	7	I	X	c
	7	I	X	d
	type	I	X	f
Reserved	type	I	X	Format Size (in words)

Default Device

```
PRINT f, list      UNIT=-3      (LPT)
PUNCH f, list     UNIT=-2      (PTP)
TYPE f, list      UNIT=-1      (TTY)
```

```
MOVEI 16, ARGBLK
PUSHJ 17, OUT.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
-5				0
→ Reserved	2	I	X	u
	7	I	X	c
	7	I	X	d
	type	I	X	f
Reserved	type	I	X	format size (in words)

D.6.3.6 Statements to Position Magnetic Tape Units - The formatted and unformatted FORTRAN-10 statements that may be used to control the positioning of a magnetic tape device and their calling sequences are:

Function (FORTRAN Statement)	FOROTS Code
SKIPFILE (u)	7
BACKFILE (u)	3
BACKSPACE (u)	2
ENDFILE (u)	4
REWIND (u)	0
SKIPRECORD (u)	5
UNLOAD (u)	1

CALL:

```
MOVEI 16, ARGBLK
PUSHJ 17, MTOP.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
-4				0
→ Reserved				u
	type	I	X	c
	7	I	X	d
	7	I	X	FOROTS code
↓ Reserved	type	I	X	

D.6.3.7 List Directed Input/Output Statements - You may write any form of a sequential Input/Output statement as a list-directed statement by replacing the referenced FORMAT statement number with an asterisk (\*). The list-directed forms of the READ and WRITE statements and their calling sequences are:

```
READ (u, *, END=c, ERR=d) list
```

```
MOVEI 16, ARGBLK
PUSHJ 17, IN.
```

and

```
WRITE (u, *, END=c, ERR=d) list
```

```
MOVEI 16, ARGBLK
PUSHJ 17, OUT.
```

## FOROTS

where ARGBLK is

0-8	9-12	13	14-17	18-35
-5				0
→ Reserved	2	I	X	u
	7	I	X	c
	7	I	X	d
	0	0	0	0
↓ Reserved	0	0	0	0

D.6.3.8 Input/Output Data Lists - The compiler generates a calling sequence to the runtime system if an I/O list is defined for the READ or WRITE statement. The argument block associated with the calling sequence contains the addresses of the variables and arrays to be transferred to or from an I/O buffer. The general form of an I/O list calling sequence is:

```
MOVEI 16, ARGBLK
PUSHJ 17, IOLST.
```

Any number of elements may be included in the ARGBLK. The end of the argument block is specified by a zero entry or a call to the FIN. entry.

Mnemonic Name	FOROTS Value
DATA	1
SLIST	2
ELIST	3
FIN	4

The elements of an I/O list are:

1. DATA

The DATA element converts one single- or double-precision or complex item from external to internal form for a READ statement and from internal to external form for a WRITE statement. Each DATA element has the following format.

0-8	9-12	13	14-17	18-35
DATA	type	I	X	SCALAR ADDR

## 2. SLIST

The SLIST argument converts an entire array from internal to external form or vice versa, depending on the type of statement, i.e., READ or WRITE, involved. An SLIST table has the following form:

0-8	9-12	13	14-17	18-35
SLIST		I	X	#ELEMENTS
0	type	I	X	INCREMENT
				BASE ADDR1.

For example, the sequence:

```
DIMENSION A(100),B(100)
READ(-,-)A
      or
READ(-,-)(A(I),I=1,100) !only when the /OPT switch is used
```

develops an SLIST argument of the form:

0-8	9-12	13	14-17	18-35
0				
2	0	0	0	144
0	0	0	0	1
0	2	0	0	A
4	0	0	0	0

More than one base address may appear in a SLIST as long as the increment is the same. The sequence

```
DIMENSION A(100), B(100)
WRITE (-,-) (A(I),B(I),I=100) ! only when the /OPT
                                switch is used
```

develops a SLIST argument of the form:

0-8	9-12	13	14-17	18-35
0				
2	0	0	0	144
0	0	0	0	1
0	2	0	0	A
0	2	0	0	B
4	0	0	0	0

## 3. ELIST

The SLIST format permits only a single increment for a number of arrays to be specified while the ELIST permits different increments to be specified for different arrays.

The format of the ELIST is

0-8	9-12	13	14-17	18-35
ELIST				No. Elements to transfer increment 1  Base ADDR 1 increment 2  Base ADDR 2 increment N  Base ADDR N

For example, the FORTRAN sequence

```
DIMENSION IC(6,100), IB(100)
WRITE(-,-) (IB(I),IC(1,I),I=1,100)
```

produces the ELIST

0-8	9-12	13	14-17	18-35
3	0	0	0	144
0	0	0	0	1
0	2	0	0	IB
0	0	0	0	12
0	2	0	0	IC
4	0	0	0	0

The increment may be zero. This could be produced by the sequence

```
DIMENSION A(100)
WRITE(-,-)(K,I=100) !only when the /OPT switch is used
```

The zero may not appear as an immediate constant in the argument block. The ELIST for the previous example would be

0-8	9-12	13	14-17	18-35
3	0	0	0	144
0	2	0	0	Pointer to a word containing a zero
0	type	0	0	K
4	0	0	0	0

## 4. FIN

The end of an I/O list is indicated by a call to the FIN routine in the object time system. This call must be made after each I/O initialization call, including calls with a null I/O list. The FIN routine may be entered by an explicit call or by an argument in the I/O list argument block. If both calls are used, the explicit call has no meaning. The FIN element has the following format:

## EXPLICIT CALL:

```
PUSHJ 17, FIN.
```

D.6.3.9 OPEN and CLOSE Statements, Calling Sequences - The form and calling sequences for the OPEN and CLOSE FORTRAN-10 statements are:

## OPEN STATEMENT CALL

```
MOVEI 16, ARGBLK
PUSHJ 17, OPEN.
```

## CLOSE STATEMENT CALL

```
MOVEI 16, ARGBLK
PUSHJ 17, CLOSE.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
Negative of the number of words in block not including this one.				0
0	2	I	X	u
0	7	I	X	c
0	7	I	X	d
G	type	I	X	H
G	type	I	X	H
G	type	I	X	H
.	.	.	.	.
.	.	.	.	.
.	.	.	.	.
G	type	I	X	H

The G field (bits 0 through 8) contains a 2-digit numeric that defines the argument name; the H field (bits 18 through 35) contains an address which points to the value of the argument.

The numeric codes that may appear in the G field and the argument that each identifies are:

G Field	Open Argument	G Field	Open Argument
01	DIALOG	12	MODE
02	ACCESS	13	FILE SIZE
03	DEVICE	14	RECORD SIZE
04	BUFFER COUNT	15	DISPOSE
05	BLOCK SIZE	16	VERSION
06	FILENAME	22	ASSOCIATE VARIABLE
07	PROTECTION	23	PARITY
10	DIRECTORY	24	DENSITY

D.6.3.10 Memory Allocation Routines - The memory management module is called to allocate or de-allocate core blocks. There are two entry points, ALCOR. and DECOR., that control memory allocation and de-allocation.

Use the ALCOR. entry to allocate the number of words specified in the argument block variable. Upon return, AC 0 will contain either the address of the allocated core block or a -1 value, which indicates that core is not available. The calling sequence for ALCOR. call is:

```
MOVEI 16, ARGBLK
PUSHJ 17, ALCOR.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
-1				0
→ Reserved	type	I	X	Address of Number of Words

Use the DECOR. entry to de-allocate a previously allocated block of memory; the argument variable must be loaded with the address of the core block to be returned. Upon return AC 0 is set to 0.

If the number of desired words is N, ALCOR. actually removes N+1 words from free storage. The pointer returned points to the second word (word 1 as opposed to word 0) removed from free storage. The 0 word contains the negative value of N in its left half. This word is used by FOROTS to maintain linked lists of allocated (using ALCOR.) and free storage.

The calling sequence for a DECOR. call is:

```
MOVEI 16, ARGBLK
PUSHJ 17, DECOR.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
-1				0
→ Reserved	type	I	X	Pointer to word containing address of block to be returned

D.6.3.11 Software Channel Allocation And De-allocation Routines - You may allocate software channels in MACRO programs via calls to the ALCHN. routine and de-allocate them by calls to the DECHN. routine. Values are returned in AC 0.

Use the ALCHN. entry to allocate a particular channel or the next available channel. The channel to be allocated is passed to ALCHN. in the argument block variable. Zero is passed in the argument block variable to allocate the next available channel. Allowed channels are 1 through 17 (octal). If the channel requested is not available, or all channels are in use, ALCHN. returns with a -1 in AC 0. In normal returns, AC 0 contains the assigned number.

The calling sequence of an ALCHN. routine is:

```
MOVEI 16, ARGBLK
PUSHJ 17, ALCHN.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
-1				0
→ Reserved	type	I	X	Pointer to a word containing the channel # or zero

Use the DECHN. entry to de-allocate a previously assigned channel. The channel to be released is passed to DECHN. in the argument block variable. If the channel to be de-allocated was not assigned by ALCHN. and thus cannot be de-assigned, AC 0 is set to -1 on return.

The calling sequence for a DECHN. routine is:

```
MOVEI 16, ARGBLK
PUSHJ 17, DECHN.
```

where ARGBLK is

0-8	9-12	13	14-17	18-35
-1				0
→ Reserved	type	I	X	Pointer to a word containing the channel # to be released

#### D.7 FUNCTIONS TO FACILITATE OVERLAYS

FOROTS provides a subroutine (FUNCT.) to serve as an interface with the LINK-10 overlay handler. This subroutine consists of a group of functions that allow the overlay handler to perform I/O, core management, and error message handling. These functions have only one entry point, FUNCT., and they are called by the sequence

```
MOVEI 16, ARGBLK
PUSHJ 17, FUNCT.
```

The general form of the ARGBLK is

0-17	18-35
Negative of the number of words in block type type type type type type . . type	0 function number error code status argument 1 argument 2 argument 3 . . argument n

where

type	= the FORTRAN argument type (see Appendix C)
function number	= the number of one of the required functions
error code	= the 3-letter mnemonic output by the object time system after ?, %, or [. (See Table D-1.)
status	= undefined on the call and set on the return with one of the values below.
	-1 Function not implemented
	0 Successful return
	1....n Specific error message

Table D-1  
Function Numbers and Function Codes

Function Number	Function Mnemonic	Function Description
0	ILL	Illegal function
1	GAD	Allocates core from a specific address
2	COR	Allocates core from available core
3	RAD	De-allocates core
4	GCH	Gets or assigns an I/O channel
5	RCH	Releases an I/O channel
6	GOT	Allocates core from FOROTS
7	ROT	De-allocates core from FOROTS
8	RNT	Returns the initial runtime from FOROTS
9	IFS	Returns initial runtime file spec. from FOROTS
10	CBC	Cuts back core if possible

FUNCTION 0 (ILL) - This function is illegal. The argument block is ignored, and the function always returns a status of -1.

FUNCTION 1 (GAD) - This function allocates core from a specific address. The arguments are:

```
arg 1      address at which to begin core allocation
arg 2      number of words of core to allocate
```

The return statuses are:

```
0 core allocated (arg 1 and 2 unchanged)
1 not enough core available in system (arg 1 and arg 2 unchanged)
2 cannot allocate core at specified address (arg 1 and arg 2
    unchanged)
3 illegal arguments (i.e., address + size is greater than 256K)
    (arg 1 and arg 2 unchanged)
```

FUNCTION 2 (COR) - This function allocates core from any address. The arguments are:

```
arg 1      undefined
arg 2      size of core to allocate
```

The returned statuses are:

```
0 core allocated (arg 2 unchanged, arg 1 beginning address of the
    allocated core)
1 not enough core available in system (arg 2 unchanged)
3 illegal argument (i.e., size is greater than 256K)
```

FUNCTION 3 (RAD) - This function de-allocates core at the specified address. The arguments are:

```
arg 1      address of core to be de-allocated
arg 2      number of words to be de-allocated
```

The returned statuses are:

```
0 core de-allocated
1 core cannot be de-allocated
3 illegal argument (i.e., both the address and the size are
    greater than 256K)
```

FOROTS

FUNCTION 4 (GCH) - This function assigns an I/O channel. The argument is:

arg 1 undefined

The returned statuses are:

0 I/O channel assigned (arg 1 channel number)  
1 no I/O channels available

FUNCTION 5 (RCH) - This function releases an I/O channel. The argument is:

arg 1 I/O channel number to be released

The returned statuses are:

0 channel released  
1 invalid channel number

FUNCTION 6 (GOT) - This function gets core from the object time system list. The arguments are:

arg 1 address at which to allocate core  
arg 2 number of words of core to allocate

The returned statuses are:

0 core allocated (arg 1 and arg 2 unchanged)  
1 not enough core available in system (arg 1 and arg 2 unchanged)  
2 cannot allocate core at specified address (arg 1 and arg 2 unchanged)  
3 illegal argument(s)

This function differs from function 1 in that if the object time system has two free core lists, then function 1 is used to allocate space for links, and this function is used to allocate space for I/O buffers. Function 1 uses the free core list for LINK-10, and function 6 uses the list for the object time system.

FUNCTION 7 (ROT) - This function returns core to the object time system. The arguments are:

arg 1 address of core to be de-allocated and returned  
arg 2 size of core to be de-allocated and returned

The returned statuses are:

0 core de-allocated  
1 core cannot be de-allocated  
3 illegal argument

FUNCTION 8 (RNT) - This function returns the initial runtime from the object time system. The argument is:

arg 1 undefined

The returned status is:

0 always (arg 1 - runtime from the object time system)

This function is used only if the user desires a log file.

## FOROTS

FUNCTION 9(IFS) - This function returns the initial runtime file specification from the object time system. The specification is obtained from accumulators 0, 7, and 11 after the initial RUN command. The arguments are:

```
arg 1      undefined
arg 2      undefined
arg 3      undefined
```

The returned status is:

```
0 always (arg 1 - device from accumulator 11, arg 2 - filename
from accumulator 0, and arg 3 - directory from accumulator 7)
```

This function tells the overlay handler which file to read after the initial RUN command.

FUNCTION 10 (CBC) - This function cuts back core if possible and is used to reduce the size of the user job. There are no arguments.

The returned status is:

```
0 always
```

### D.8 LOGICAL/PHYSICAL DEVICE ASSIGNMENTS

You make FORTRAN logical and physical device assignments at run time, or standard system assignments are made according to a FOROTS Device Table, i.e., DEVTB. Table D-2 shows the standard assignments contained by the Device Table.

## FOROTS

Table D-2  
FORTRAN Device Table

Device/Function	FORTRAN Logical Unit Number	Use
REREAD	-6	REREAD statement
CDR	-5	READ statement
TTY	-4	ACCEPT statement
LPT	-3	PRINT statement
PTP	-2	PUNCH statement
TTY	-1	TYPE statement
0	00	ILLEGAL
DSK	01	DISK
CDR	02	Card Reader
LPT	03	Line Printer
CTY	04	Console Teletype
TTY	05	User's Teletype
PTR	06	Paper Tape Reader
PTP	07	Paper Tape Punch
DIS	08	Display
DTA1	09	DECtape
DTA2	10	DECtape
DTA3	11	DECtape
DTA4	12	DECtape
DTA5	13	DECtape
DTA6	14	DECtape
DTA7	15	DECtape
MTA0	16	Magnetic Tape
MTA1	17	Magnetic Tape
MTA2	18	Magnetic Tape
FORTR	19	Assignable Device
DSK	20	DISK
DSK	21	DISK
DSK	22	DISK
DSK	23	DISK
DSK	24	DISK
DEV1	25	Assignable Devices
DEV2	26	
DEV3	27	
DEV4	28	
DEV5	29	
.	.	
.	.	
.	.	
DEV39	63	



## APPENDIX E

## FORDDT

FORDDT is an interactive program used to debug FORTRAN programs and control their execution. By using the symbols created by the FORTRAN compiler, FORDDT allows you to examine and modify the data and FORMAT statements in your program, set breakpoints at any executable statement or routine, trace your program statement-by-statement, and make use of many other debugging techniques described in this appendix.

Table E-1 lists all the commands available to the user of FORDDT.

Table E-1  
Table of Commands

Command	Purpose
Data Access Commands	
ACCEPT	Modifies data locations.
TYPE	Displays data locations.
Declarative Commands	
GROUP	Defines indirect lists for TYPE statements.
MODE	Specifies format of typeout.
OPEN	Accesses program unit symbol table.
PAUSE	Places pause requests.
REMOVE	Removes pause requests.
DIMENSION	Defines dimensions of arrays for FORDDT references. (Unnecessary if /DEBUG:DIMENSIONS was used. See Table B-2.)
DOUBLE	Defines dimensions of double-precision arrays for FORDDT references. (Unnecessary if /DEBUG: DIMENSIONS was used. See Table B-2.)

## FORDDT

Table E-1 (Cont.)  
Table of Commands

Command	Purpose
Control Commands	
START	Begins execution of FORTRAN program.
CONTINUE	Continues execution after a pause.
GOTO	Transfers control to some program statement within the open program unit.
NEXT	Traces execution of the program.
STOP	Terminates program and returns to monitor mode.
DDT	Enters DDT (if DDT is loaded).
Other Commands	
LOCATE	Lists program unit names in which a given symbol is defined.
STRACE	Displays routine backtrace of current program status.
WHAT	Displays current DIMENSION, GROUP, and PAUSE information.

E.1 INPUT FORMAT

FORDDT commands are made up of alphabetic FORTRAN-like identifiers and need consist of only those characters required to make the command unique. If you wish to specify parameters, a space or tab is required following the command name. FORDDT expects a parameter if a delimiter (i.e., space or tab) is found. Comments may be appended to command lines by preceding the comment with an !.

E.1.1 Variables and Arrays

FORDDT allows you to access and modify the data locations in your program by using standard FORTRAN-10 symbolic names. Variables are specified simply by name. Array elements are specified in the following format:

name (S1,...,Sn)

where

name = a FORTRAN variable or array name  
(S1,...,Sn) = the subscripts of the particular array.

You may reference an entire array simply by its unsubscripted name; you may specify a range of array elements by inputting the first and last array elements of the desired range, separated by a dash(-).

**Examples**

```

ALPHA
ALPHA(7)
ALPHA(PI)
ALPHA(2)-ALPHA(5)

```

**E.1.2 Numeric Conventions**

FORDDT accepts optionally signed numeric data in the standard FORTRAN-10 input formats:

1. INTEGER - A string of decimal digits.
2. FLOATING-POINT - A string of decimal digits optionally including a decimal point. Standard engineering and double-precision exponent formats are also accepted.
3. OCTAL - A string of octal digits optionally preceded by a double quote (").
4. COMPLEX - An ordered pair of integer or real constants separated by a comma and enclosed in parentheses.

**E.1.3 Statement Labels and Source Line Numbers**

FORTRAN statement labels are input and output by straightforward numeric reference, i.e., 1234. However, source line numbers must be input to FORDDT with a number sign (#) preceding them. This mandatory sign distinguishes statement labels from source line numbers.

**E.2 NEW USER TUTORIAL**

The new FORDDT user can rely on the commands described below as a basis for debugging FORTRAN programs. These commands are easy to understand and apply.

**E.2.1 Basic Commands**

The easiest method of loading and starting FORDDT is:

```
.DEBUG filename.ext (DEBUG)/F10
```

FORDDT will respond with

```
ENTERING FORDDT
>>
```

Just as an asterisk (\*) signifies FORTRAN-10's readiness, the two angle brackets signify that FORDDT is awaiting one of the following commands:

OPEN	Makes available to FORDDT the symbol names in a particular program unit of the FORTRAN program. When a program unit symbol table is opened, the previously
------	--

## FORDDT

open program unit is automatically closed. When FORDDT is entered, the MAIN program is automatically opened. The command format is:

OPEN name

This will open the particular program unit named and allow all variables within that subprogram to be accessible to FORDDT.

OPEN

with no arguments will reopen the symbol table of the main program unit.

START Starts your program at the main program entry point. The command format is:

START

STOP Terminates program execution, causes all files to be closed, and exits to the monitor. The command format is:

STOP

MODE Defines the display format for succeeding FORDDT TYPE commands. You need type only the first character of the mode to identify it to FORDDT. The modes are:

Mode	Meaning
A	ASCII (left-justified)
C	COMPLEX
D	DOUBLE-PRECISION
F	FLOATING-POINT
I	INTEGER
O	OCTAL
R	RASCII (right-justified)

Unless the MODE command is given, the default typeout mode is the floating-point format.

The command format is:

MODE list

where list contains one or more of the mode identifiers separated by commas. The current setting can be changed by issuing another MODE command. If more than one mode is given, the values are typed out in the order: F,D,C,I,O,A,R

MODE

with no arguments will reset FORDDT to the original setting of floating-point format.

TYPE Allows you to display the contents of one or more data locations. They are displayed on your terminal formatted according to the last MODE specification. The command format is:

TYPE list

## FORDDT

where list may contain one or more arrays, variables, array elements, or array element ranges separated by commas. For example:

```
TYPE I, ALPHA, BETA(2),J(3)-J(5)
```

Each item will be displayed in each of the currently active typeout modes as set by the last MODE command.

ACCEPT Allows you to change the contents of a FORTRAN variable, array, array element, or array element range. The command format is:

```
ACCEPT name/mode value
```

where

name = the name of the variable, array, array element, or array element range to be modified. If the field contains an unsubscripted array name or an element range, it causes all the elements to be set to the given value (see special case for ASCII in Section F.6).

mode = the format of the data value to be entered. If given, it must be preceded by a slash (/) and immediately follow the name. (Note that /mode does not apply to FORMAT modification.)

value = the new value to be assigned. It must correspond in format to the given mode.

### Data Modes

You need type only the first character of a data mode to identify it to FORDDT. If not specified, the default mode is REAL. The following input modes are available:

Mode	Meaning	Example
A	ASCII(left-justified)	/FOO/
C	COMPLEX	(1.25,-78.E+9)
D	DOUBLE-PRECISION	123.4567890
F	REAL	123.45678
I	INTEGER	1234567890
O	OCTAL	76543210
R	RASCII(right-justified)	\BAR\
S	SYMBOLIC	PSI(2,4)

An example of the ACCEPT command format is:

```
ACCEPT ALPHA 100.6
```

This changes the value of the variable ALPHA to 100.6 with the default input mode of REAL, since mode was not specified.

PAUSE Allows you to set a breakpoint at any label, line number, or subroutine entry in your program. You may set up to ten pauses at one time. When one of these pauses is encountered, execution of the FORTRAN program

## FORDDT

is suspended and control is transferred to FORDDT. Also, when a pause is encountered, the symbol table of that subprogram is automatically opened. The command format is:

```
PAUSE P
```

where P is a statement label number, line number, or routine entry point name; for example,

```
PAUSE 100
```

will cause a breakpoint at statement label 100 of the currently open program unit.

Note that subprogram parameter values will be displayed when a pause is encountered at a subprogram entry point.

**CONTINUE** Allows the program to resume execution after a FORDDT pause. After a CONTINUE is executed, the program either runs to completion, or it runs until another pause is encountered. If you include a value with this command, the program will run until the nth occurrence of the given pause or until a different pause is encountered. The command formats are:

```
CONTINUE  
or  
CONTINUE n
```

Example

```
CONTINUE 15
```

will continue execution until the fifteenth occurrence of the pause.

**REMOVE** Used to remove those pauses from the program previously set up by the PAUSE command. The command format is

```
REMOVE P
```

where P is the number of the statement label where the pause was set, i.e.,

```
REMOVE 100
```

will remove the pause at statement label 100.

Note that REMOVE with no arguments will remove all pauses; therefore, no abbreviation of the command is allowed in this instance. This precaution prevents the accidental removal of all pauses.

**WHAT** Displays on your terminal the name of the currently open program unit and any currently active pause settings. The command format is:

```
WHAT
```

### E.3 FORDDT AND THE FORTRAN-10/DEBUG SWITCH

Most facilities of FORDDT are available without the FORTRAN-10 /DEBUG features; however, if you do not use the /DEBUG switch when compiling a FORTRAN program, the trace features (NEXT command) will not be available, and several of the other commands will be restricted.

Using the /DEBUG switch tells FORTRAN-10 to compile extra information for FORDDT. (See Appendix B, Using the Compiler, for a complete description of each feature.) The additional features include:

1. /DEBUG:DIMENSIONS, which will generate dimension information to the REL file for all arrays dimensioned in the subprogram. The dimension information will automatically be available to FORDDT if you wish to reference an array in a TYPE or ACCEPT command. This feature eliminates the need to specify dimension information for FORDDT by using the DIMENSION command.
2. /DEBUG:LABELS, which will generate labels for every executable source line in the form "line-number L". If these labels are generated, they may be used as arguments with the FORDDT commands PAUSE and GOTO.

This switch will also generate labels at the last location allocated for a FORMAT statement so that FORDDT can detect the end of the statement. These labels have the form "format-label F". If they are generated, you will be able to display and modify FORMAT statements via the TYPE and ACCEPT commands.

Note that the :LABELS switch is automatically activated with the :TRACE switch, since labels are needed to accomplish the trace features.

3. /DEBUG:TRACE, which will generate a reference to FORDDT before each executable statement. This switch is required for the trace command NEXT to function.

Note that if more than one FORTRAN statement has been placed on a single input line, only the first statement will have a FORDDT reference and line-number label associated with it. This also applies to the :LABELS switch.

4. /DEBUG:INDEX, which will force the compiler to store in its respective data location as well as a register the index variable of all DO loops at the beginning of each loop iteration. You will then be able to examine DO loops by using FORDDT. If you modify a DO loop index using FORDDT, it will not affect the number of loop iterations because a separate loop count is used. (See Section D.1.5.)

Note that this switch has no direct affect on any of the commands in FORDDT.

### E.4 LOADING AND STARTING FORDDT

1. The simplest method of loading and starting FORDDT is with the following command string:

```
.DEBUG filename.ext(DEBUG)/F10
```

## FORDDT

FORDDT responds with

```
ENTERING FORDDT  
>>
```

The angle brackets indicate that FORDDT is ready to receive a command, just as an asterisk (\*) signifies FORTRAN-10's readiness.

The DEBUG command to the monitor will also load DDT (standard system debugging program). DDT can be used or ignored, but it does require an extra 2K (octal) of core.

2. You may wish to load your compiled program and FORDDT directly with the LINK-10 loader. (Loading with LINK-10 was accomplished implicitly in the previous command string.) The command sequence is as follows:

```
.R LINK  
*filename.ext /DEB/G (loads DDT)  
*filename.ext /DEB: FORDDT /G (loads FORDDT)  
FORTRA  
  
*filename.ext /DEB:(DDT, FORDDT )/G loads both DDT  
FORTRA and FORDDT
```

If the total FORTRAN program consists of many subroutines and insufficient core is available to complete loading with symbols, it is possible to load with symbols just those sections expected to give trouble. The remaining routines need not be loaded.

### E.5 SCOPE OF NAME AND LABEL REFERENCES

Each program unit has its own symbol table. When you initially enter FORDDT, you automatically open the symbol table of the main program. All references to names or labels via FORDDT must be made with respect to the currently open symbol table. If you have given the main program a name other than MAIN by using the PROGRAM statement (see Chapter 5, Section 5.2), FORDDT will ask for the defined program name. After you enter the program name, FORDDT will open the appropriate symbol table. At this point, symbol tables in programs other than the main program can be opened by using the OPEN command. (See Section F.5.)

References to statement labels, line numbers, FORMAT statements, variables, and arrays must have labels that are defined in the currently open symbol table. However, FORDDT will accept variable and array references outside the currently open symbol table, providing the name is unique with respect to all program units in the given load module.

### E.6 FORDDT COMMANDS

This section gives a detailed description of all commands in FORDDT. The commands are given in alphabetical order.

## FORDDT

ACCEPT Allows you to change the contents of a FORTRAN variable, array, array element, array element range, or FORMAT statement. The command format is:

ACCEPT name/mode value

where

name = the variable array, array element, array element range, or FORMAT statement to be modified.

mode = the format of the data value to be entered. The mode keyword must be preceded by a slash (/) and immediately follow the name. Intervening blanks are not allowed. (Note that /mode does not apply to FORMAT modification.)

value = the new value to be assigned. The format of the input value must correspond to the specified mode.

### DATA LOCATION MODIFICATION

#### Data Modes

The following data modes are accepted:

Mode	Meaning	Example
A	ASCII (left-justified)	/FOO/
C	COMPLEX	(1.25,-78.E+9)
D	DOUBLE-PRECISION	123.4567890
F	REAL	123.45678
I	INTEGER	1234567890
O	OCTAL	76543210
R	RASCII (right-justified)	\BAR\
S	SYMBOLIC	PSI(2,4)

If not specified, the default mode is REAL.

#### Two-Word Values

For the data modes ASCII, RASCII, OCTAL, and SYMBOLIC, FORDDT will accept a "/LONG" modifier on the mode switch. This modifier indicates that the variable and the value are to be interpreted as two words long.

#### Example

```
ACCEPT VAR/RASCII/LONG '1234567890'
```

will assume that VAR is two words long and store the given 10-character literal into it.

#### Initialization of Arrays

If the name field of an ACCEPT contains an unsubscripted array name or a range of array elements, all elements of the array or the specified range will be set to the given value.

**Example**

```
ACCEPT ARRAY/F 1.0
or
ACCEPT ARRAY(5)-ARRAY(10)/F 1.0
```

Note that this applies only to modes other than ASCII and RASCII.

**Long Literals**

When the value field of an ACCEPT contains an unsubscripted array name or range of array elements, and the specified data mode is ASCII or RASCII, the value field is expected to contain a long literal string. ACCEPT will store the string linearly into the array or array range. If the array is not filled, the remainder of the array or range will be set to zero. If the literal is too long the remaining characters will be ignored.

**Example**

```
ACCEPT ARRAY/RASCII 'ABCDEFGHIJKLMNPQRSTUVWXYZ'
```

**FORMAT STATEMENT MODIFICATION**

When the name field of an ACCEPT contains a label, FORDDT expects this label to be a FORMAT statement label and that the value field contains a new FORMAT specification.

**Example**

```
ACCEPT 10 (1H0,F10.2,3(I2))
```

The new specification cannot be longer than the space originally allocated to the FORMAT by the compiler. The remainder of the area is cleared if the new specification is shorter.

Note that FOROTS performs some encoding of FORMAT statements when it processes them for the first time. If any I/O statement referencing the given FORMAT has been executed, the FORTRAN program has to be restarted (re-initializing FOROTS).

**CONTINUE** Allows the program to resume execution after a FORDDT pause. After a CONTINUE is executed, the program either runs to completion or until another pause is encountered. The command format is:

```
CONTINUE n
```

where the n is optional and, if omitted, will be assumed to be one. If a value is provided, it may be a numeric constant or program variable, but it will be treated as an integer. When the value n is specified, the program will continue execution until the nth occurrence of this pause. For example,

```
CONTINUE 20
```

will continue execution after the 20th occurrence of the pause.

## FORDDT

DDT Transfers control of the program to DDT, the standard system debugging program (if loaded). Any files currently opened by FOROTS are unaffected and return to FORDDT is possible so that program execution may be resumed.

.F10 is the global symbol used to return control to FORDDT. The command format is:

.F10\$G

where \$ represents altnode or escape. Your program will be in the same condition as before unless you have modified your core image with DDT.

DIMENSION Sets the user-defined dimensions of an array for FORDDT access purposes. These dimensions need not agree with those declared to the compiler in the source code. FORDDT will allow you to redimension an array to have a larger scope than that of the source program. If this is done, a warning is given. The command format is:

DIMENSION S

where S is the name of the array specified.

For example:

DIMENSION ALPHA(7,5/6,10)

FORDDT will remember the dimensions of the array until it is redefined or removed.

The command

DIMENSION

will give a full list of all the user-defined dimensions for all arrays.

DIMENSION ALPHA

will display the current information for the array ALPHA only.

DIMENSION ALPHA/REMOVE

will remove any user defined array information for the array ALPHA.

### Arrays, Array Elements, and Ranges

Array elements are specified in the following format:

name [d1/d2,...](s1,...)

where

name = the name of the array

[...] = optional, and contains dimension information.  
This form is equivalent in effect to the  
DIMENSION statement.

FORDDT

(...) = the subscripts of the specific element desired.

The entire array is referenced simply by its unsubscripted name. A range of array elements is specified by inputting the first and last array elements of the desired range separated by a dash (-) (A(5)-A(10)).

DOUBLE Defines the dimensions of a double-precision array. The result of this command is the same as for the DIMENSION command except that the array so dimensioned is understood by FORDDT to be an array with word entries and, therefore, reserves twice the space. The command format is:

DOUBLE arrayname

GOTO Allows you to continue your program from a point other than the one at which it last paused. The GOTO allows you to continue at a statement label or code-generating source line number provided that the /DEBUG:LABELS switch has been used or the contents of a symbol previously ASSIGNED during the program execution.

Note that the program must be STARTed before this command can be used, and also note that a GOTO is not allowed after the ^C^C REENTER sequence. (See F.6.)

The command format is:

GOTO n

GROUP Sets up a string of text for input to a TYPE command. You can store TYPE statements as a list of variables identified by the numbers 1 through 8. This feature eliminates the need to retype the same list of variables each time you wish to examine the same group. Refer to the TYPE command for the proper format of the list.

The command format is:

GROUP n list

where

n = the group number 1-8

list = a string of TYPE statements to be called in future accessing of the current group number.

GROUP

with no arguments will cause FORDDT to type out the current contents of all the groups

GROUP n

will type out the contents of the particular group requested.

Note that one group may call another.

FORDDT

LOCATE      Lists the program unit names in which a given symbol is defined. This is useful when the variable you wish to locate is not in the currently open program unit and is defined in more than one program unit. The command format is:

LOCATE n

where n may be any FORTRAN variable, array, label, line number, or FORMAT statement number.

MODE      Defines the default formats of typeout from FORDDT. In initial default mode, variables will be typed in floating-point format. If you wish to change the typeout modes, the command format is:

MODE list

where list contains one or more of the modes in the following table. (Only the first character of each mode need be typed to identify it to FORDDT.)

Mode	Meaning
F	FLOATING-POINT
D	DOUBLE-PRECISION
C	COMPLEX
I	INTEGER
O	OCTAL
A	ASCII (left-justified)
R	RASCII (right-justified)

NEXT      Allows you to cause FORDDT to trace source lines, statement labels, and entry point names during execution of your program. This command will only provide trace facilities if the program was compiled with the FORTRAN-10 /DEBUG switch. If this switch was not used, the NEXT command will act as a CONTINUE command. The command format is:

NEXT n/sw

where

n      = a program variable or integer numeric value  
and

sw      = one of the following switches

/S= statement label  
/L= source line  
/E= entry point

The default starting value of n is 1, a single statement trace. The default switch is /L.

The command

NEXT 20/L

## FORDDT

will trace the execution of the next 20 source line numbers or until another pause is encountered.

Note that if no argument is specified, the last argument given will be used. For example,

```
NEXT /E
```

will change the tracing mode to trace only subprogram entries using the numeric argument previously supplied.

**OPEN** Allows you to open a particular program unit of the loaded program so that the variables will be accessible to FORDDT. Any previously opened program unit is closed automatically when a new one is opened. Only global symbols, symbols in the currently open unit, and unique locals are available at any one time. Note that starting FORDDT automatically opens the MAIN program. The command format is:

```
OPEN name
```

where name is the subprogram name. OPEN with no arguments will reopen the MAIN program.

If the PROGRAM statement was used in the FORTRAN program, the name supplied by you will be requested upon entering FORDDT.

**PAUSE** Allows you to place a pause request at a statement number, source line number, or subroutine entry point. Up to ten pauses may be set at any one time. When a pause is encountered, execution is suspended at that point and control is returned to FORDDT. Also, when a pause is encountered, the symbol table of that subprogram is automatically opened.

The command formats include:

```
PAUSE P
PAUSE P AFTER n
PAUSE P IF condition
PAUSE P TYPING /g
PAUSE P AFTER n TYPING /g
PAUSE P IF condition TYPING /g
```

where

P = the point where the pause is requested,  
n = an integer constant or variable or array element  
g = a group number

```
PAUSE 100
```

will set a pause at statement label 100, cause execution to be suspended, and cause FORDDT to be entered on reaching 100 in the program.

```
PAUSE #245 AFTER MAX(5)
```

will cause a pause to occur at source line number 245 after encountering this point the number of times specified by MAX(5). Note that AFTER may not be abbreviated.

FORDDT

PAUSE DELTA IF LIMIT(3,1).GT.2.5E-3

If the variable LIMIT(3,1) is greater than the value 2.5E-3, the pause request will be granted. The IF may not be abbreviated, but all the usual FORTRAN logical connectives are allowed.

PAUSE 505 TYPING /5

will request a pause to be made at the first occurrence of the label 505, and the variables in group 5 will be displayed. The TYPING specification may not be abbreviated.

PAUSE LINE#24 AFTER 16 TYPING 3

will place a request at source line number 24 after 16 (octal) times through; however, the contents of group 3 will be displayed every time.

When the TYPING option is used with the PAUSE command, control can be transferred to FORDDT at the next typeout by typing any character on the terminal.

Note that pause requests remain after a control C REENTER sequence, a START command, or a control C START sequence.

REMOVE Removes the previously requested pauses. The command format is:

REMOVE P

For example,

REMOVE L#123

will remove a pause at program source line number 123.

REMOVE ALPHA

will remove a pause at the subroutine entry to ALPHA.

REMOVE with no arguments will remove all your pause requests, and, in this case, no abbreviation of REMOVE is allowed. This prevents the unintentional removal of pauses.

START Starts your program at the normal FORTRAN main program entry point. The command format is:

START

STOP Terminates the program, requests FOROTS to close all open files, and causes an exit to the monitor. The usual command format is:

STOP

STOP/RETURN

will allow a return to monitor mode without releasing devices or closing files so that a CONTINUE can be issued.

FORDDT

STRACE      Displays a subprogram level backtrace of the current state of the program. The command format is:

STRACE

TYPE      Causes one or more FORTRAN defined variables, arrays, or array elements to be displayed on your terminal. The command format is:

TYPE list

where list may be one or more variable or array references and/or group numbers. These specifications must be separated by commas, and group numbers must be preceded by a slash (/). The command with no arguments will use the last argument list submitted to FORDDT.

An array element range can also be specified. For example:

TYPE PI(5)-PI(13)

will display the values from PI(5) to PI(13) inclusive. If an unsubscripted array name is specified, the entire array will be typed.

There are several methods of choosing the form of typeout in conjunction with the MODE command.

1. If you do not specify a format, the default is floating-point form.
2. You can specify a format via the MODE command described in this appendix.
3. You can change the format previously designated by the MODE command by including print modifiers in the TYPE or GROUP string. The print modifiers are:

/A,/C,/D,/F,/I,/O,/R

The first print modifier specified in a string of variables determines the mode for the entire string unless another mode is placed directly to the right of a particular variable. For example, in

TYPE /IK,L/O,M,N/A,/2

the typeout mode is integer until another mode is specified. Therefore,

K,M, and /2 = Integer  
L = OCTAL  
N = ASCII

WHAT      Displays the information saved by FORDDT. The command format is:

WHAT

E.7 ENVIRONMENT CONTROL

If a program enters an indefinite loop, you can recover by typing a ^C^C REENTER sequence. This action will cause FORDDT to simulate a pause at the point of reentry and allow you to control your run-away program.

Most commands can be used once the program has been reentered; however, GOTO, STRACE, TYPE, and ACCEPT cause transfer of control to routines external to FORDDT. No guarantee can be made to ensure that any of these commands following a ^C^C REENTER sequence will not destroy the user profile. The program must be returned to a stable state before any of these four commands can be issued. In order to restore program integrity, you should set a pause at the next label and then CONTINUE to it. If the /DEBUG:TRACE switch was used, a NEXT 1 command can be issued to restore program integrity.

E.8 FORTRAN-10/OPTIMIZE SWITCH

You should never attempt to use FORDDT with a program that has been compiled with the /OPTIMIZE switch. The global optimizer causes variables to be kept in ACs. For this reason, attempts to examine or modify variables in optimized programs will not work. Also, since the optimizer moves statements around in your program, attempts to trace program flow will lead to great confusion.

E.9 FORDDT MESSAGES

FORDDT responds with two levels of messages - fatal error and warning. Fatal error messages indicate that the processing of a given command has been terminated. Warning messages provide helpful information. The format of these messages is:

```
?FDTXXX text
      or
%FDTXXX text
```

where

```
?    = fatal
%   = warning
FDT = FORDDT mnemonic
XXX = 3-letter mnemonic for error message
text = explanation of error
```

Square brackets ([ ]) in this section signify variables and are not output on the terminal.

#### Fatal Errors

The fatal errors in the following list are each preceded by ?FD<sub>T</sub> on the user terminal and on listings. They are listed in alphabetical order.

BDF [symbol] IS UNDEFINED OR IS MULTIPLY DEFINED

BOI BAD OCTAL OUTPUT

An illegal character was detected in an octal input value.

FORDDT

CCN CANNOT CONTINUE  
Pause has been placed on some form of skip instruction causing FORDDT to loop; should never be encountered in FORTRAN-10 compiled programs.

CFO CORE FILE OVERFLOW  
The storage area for GROUP text has been exhausted.

CNU THE COMMAND [name] IS NOT UNIQUE  
More letters of the command are required to distinguish it from the other commands.

CSH CANNOT START HERE  
The specified entry point is not an acceptable FORTRAN-10 main program entry point.

DTO DIMENSION TABLE OVERFLOW  
FORDDT does not have the space to record any more array dimensions until some are removed.

FCX FORMAT CAPACITY EXCEEDED  
An attempt was made to specify a FORMAT statement requiring more space than was originally allocated by FORTRAN-10.

FNI FORMAL NOT INITIALIZED  
Reference to a FORMAL parameter of some subprogram that was never executed.

FNR [array name] IS A FORMAL AND MAY NOT BE RE-DEFINED  
FORMAL parameters may not be DIMENSIONed.

IAF ILLEGAL ARGUMENT FORMAT  
The parameters to the given command were not specified properly. Refer to the documentation for correct format.

IAT ILLEGAL ARGUMENT TYPE = [number]  
An unrecognized subprogram argument type was detected. Submit an SPR if this message occurs.

ICC COMPARE TWO CONSTANTS IS NOT ALLOWED  
Conditional test involves two constants.

IER E (number)  
Internal FORDDT error - please report via an SPR.

IGN INVALID GROUP NUMBER  
Group numbers must be integral and in the range 1 through 8.

INV INVALID VALUE  
A syntax error was detected in the numeric parameter.

FORDDT

ITM        ILLEGAL TYPE MODIFIER - S  
The mode S is only valid for ACCEPT statements.

LGU        [array name] LOWER SUBSCRIPT.GE.UPPER  
The lower bound of any given dimension must be less than or equal to the upper bound.

LNF        [label] IS NOT A FORMAT STATEMENT

MLD        [array name] MULTI-LEVEL ARRAY DEFINITION NOT ALLOWED  
The same array cannot be dimensioned more than once (via the [dimensions] construct) in a single command.

MSN        MORE SUBSCRIPTS NEEDED  
The array is defined to have more dimensions than were specified in the given reference.

NAL        NOT ALLOWED  
An attempt has been made to modify something other than data or a FORMAT.

NAR        NOT AFTER A RE-ENTER  
The given command is not allowed until program integrity has been restored via a CONTINUE or NEXT command.

NDT        DDT NOT LOADED

NFS        CANNOT FIND FORTRAN START ADDRESS FOR [program name]  
Main program symbols are not loaded.

NFV        [symbol] IS NOT A FORTRAN VARIABLE  
Names must be 6-character alphanumeric strings beginning with a letter.

NGF        CANNOT GOTO A FORMAT STATEMENT

NPH        CANNOT INSERT A PAUSE HERE  
An attempt has been made to place a pause at other than an executable statement or subprogram entry point.

NSP        [symbol] NO SUCH PAUSE  
An attempt has been made to REMOVE a pause that was never set up.

NUD        [symbol] NOT A USER DEFINED ARRAY  
An attempt has been made to remove dimension information for an array that was never defined.

PAR        PARENTHESES REQUIRED (...)  
Parentheses are required for the specification of FORMAT statements and complex constants.

FORDDT

PRO        TOO MANY PAUSE REQUESTS  
The PAUSE table has been exhausted. The maximum limit is 10.

SER        SUBSCRIPT ERROR  
The subscript specified is outside the range of its defined dimensions.

STL        [array name] SIZE TOO LARGE  
An attempt has been made to define an array larger than 256K.

TMS        TOO MANY SUBSCRIPTS  
The array is defined to have fewer dimensions than are specified in the given element reference.

URC        UNRECOGNIZED COMMAND

Warning Messages

Each warning message in this list is preceded by %FTN on your terminal and on listings. They are given here in alphabetical order.

ABX        [array name] COMPILED ARRAY BOUNDS EXCEEDED  
FORDDT has detected another symbol defined in the specified range of the array. Note that this will occur in certain EQUIVALENCE cases and can be ignored at that time.

CHI        CHARACTERS IGNORED: "[text]"  
The portion of the command string included in "text" was thought to be extraneous and was ignored.

NAR        [symbol] IS NOT AN ARRAY

NSL        NO SYMBOLS LOADED  
FORDDT cannot find the symbol table.

NST        NOT STARTED  
The specified command requires that a START be previously issued to ensure that the program is properly initialized.

POV        PROGRAM OVERLAYED  
The symbol table is different from the last time FORDDT had control.

SFA        SUPERSEDES F10 ARRAY  
The FORTRAN-10 generated dimension is being superseded for the given array.

SPO        VARIABLE IS SINGLE-PRECISION ONLY

XPA        ATTEMPT TO EXCEED PROGRAM AREA WITH [symbol name]  
An attempt has been made to access memory outside the currently defined program space.

APPENDIX F  
COMPILER MESSAGES

FORTRAN-10 responds with two levels of messages - fatal error and warning. If a warning message is received, the compilation will continue, but a fatal error will stop the program from being compiled. The format of messages is:

?FTNXXX LINE:n text  
or  
%FTNXXX LINE:n text

where

? = fatal  
% = warning  
FTN = FORTRAN mnemonic  
XXX = 3-letter mnemonic for the error message  
LINE:n = line number where error occurred  
text = explanation of error

Square brackets ([ ]) in this appendix signify variables and are not output on the terminal.

Fatal Errors

Each fatal error in the following list is preceded by ?FTN on the user terminal and on listings. They are presented here in alphabetical order.

ABD [symbolname] HAS ALREADY BEEN DEFINED [definition]

The usage given conflicts with current information about the symbol. For example, a symbol defined in an EQUIVALENCE statement cannot be referenced as a subprogram name.

ATL ARRAY [name] TOO LARGE

The total amount of core necessary to accommodate this array is greater than 512P.

AWN ARRAY REFERENCE [name] HAS WRONG NUMBER OF SUBSCRIPTS

The array was defined to have more or fewer dimensions than the given reference.

BOV STATEMENT TOO LARGE TO CLASSIFY

To determine statement type, some portion of the statement must be examined by the compiler before actual semantic and syntactic analysis begins. During this classification the entire portion of the required statement must fit into the

## COMPILER MESSAGES

internal statement buffer (large enough for a normal 20-line statement). This error message is issued when the portion of a given statement required for classification is too large to fit in the buffer. Once FORTRAN-10 has classified a statement, there is no explicit restriction on its length.

CER	COMPILER ERROR IN ROUTINE [name]
	Submit an SPR for any occurrence of this message.
CFF	CANNOT FIND FILE
	The file referenced in an INCLUDE statement was not found.
CPE	CHECKSUM OR PARITY ERROR IN [source/listing/object] FILE [name]
CQL	NO CLOSING QUOTE IN LITERAL
CSF	ILLEGAL STATEMENT FUNCTION REFERENCE IN CALL STATEMENT
DDA	[symbolname] IS DUPLICATE DUMMY ARGUMENT
DFC	VARIABLE DIMENSION [name] MUST BE SCALAR, DEFINED AS FORMAL OR IN COMMON
DFD	DOUBLE [type] NAME ILLEGAL
	Duplicate fields were encountered in an INCLUDE file specification.
DIA	DO INDEX VARIABLE [name] IS ALREADY ACTIVE
	In any nest of DO loops, a given index variable may not be defined for more than one loop.
DID	CANNOT INITIALIZE A DUMMY PARAMETER IN DATA
DLN	OPTIONAL DATA VALUE LIST NOT SUPPORTED
	The extended FORTRAN statement form that allows data values to be defined in type specification statements is not supported by FORTRAN-10.
DNL	IMPLIED DO SPECIFICATION WITHOUT ASSOCIATED LIST OF VARIABLES
DPR	DUMMY PARAMETER [name] REFERENCED BEFORE DEFINITION
DSF	ARGUMENT [name] IS SAME AS FUNCTION NAME
DTI	THE DIMENSIONS OF [arrayname] MUST BE OF THE TYPE INTEGER
DVE	CANNOT USE DUMMY VARIABLE IN EQUIVALENCE
DWL	[source/listing/object] DEVICE [[device]] WRITE LOCKED
ECT	ATTEMPT TO ENTER [symbolname] INTO COMMON TWICE
EDN	EXPRESSION TOO DEEPLY NESTED TO COMPILE
EID	ENTRY STATEMENT ILLEGAL INSIDE A DO LOOP
EIM	ENTRY STATEMENT ILLEGAL IN MAIN PROGRAM

## COMPILER MESSAGES

ENF      LABEL [number] MUST REFER TO AN EXECUTABLE STATEMENT, NOT A FORMAT

ETF      ENTER FAILURE [filename]

EXB      EQUIVALENCE EXTENDS COMMON BLOCK [name] BACKWARD

FEE      FOUND [symbol] WHEN EXPECTING EITHER [symbol] OR A [symbol]  
General syntax error message.

FNE      LABEL [number] MUST REFER TO A FORMAT, NOT AN EXECUTABLE STATEMENT

FWE      FOUND [symbol] WHEN EXPECTING [symbol]

HDE      HARDWARE DEVICE ERROR ON [source/listing/object] DEVICE [[device]]

IAC      ILLEGAL ASCII CHARACTER [character] IN SOURCE

IAL      INCORRECT ARGUMENT TYPE FOR LIBRARY FUNCTION [name]

IBK      ILLEGAL STATEMENT IN BLOCKDATA SUBPROGRAM

ICL      ILLEGAL CHARACTER [character] IN LABEL FIELD

IDN      DO LOOP AT LINE: [number] IS ILLEGALLY NESTED  
  
You are attempting to terminate a DO loop before terminating one or more loops defined after the given one.

IDS      IMPLICIT DO INDICES MAY NOT BE SUBSCRIPTED

ID'T      ILLEGAL OR MISSPELLED DATA TYPE

IDV      IMPLIED DO INDEX IS NOT A VARIABLE

IED      INCONSISTENT EQUIVALENCE DECLARATION  
  
The given EQUIVALENCE declaration would cause some symbolic name to refer to more than one physical location.

IFD      INCLUDED FILES MUST RESIDE ON DISK

IID      NON-INTEGER IMPLIED DO INDEX

IIP      ILLEGAL IMPLICIT SPECIFICATION PARAMETER

IIS      INCORRECT INCLUDE SWITCH

ILF      ILLEGAL STATEMENT AFTER LOGICAL IF  
  
Refer to Section 9.3.2 for restrictions on logical IF object statements.

INN      INCLUDE STATEMENTS MAY NOT BE NESTED

IOD      ILLEGAL STATEMENT USED AS OBJECT OF DO

ISD      ILLEGAL SUBSCRIPT EXPRESSION IN DATA STATEMENT  
  
Subscript expressions may be formed only with implicit DO indices and constants combined with +, -, \*, or /.

COMPILER MESSAGES

ISN [symbolname] IS NOT [symboltype]  
The symbol cannot be used in the attempted manner.

IUT PROGRAM UNITS MAY NOT BE TERMINATED WITHIN INCLUDED FILES

IVP INVALID PPN

IXM ILLEGAL MIXED MODE ARITHMETIC  
Complex and double-precision cannot appear in the same expression.

IZM ILLEGAL [datatype] SIZE MODIFIER [number]  
Refer to Section 6.3.

LAD LABEL [number] ALREADY DEFINED AT LINE: [number]

LED ILLEGAL LIST DIRECTED [statement type]

LFA LABEL ARGUMENTS ILLEGAL IN FUNCTION OR ARRAY REFERENCE

LGB LOWER BOUND GREATER THAN UPPER BOUND FOR ARRAY [name]

LLS LABEL TOO LARGE OR TOO SMALL  
Labels cannot be 0 or greater than 5 digits.

LNI LIST DIRECTED I/O WITH NO I/O LIST

LTL TOO MANY ITEMS IN LIST - REDUCE NUMBER OF ITEMS  
In rare instances, a combination of long lists in a single statement can exhaust the syntax stack.

MCE MORE THAN 1 COMMON VARIABLE IN EQUIVALENCE GROUP

MSP STATEMENT NAME MISSPELLED

MWL ATTEMPT TO DEFINE MULTIPLE RETURN WITHOUT FORMAL LABEL ARGUMENTS

NCF NOT ENOUGH CORE FOR FILE SPECS. TOTAL K NEEDED= [number]

NEX NO EXPONENT AFTER D OR E CONSTANT

NFS NO FILENAME SPECIFIED  
The INCLUDE statement requires a filename.

NIO NAMELIST DIRECTED I/O WITH I/O LIST

NGS CANNOT GET SEGMENT [name] - ERROR CODE: [number]  
Refer to Appendix E of the Monitor Calls Manual for full description of codes.

NIR REPEAT COUNT MUST BE AN UNSIGNED INTEGER

NIU NON-INTEGER UNIT IN I/O STATEMENT

NLF WRONG NUMBER OF ARGUMENTS FOR LIBRARY FUNCTION [name]

## COMPILER MESSAGES

NNF	NO STATEMENT NUMBER ON FORMAT
NRC	STATEMENT NOT RECOGNIZED
NUO	.NOT. IS A UNARY OPERATOR
NWD	INCORRECT USE OF * OR ? IN [filename]
OPW	OPEN PARAMETER [name] IS OF WRONG TYPE
PD6	FORTRAN WILL NOT RUN ON A PDP-6
PIC	THE DO PARAMETERS OF [index name] MUST BE INTEGER CONSTANTS
PRF	PROTECTION FAILURE [filename]
PTL	PROGRAM TOO LARGE  The program takes up more than 512P
QEF	QUOTA EXCEEDED OR DISK FULL [filename]
QEX	BLOCK TOO LARGE OR QUOTA EXCEEDED FOR [source/listing/object] FILE [name]
RDE	RIB OR DIRECTORY ERROR [filename]
RFC	[function name] IS A RECURSIVE FUNCTION CALL
RIC	COMPLEX CONSTANT CANNOT BE USED TO REPRESENT THE REAL OR IMAGINARY PART OF A COMPLEX CONSTANT
SAD	ARRAY [name] - SIGNED DIMENSIONS MAY APPEAR ONLY AS CONSTANT RANGE LIMITS
SNL	[statement name] STATEMENTS MAY NOT BE LABELED
SOR	SUBSCRIPT OUT OF RANGE
TFL	TOO MANY FORMAT LABELS SPECIFIED
TOF	MORE THAN 2 OUTPUT FILES ARE NOT ALLOWED  Only a listing and a relocatable binary file may be specified as output files.
UCE	USER CORE EXCEEDED
UMP	UNMATCHED PARENTHESES
USI	[symbol type] [symbol name] USED INCORRECTLY  The given symbol cannot be used in this way.
VNA	SUBSCRIPTED VARIABLE IN EQUIVALENCE BUT NOT AN ARRAY
VSE	EQUIVALENCE SUBSCRIPTS MUST BE INTEGER CONSTANTS
VSO	VARIABLE DIMENSION ALLOWED IN SUBPROGRAMS ONLY

## COMPILER MESSAGES

### Warning Messages

Each warning message in the following list is preceded by %FTN on the user terminal and on listings. They are presented here in alphabetical order.

- AGA        OPT - OBJECT VARIABLE, OF ASSIGNED GOTO WITHOUT OPTIONAL LIST, WAS NEVER ASSIGNED
- CAI        COMPLEX EXPRESSION USED IN ARITHMETIC IF
- CTR        COMPLEX TERMS USED IN A RELATIONAL OTHER THAN EQ OR NE  
The result of the other relational operators with complex operands is undefined.
- CUO        CONSTANT UNDERFLOW OR OVERFLOW  
This message is issued when overflow or underflow is detected as the result of building constants or evaluating constant expressions at compile time.
- DIM        POSSIBLE DO INDEX MODIFIED INSIDE LOOP  
A program that does this may be incorrectly compiled by the optimizer, since it assumes that indices are never modified. Note that the number of iterations is calculated at the beginning of the loop and is never affected by modification of the index within the loop.
- DIS        OPT - PROGRAM IS DISCONNECTED - OPTIMIZATION DISCONTINUED  
Submit an SPR if this message occurs.
- DXB        DATA STATEMENT EXCEEDS BOUNDS OF ARRAY [name]
- FMR        MULTIPLE RETURNS DEFINED IN A FUNCTION
- FNA        A FUNCTION WITHOUT AN ARGUMENT LIST
- ICC        ILLEGAL CHARACTER, CONTINUATION FIELD OF INITIAL LINE  
Continuation lines cannot follow comment lines.
- ICD        INACCESSIBLE CODE. STATEMENT DELETED  
The optimizer will delete statements that cannot be reached during execution.
- ICS        ILLEGAL CHARACTER IN LINE SEQ#
- IDN        OPT - ILLEGAL DO NESTING - OPTIMIZATION DISCONTINUED  
A GO TO within a DO loop goes to the ending statement of an inner, nested DO loop. The line number printed out with the warning message is that of the OUTER DO.

```
DO
.
.
.
GO TO
.
.
```

COMPILER MESSAGES

DO  
.  
.  
.  
CONTINUE  
.  
.  
CONTINUE

IFL OPT - INFINITE LOOP. OPTIMIZATION DISCONTINUED

LID IDENTIFIER [name] MORE THAN SIX CHARACTERS  
The remaining characters are ignored.

MVC NUMBER OF VARIABLES DOES NOT EQUAL THE NUMBERS OF CONSTANTS IN DATA STATEMENT

NED NO END STATEMENT IN PROGRAM

NOD GLOBAL OPTIMIZATION NOT SUPPORTED WITH /DEBUG - /OPT IGNORED

NOF NO OUTPUT FILES GIVEN

PPS PROGRAM STATEMENT PARAMETERS IGNORED  
For compatibility purposes.

RDI ATTEMPT TO REDECLARE IMPLICIT TYPE

SOD [name] STATEMENT OUT OF ORDER

VAI [name] ALREADY INITIALIZED

VND FUNCTION RETURN VALUE IS NEVER DEFINED

VNI OPT - VARIABLE [name] IS NOT INITIALIZED  
The optimizer analysis determined that the given variable was never initialized prior to its use in a calculation.

WOP OPT - WARNING GIVEN IN PHASE 1. OPTIMIZED CODE MAY NOT BE CORRECT  
One or more of the messages issued prior to this message resulted from situations that violate assumptions made by the optimizer and thus may cause it to generate code that does not execute as desired.

XCR EXTRANEOUS CARRIAGE RETURN  
Carriage return was not immediately preceded or followed by a line termination character.

ZMT SIZE MODIFIER [number] TREATED AS [data type]  
Message is issued when one of the data type size modifiers is used that is accepted only for compatibility.

## COMPILER MESSAGES

### Internal Compiler errors

An internal compiler error is either an attempt by the compiler or the monitor to document an error inside the FORTRAN compiler. An occurrence of an internal compiler error signifies that something is wrong with the FORTRAN-10 compiler.

Monitor-detected internal errors are of the form

```
[message] AT LOCATION [address] IN PHASE [segment]  
WHILE PROCESSING STATEMENT [line-number]
```

where [message] can be one of

```
ILLEGAL MEMORY REFERENCE  
STACK EXHAUSTED  
MEMORY PROTECTION VIOLATION
```

Compiler-detected errors are of the form

```
? INTERNAL COMPILER ERROR PROCESSING STATEMENT NUMBER [line-number]  
? CALL TO [routine-name] FROM [address]
```

Submit an SPR if you received an internal compiler error.

APPENDIX G  
FORTRAN-10 REALTIME SOFTWARE

This appendix explains how to use the FORTRAN-10 realtime software.

#### G.1 INTRODUCTION

The FORRTF library subroutines (LOCK, RTINIT, CONECT, RTSTART, BLKRW, RTREAD, RTWRIT, STATO, STATI, RTSLP, RTWAKE, DISMIS, DISCON, UNLOCK, and temporary subroutine GETCOR (refer to Section G.3)) are designed to allow the timesharing FORTRAN user to do realtime programming. With these subroutines, the timesharing job can dynamically connect realtime devices to the priority interrupt (PI) system, respond to these devices at interrupt level, remove the devices from the PI system, and change their PI level. Use of these routines requires that you have realtime privileges and are able to lock your job in core. The privilege bits required are:

JPORRT (BIT 13) - realtime privileges  
JPOLCK (BIT 14) - locking privileges

The number of realtime devices that can be handled at one time is an assembly-time constant, RTDEVN, in the FORRTF source. The DIGITAL-distributed software has RTDEVN equal to 2 but it can be changed (up to 6) by editing the statement "RTDEVN==2" in FORRTF.MAC and reassembling.

The error messages output by FORRTF can be in either full message format or coded format. (Refer to Table G-1.) Use of the code and format saves 165 words of run-time core. If core is limited, reassembly of FORRTF.MAC with the assembly-time constant SHORT changed from the DIGITAL-distributed 0 (full format) to -1 (coded format) accomplishes the core saving.

On multiprocessor systems, the realtime traps apply only to the processor specified by the job's CPU specification. If the specification indicates more than one processor, the specification is changed to indicate CPU0. Note that the priority interrupt channel is only for the indicated CPU.

## G.2 USING FORRTF

Users of FORTRAN-10 realtime software must consider the following:

1. Use of core
2. Device control in block or single mode
3. Priority interrupt levels
4. Masks

### G.2.1 Core

The job being executed must be locked in core with the LOCK subroutine. Any data being read into core can only be read into the low segment and above the protected job data area (the first 140 locations). The subroutine BLKRW tests the validity of the locations specified to receive data in block-reading to ensure that no overwritings occur.

However, when in block mode, the block pointer must be reset before dismissing the end-of-block interrupt; otherwise, all memory could be overwritten.

### G.2.2 Modes

Realtime jobs can control their devices in one of two ways: block mode or single mode. In block mode, an entire block of data is read or written before the user interrupt routine is run, whereas in single mode, the user interrupt program is run every time the device interrupts. There are two types of block mode; fast block mode and normal block mode. The response time to read a word of data is 6.5 microseconds for fast mode and 14.6 microseconds for normal mode. (These are the times necessary to completely service the interrupts on a KI10 processor). In single mode, the response time measured from the receipt of a realtime device interrupt until the start of the user control program is 100 microseconds on a KI10 processor. A device in fast block mode requires that a PI channel be dedicated entirely to itself.

### G.2.3 Priority Interrupt Levels

Priority interrupt levels 1 through 6 are legal depending on the system configuration. The lower the number of the level, the higher the priority of that level. Programs that execute for a long time should not be put on high-priority interrupt levels, since they could cause other realtime programs on lower levels to lose data. Specification of the PI level as zero for a particular device causes the device to be removed from the PI system.

**G.2.4 Masks**

For a description of the bits included in the startmsk and intmsk parameters of RTSTART and the status word in STAT0 and STAT1, see Chapters 3 through 8 of the DECsystem-10 System Reference Manual and Appendix C, IN-OUT DEVICE BIT ASSIGNMENTS of that manual.

**G.3 SUBROUTINES**

Each of the 15 subroutines associated with FORTRAN-10 realtime software is described briefly in this section. These subroutines have been programmed to be compatible with programs written according to the RTTRP: REAL TIME TRAPPING UUO specifications, edition 4 of 12-Feb-73.

**G.3.1 LOCK**

LOCK locks the job in core and allocates and initializes the internal controlling tables for all realtime devices. LOCK must be called before any other of the realtime routines, except GETCOR (refer to Section G.3.15), and must be called exactly once.

```
CALL LOCK
```

**G.3.2 RTINIT**

RTINIT initializes the internal tables controlling a realtime device. RTINIT must be called for each individual device being used.

```
CALL RTINIT (unit, dev, pi, trpadr, intmsk)
```

unit	- realtime device unit number (any number from 1 to RTDEVN) This number is not connected in any way with the FORTRAN logical unit number.
dev	- device code for the realtime device (see Appendix A, DEVICE MNEMONICS in the <u>DECsystem-10 System Reference Manual</u> DEC-10-XSRMA-A-D).
pi	- priority interrupt level on which the realtime device is to be run. Each individual device in fast block mode must have a level dedicated to itself. If the level is equal to zero, the device will be removed from the priority interrupt system altogether. If it is necessary to connect one device to several levels simultaneously, a negative value for pi tells the system not to remove any other occurrences of the device from any other (or the same) PI level. (Note that this counts as another realtime device.)

trpadr - address of a FORTRAN entry to which realtime interrupts are to trap. This can be a FUNCTION or SUBROUTINE subprogram. Any variables that must be shared between the user level code and the interrupt level routine must be passed by means of COMMON. Passing them as parameters causes disastrous results.

intmsk - mask of all interrupting flags for the realtime device. This is actually set up by RTSTART and should be zero whenever the realtime device is inactive, i.e., in a call to RTINIT, except in the case of fast block mode. In fast block mode, intmsk must be set to -1.

#### G.3.3 CONECT

CONECT tells the system to connect a realtime device to the proper PI level and sets up several elements of the device controlling tables. Every device must be CONECTed.

CALL CONECT (unit, mode)

unit - realtime device unit number (see RTINIT)

mode - -2, write a block of data, fast mode; then interrupt.  
       -1, write a block of data, normal mode; then interrupt.  
       0, interrupt every word  
       +1, read a block of data, normal mode; then interrupt.  
       +2, read a block of data, fast mode; then interrupt.

#### G.3.4 RTSTART

RTSTART can be used to start a realtime device as well as to stop it and zero its interrupt mask. A device must be started to be used and should be stopped before it is disconnected.

CALL RTSTART (unit, startmsk, intmsk)

unit - realtime device unit number (see RTINIT)

startmsk - flags necessary to start the device (see the System Reference Manual, Appendix C). If the device is being stopped, this parameter should be zero.

intmsk - mask of all interrupting bits for the particular device (see the System Reference Manual Appendix C). If the device is in fast block mode and being started, intmsk should equal -1; if, however, the device in any mode is being stopped, the parameter must be 0.

## FORTRAN-10 REALTIME SOFTWARE

### G.3.5 BLKRW

BLKRW is used with either of the block modes. It sets up the size and starting address of the data block being handled. A new count and starting address must be set up each time the current one runs out.

```
CALL BLKRW (unit, count, blkadr)
```

unit - realtime device unit number

count - number of words to be read or written

blkadr - array into which the data is to be written or from which it is to be read.

### G.3.6 RTREAD

RTREAD, used with a device in single mode, reads from the device a single word of data.

```
CALL RTREAD (unit, datadr)
```

unit - realtime device unit number (see RTINIT)

datadr - address of where to store the data read

### G.3.7 RTWRIT

RTWRIT sends a single word of data to a realtime device in single mode.

```
CALL RTWRIT (unit, datadr)
```

unit - realtime device unit number (see RTINIT)

datadr - location of the data word to be sent to the device

### G.3.8 STATO

STATO sends the specified status word to the status register of a realtime device. (See Appendix C, In-Out Device Bit Assignments, in the DECsystem-10 System Reference Manual, DEC-10-XSRMA-A-D.)

```
CALL STATO (unit, statadr)
```

unit - realtime device unit number (see RTINIT)

statadr - location of the word of status bits to be sent to the realtime device

### G.3.9 STATI

STATI reads the current device status bits into the location specified for inspection by the FORTRAN program. (See Appendix C, "In-Out Device Bit Assignments", in the DECsystem-10 System Reference Manual, DEC-10-XSRMA-A-D.)

## FORTRAN-10 REALTIME SOFTWARE

CALL STATI (unit, adr)

    unit     - realtime device unit number (see RTINIT)

    adr     - location into which the device status bits are to be read.

### G.3.10 RTSLP

RTSLP is called from the timesharing level and causes the FORTRAN job to sleep until RTWAKE is called from interrupt level. The program goes to sleep for the specified number of seconds (up to 60). When it wakes up, it checks to see if RTWAKE has been called from interrupt level. If RTWAKE has been called, RTSLP returns to the calling program, otherwise the job goes back to sleep again.

CALL RTSLP (time)

    time     - length of sleep time in seconds

### G.3.11 RTWAKE

RTWAKE is called at interrupt level to wake up the FORTRAN program.

CALL RTWAKE

### G.3.12 DISMIS

DISMIS dismisses the interrupt currently being processed. The user interrupt must be sure to dismiss the interrupt that causes its execution to begin.

CALL DISMIS

### G.3.13 DISCON

DISCON disconnects a realtime device from its PI level. All devices should be disconnected through calls to DISCON before the job is terminated.

CALL DISCON (unit)

    unit     - realtime device unit number (see RTINIT)

### G.3.14 UNLOCK

UNLOCK unlocks the job from core. When execution of a job is complete, the job is automatically unlocked before the return to the monitor. The UNLOCK subroutine provides a method to unlock a job before execution is complete. Note that all realtime device handling must be finished before the job is unlocked.

CALL UNLOCK

G.3.15 GETCOR, A Temporary Subroutine

GETCOR is a routine that allocates a specified amount of core for FOROTS use. The design of FOROTS does not allow FORTRAN jobs to be locked in core due to its run-time core needs. Thus, you must allocate an amount of core sufficient to satisfy FOROTS for running the particular program being executed through a GETCOR call. The GETCOR call must precede the LOCK call (see G.3.2). Unfortunately, the only way to determine the core required for each program is by running the job with ever-increasing arguments to GETCOR. If the argument is too small, the following error message appears:

```
?FRSSYS USER PROGRAM REQUESTED MORE CORE THAN IS AVAILABLE  
CALL GETCOR (wds)
```

wds - number of words of storage to be allocated

Table G-1  
Error Messages  
Code Format and Full Message Format

Code Format	Full Message Format	Subroutine in which message occurs
1	?ILLEGAL UNIT NUMBER. TO HANDLE MORE DEVICES, REASSEMBLE FORRTF WITH A LARGER	"RTDEVN"
A	?ERROR COMES FROM THE SUBROUTINE "subroutine name"	
2	?RTINIT MUST BE CALLED BEFORE CONECT	CONECT
3	?CONECT MUST BE CALLED BEFORE RTSTRTR OR BLKRW	RTSTRTR, BLKRW
4	?REAL TIME BLOCK OUT OF BOUNDS ?END OF BLOCK TOO HIGH [i.e., overwrites some program or in high segment] B ?END OF BLOCK TOO LOW, i.e., start address less than 140	BLKRW
5	?JOB CANNOT BE LOCKED IN CORE A ?JOB NOT PRIVILEGED B ?NOT ENOUGH CORE AVAILABLE FOR LOCKING	LOCK
6	?APR ERROR AT INTERRUPT LEVEL A ?PDL OVERFLOW B ?ILLEGAL MEMORY REFERENCE	

## FORTRAN-10 REALTIME SOFTWARE

Table G-1 (Cont.)  
Error Messages  
Code Format and Full Message Format

Code Format	Full Message Format	Subroutine in which message occurs
7	?RTTRP ERROR realtime trap error of the following sort	
A	?ILLEGAL PI NUMBER PI channel not available	
B	?TRAP ADDRESS OUT OF BOUNDS	
C	?SYSTEM LIMIT FOR REALTIME DEVICES EXCEEDED	
D	?JOB NOT LOCKED IN CORE OR NOT PRIVILEGED	
E	?DEVICE ALREADY IN USE BY ANOTHER JOB	
0	?OCCURRED IN THE DISCON ROUTINE	DISCON
1	?OCCURRED IN THE CONECT ROUTINE	CONECT
8	A      ?NOT ENOUGH CORE AVAILABLE FOR THE CONTROL BLOCKS	LOCK
	B      ?NOT ENOUGH CORE AVAILABLE FOR THE GETCOR ROUTINE	GETCOR
	?FRSSYS USER PROGRAM REQUESTED MORE CORE THAN IS AVAILABLE	GETCOR

## APPENDIX H

### FOROTS ERROR MESSAGES

Errors detected at run-time by FOROTS fall into the following categories:

1. system errors (SYS) - errors internal to FOROTS
2. open errors (OPN) - I/O errors that occur during file OPEN and CLOSE
3. arithmetic fault errors (APR) - errors in numeric calculations
4. library errors (LIB) - errors generated by FORLIB library routines
5. data errors (DAT) - errors in data conversion on I/O
6. device errors (DEV) - I/O hardware errors

APR and LIB errors are usually reported as warnings and the program continues. The number of APR and LIB errors listed on the user's terminal can be changed by the FORTRAN Library Subroutine ERSET. See Table 15-3 for details. The I/O errors (SYS, OPN, DAT, and DEV) either cause messages to be printed on the terminal or can be trapped by an error exit argument (ERR=statement label) on OPEN, READ, WRITE, and CLOSE.

Table H-1 gives the text of the messages which can be printed for SYS, OPN, DAT, and DEV errors. The included footnotes give additional information. Table H-2 gives the text of the messages which can be printed for APR and LIB errors.

The FORTRAN Library Subroutine ERRSNS allows you to find out which I/O error occurred. When called, ERRSNS returns one or two integer values that describe the status of the last I/O operation performed by FOROTS. (The second integer value is optional.)

```
CALL ERRSNS (I,J)
```

calls this subroutine. J is the second, optional integer value.

## FOROTS ERROR MESSAGES

Table H-1  
FOROTS I/O Error Messages and ERRSNS Returned Values

First Value	Second Value	Explanation
0	0	No error detected
	101	Satisfactory completion (no error detected)
1	243	Normal end of job (1)
	246	Invalid error call
23	312	Unidentified entry in FORERR (3)
24	308	Unidentified entry in FORERR (3)
25	302	Backspace error
	312	BACKSPACE illegal for device (9)
24	308	End-of-file during READ
25	302	Attempt to READ beyond valid input (8)
	302	Invalid record number
	302	LSCW illegal in binary record or reading ASCII; or attempt to read unwritten ASCII
	302	RANDOM ACCESS record or unwritten or destroyed record number
26	311	RANDOM ACCESS record or unwritten or destroyed record number
28	252	Direct access not specified
	252	Cannot RANDOM ACCESS a SEQUENTIAL file
	252	CLOSE error
	252	DTA directory is full (2) or protection error
	254	Rename file already exists (2)
	262	No room or quota exceeded (2)
	268	Cannot delete or rename a non-empty directory (2)
29	250	No such file
30	250	File was not found
	237	OPEN failure
	237	DUMP mode RANDOM or APPEND access not implemented; try IMAGE MODE
	238	DIALOG file cannot be opened (3)
	240	Record length missing for RANDOM ACCESS
	242	Too many devices open: fifteen maximum
	245	Device not available (2)
	248	Illegal ACCESS for device (2)
	249	Illegal MODE or MODE switch (2)
	251	No directory for project, programmer number (2)
	253	File was being modified (2)
<p>1. Not currently implemented.</p> <p>2. OPEN errors 251 through 276 map directly onto error numbers returned by the OPEN UUO; see Appendix E, "Error Codes", in Software Notebook 4, "DEC-10 Monitor Calls".</p> <p>3. Error cannot currently occur.</p> <p>8. Occurs when simulating mag tape output; SKIP RECORD and SKIP FILE are illegal. Also occurs when a non-existent file is opened in MODE=SEQINOUT and the first operation on that file is a READ.</p> <p>9. Occurs if OPEN output with BACKSPACE is not a mag tape or disk.</p>		

## FOROTS ERROR MESSAGES

Table H-1 (Cont.)  
FOROTS I/O Error Messages and ERRSNS Returned Values

First Value	Second Value	Explanation
	255	Illegal sequence of Monitor Calls (11)
	256	Bad UFD or bad RIB (2)
	259	Device not available (2)
	265	Partial allocation only (2)
	266	Block not free on allocation (2)
	267	Cannot supersede an existing directory (2)
	269	SFD not found (2)
	270	Search list empty (2)
	271	SFD nested too deeply (2)
	272	No CREATE flag for specified UFD (2)
	274	File cannot be updated (2)
	277	LOOKUP ENTER or RENAME error (2)
31		Mixed access modes
31	315	Cannot do SEQUENTIAL ACCESS on a RANDOM file
32		Invalid logical unit number
32	239	Illegal FORTRAN unit number (2)
39		Error during READ
39	310	REREAD before first READ is illegal (1)
42		Device handler not resident
42	244	No such device (2)
42	260	No such device (2)
45		OPEN statement keyword error
45	241	Switch error during DIALOG or OPEN statement scan (2)
47		Write on read-only file
47	263	Write-lock error (2)
59		List-directed I/O syntax error
59	313	Illegal delimiter in LIST DIRECTED input
62		Syntax error in FORMAT
62	301	Illegal character in FORMAT statement (4)
62	306	I/O list without data conversion in FORMAT
62	314	Missing width field for A or R on input
63		Output conversion error
63	305	Optional * fill: unidentified entry in FORERR (7)
<p>1. Not currently implemented.</p> <p>2. OPEN errors 251 through 276 map directly onto error numbers returned by the OPEN UUO; see Appendix E, "Error Codes", in Software Notebook 4, "DEC-10 Monitor Calls".</p> <p>4. In runtime FORMAT.</p> <p>7. * fill controlled by compile-time variable ASTFIL.</p> <p>11. Can occur on OPEN (MODE= 'APPEND') when file is found in LIB: or on [1,4] when device specified was SYS: and /NEW was in your search list.</p>		

## FOROTS ERROR MESSAGES

Table H-1 (Cont.)  
FOROTS I/O Error Messages and ERRSNS Returned Values

First Value	Second Value	Explanation
64	303	Input conversion error
	307	Checksum error reading binary records (5)
67	304	Illegal character in data
	102	Record too small for I/O list
81	261	I/O list greater than record size (6)
	102	Invalid argument
699	247	Argument block not in correct format
	257	Argument block not in correct format (2)
	258	Unclassifiable error on OPEN
	264	FOROTS system error (2,3)
	273	FOROTS system error (2)
	275	FOROTS system error (2)
	276	FOROTS system error (2)
799	309	Unclassifiable data error
899	400	Variable cannot be found in NAMELIST block
	401	Unclassifiable device errors
	402	Write protected
	403	Device error
	403	Parity error
	403	Block too large, quota exceeded, or file structure full. Nonexistent CDR reader.
	403	Spooled CDR file does not exist.
	404	End-of-file (10)
999	407	End-of-tape
	100	Unclassified system error
	103	FOROTS system error
	104	Monitor not build to support FOROTS
	105	Fatal error
	105	User program has requested more code than is available
	106	Run time memory management error
<p>2. OPEN errors 251 through 276 map directly onto error numbers returned by the OPEN UUO; see Appendix E, "Error Codes", in Software Notebook 4, "DEC-10 Monitor Calls".</p> <p>3. Error cannot currently occur.</p> <p>5. Checksumming controlled by compile-time variable CHKSUM.</p> <p>6. Occurs when a type 2 LSCW is found in a FORSE binary record.</p> <p>10. Trappable if there is no END= clause.</p>		

## FOROTS ERROR MESSAGES

Table H-2  
FOROTS Arithmetic and Library Error Messages

APR	LIB
Integer Overflow	Attempt to take DLOG of Negative Arg.
Integer Divide Check	Attempt to take DSQRT of Negative Arg.
Illegal APR Trap	ACOS of Arg. > 1.0 in Magnitude
Floating Divide Check	ASIN of Arg. > 1.0 in Magnitude
Floating Underflow	Attempt to take SQRT of Negative Arg.
	Attempt to take LOG of Negative Arg.



## INDEX

A format descriptor, 13-12  
ACCEPT, INTRO-5-2  
ACCEPT statement, 10-18  
ACCEPT transfer,  
    formatted, 10-18  
    into FORMAT statement, 10-19  
Account number, INTRO-5-2  
ACCESS in file control  
    statement, 12-3  
Accumulator usage, C-10  
Accuracy of double-  
    precision numbers, C-1  
ACOS function, 15-11  
Addition, 4-1  
Adjustable dimensions, 6-2  
ALL with DEBUG, B-3  
Allocation,  
    register, C-7  
 ALOG function, 15-10  
 ALOG10 function, 15-10  
 Alphanumeric data transfer,  
    13-12  
 Alphanumeric FORMAT field  
    descriptor, 13-11  
.AND., 4-5  
ANSI standard, 1-1  
APPEND with ACCESS, 12-4  
Argument,  
    subprogram, 15-1  
Argument type,  
    COBOL/FORTRAN, C-12  
Arithmetic,  
    mixed-mode, 4-2  
Arithmetic assignment  
    statement, 8-1  
Arithmetic expression, 4-1  
Arithmetic IF statement, 9-3  
Arithmetic operator, 4-1  
Array, 3-7  
    dimensioning, 3-9, C-4  
Array elements,  
    storage of, 3-10  
Array subscript, 3-8  
ASCII with MODE, 12-4  
ASCIZ string, C-14  
ASIN function, 15-11  
ASSIGN statement, 8-4  
Assigned GOTO statement, 9-2  
Assignment statement,  
    arithmetic, 8-1  
    label, 8-4  
    logical, 8-4  
    mixed-mode, 8-1  
ASSOCIATE VARIABLE in file  
    control statement, 12-8  
ATTACH, INTRO-7-3  
ATAN function, 15-11  
ATAN2 function, 15-11  
AXIS subroutine, 15-19  
BACKFILE statement, 14-3  
BACKSPACE statement, 14-2  
BASIC,  
    input from, 2-6  
Basic external function  
    subprogram, 15-8  
Beginning a job, INTRO-1-1  
BINARY with MODE, 12-4  
Blank line, 2-6  
BLOCK DATA statement, 16-1  
BLOCK SIZE in file control  
    statement, 12-8  
Block data subprogram, 16-1  
BOUNDS with DEBUG, B-3  
BUFFER COUNT in file control  
    statement, 12-8  
  
↑C, INTRO-1-1  
↑C monitor call, INTRO-3-3  
Call,  
    FUNCTION, 15-16  
    subroutine, 15-13  
CALL statement, 15-13  
Carriage control character,  
    13-16  
Carriage return key, INTRO-1-2  
Category,  
    statement, 1-1  
CCOS function, 15-11  
CEXP function, 15-10  
Changing a line, INTRO-3-4  
Changing a program, INTRO-4-1  
Changing line numbers, INTRO-4-5  
Character code, A-1  
Character set, 2-1  
Character set with MODE, 12-4  
Characters,  
    line formatting, 2-2  
    line termination, 2-2  
CLOG function, 15-10  
CLOSE, INTRO-5-4  
CLOSE statement, 12-1  
CLOSE statement summary, 12-10  
CONFIRM, INTRO-7-1  
COBOL-10,  
    interaction with, C-18  
COBOL/FORTRAN argument type,  
    C-12  
Command,  
    COMPILE, B-4  
    DEBUG, B-4  
    EXECUTE, B-4  
    LOAD, B-4  
Comment line, 2-5  
Common block name, 6-5  
COMMON statement, 6-5  
COMPIL in FOROTS, D-2

## INDEX (CONT.)

Compilation control statement, 5-1  
**COMPILE** command, B-4  
 Compiler commands, B-4  
 Compiler generated variable, B-6  
 Compiler switches, B-1  
 Compiler version, B-8  
 Complex constant, 3-3  
 Complex format, 13-4  
**COMPLEX** statement, 6-3  
 Computation,  
     redundant, C-5  
     reordering, C-3  
 Computation in DO-loop,  
     constant, C-6  
 Computed GOTO statement, 9-2  
**CONJG** function, 15-12  
 Constant, 3-1  
     complex, 3-3  
     double-precision, 3-3  
     integer, 3-2  
     label, 3-6  
     literal, 3-5  
     logical, 3-5  
     octal, 3-4  
     real, 3-2  
 Constant computation in  
     DO-loop, C-6  
 Constant folding, C-7  
 Constant propagation, C-7  
 Continuation field,  
     line, 2-3  
 Continuation line, 2-4  
 Continue (G) option after  
     PAUSE, 9-11  
**CONTINUE** statement, 9-10  
 Control statement, 9-1  
     compilation, 5-1  
 Control Z, 2-1  
**COS** function, 15-11  
**COSD** function, 15-11  
**COSH** function, 15-11  
**<CR>**, INTRO-1-2  
**CROSSREF** switch, B-2  
**CSIN** function, 15-11  
**CSQRT** function, 15-10

**D**, INTRO-4-3  
 D (double-precision notation), 3-3  
 D format descriptor, 13-4  
**.DAT** extension, 12-5  
 Data,  
     input/output, INTRO-5-1  
 Data file, INTRO-5-3  
 Data files,  
     FOROTS, D-4

**DATA** statement, 7-1  
 Data transfer operations, 10-1  
 Data type, 3-1  
**DATAN** function, 15-11  
**DATAN2** function, 15-12  
**DATE** subroutine, 15-19  
**DCOS** function, 15-11  
**DEBUG** command, B-4  
 Debug line, 2-6  
**DEBUG** switch, B-2, B-3  
 Debugger,  
     FORDDT, E-1  
 Debugger code size, B-4  
**DECODE** statement, 10-22  
**DEFAULT**, B-15  
**DEFINE FILE** subroutine, 15-17  
**DELETE**, INTRO-4-3, INTRO-6-2  
**DELETE** with DISPOSE, 12-5  
 Deleting a file, INTRO-6-2  
 Deleting a line, INTRO-4-3  
**DENSITY** in file control  
     statement, 12-9  
**Descriptor**,  
     G format, 13-7  
**Device control statement**, 14-1  
**Device control statement**  
     summary, 14-3  
**DEVICE** in file control state-  
     ment, 12-2  
 Device number,  
     logical, 10-3  
**DEXP** function, 15-10  
**DIALOG** in file control  
     statement, 12-9  
**DIMENSION** statement, 6-1  
 Dimensioning,  
     array in COMMON, 6-7  
 Dimensioning array, 3-9, C-4  
 Dimensions,  
     adjustable, 6-2  
**DIMENSIONS** with DEBUG, B-3  
**DIR**, INTRO-6-1  
**Directory**,  
     sub-file, 12-6  
     user file, 12-6  
**DIRECTORY**,  
     in file control statement, 12-6  
**Directory file**, INTRO-6-1  
**DISPOSE** in file control  
     statement, 12-5  
 Division, 4-1  
**DLOG** function, 15-10  
**DLOG10** function, 15-10  
**DO** statement, 9-5  
 DO-loop,  
     constant computation in, C-6

## INDEX (CONT.)

DO-loop (Cont.),  
     execution, 9-6  
     extended range, 9-8  
     floating-point, C-2  
     implied in I/O list, 10-5  
     nested, 9-6  
     parameters, 9-6  
     permitted transfers, 9-9  
     range, 9-5  
 DO-loop iteration, C-2  
 DO-loop replacement, C-8  
 DOUBLE PRECISION statement,  
     6-3  
 Double-precision constant,  
     3-3  
 Double-precision format,  
     13-4  
 Double-precision numbers,  
     accuracy of, C-1  
     range of, C-1  
 DSIN function, 15-11  
 DSQRT function, 15-10  
 Dummy argument,  
     subprogram, 15-1  
 DUMP subroutine, 15-20  
 DUMP with MODE, 12-4  
  
 E, INTRO-2-2, INTRO-4-5  
 E (exponential notation),  
     3-2  
 E format descriptor, 13-4  
 EDIT, INTRO-4-1  
 Editing source files, INTRO-4-1  
 ENCODE statement, 10-22  
 END, INTRO-4-5  
 END argument in I/O statement,  
     10-10  
 END FILE statement, 14-2  
 END statement, 5-2, 15-7  
 Ending source input, INTRO-2-2  
 ENTER in FOROTS, C-18  
 Entering a program, INTRO-2-1  
 ENTRY statement, 15-17  
 EQ, INTRO-4-5  
     .EQ., 4-7  
 EQUIVALENCE statement, 6-7  
     .EQV., 4-5  
 ERR argument in I/O statement,  
     10-10  
 ERR in file control statement,  
     12-10  
 Error,  
     fatal, B-17  
 Error processing,  
     FOROTS, D-3  
 Error reporting, B-17  
 ERRSET subroutine, 15-21  
 ERRSNS subroutine, 15-21  
 ESCAPE, INTRO-2-2  
  
 Evaluation of expression,  
     4-9  
 EVEN with PARITY, 12-9  
 EX, INTRO-3-1  
 Examples,  
     SOS, INTRO-8-1  
 Executable statement, 1-1  
 EXECUTE, INTRO-3-1  
 EXECUTE command, B-4  
 Execution,  
     interrupting, INTRO-3-3  
 Execution on non-DEC  
     machines, C-1  
 Exit (X) option after PAUSE,  
     9-11  
 EXIT subroutine, 15-21  
 EXP function, 15-10  
 EXPAND switch, B-2  
 Exponential notation, 3-2  
 Exponentiation, 4-1  
     permitted, 4-4  
 Expression,  
     arithmetic, 4-1  
     evaluation of, 4-9  
     logical, 4-4  
     mixed-mode, 4-10, 4-11  
     nested, 4-9  
     relational, 4-7  
 Extension,  
     .SHR, B-18  
 External function subprogram,  
     15-7  
     basic, 15-8  
 EXTERNAL statement, 6-8  
  
 F format descriptor, 13-4  
 F40 compiled programs, C-18  
     .FALSE., 3-5  
 Fatal error, B-17  
 Field,  
     label, 2-3  
     line continuation, 2-3  
     remarks, 2-4  
     statement, 2-3  
 Field descriptor,  
     alphanumeric FORMAT, 13-11  
     FORMAT, 13-2  
     logical FORMAT, 13-10  
     numeric FORMAT, 13-4  
 FILE, INTRO-2-1  
 File,  
     .FOR, INTRO-2-1  
     .REL, INTRO-7-1  
     data, INTRO-5-3  
     deleting a, INTRO-6-2  
     directory, INTRO-6-1  
     directory subfile, 12-6  
     editing, INTRO-4-1

## INDEX (CONT.)

**File (Cont.).**  
 FOROTS data, D-4  
 non-FORTRAN-10, C-9  
 renaming a, INTRO-6-2  
 source, INTRO-2-1  
**File control statement**, 12-1  
**File directory**,  
 user, 12-6  
**FILE** in file control  
 statement, 12-5  
**FILE SIZE** in file control  
 statement, 12-8  
**FIND** statement, 10-21  
**Floating-point DO-loop**, C-2  
**Folding**,  
 constant, C-7  
**.FOR** extension, INTRO-2-1  
**FORDDT** debugger, E-1  
**FORDDT** messages, E-17  
**FORMAT** field descriptor,  
 alphanumeric, 13-11  
 logical, 13-10  
 numeric, 13-4  
 record formatting, 13-15  
**FORMAT** statement, 13-1  
 ACCEPT transfer into, 10-19  
 transfer into, 10-3  
**FORMAT** statement descriptor,  
 13-2  
 Formatted ACCEPT transfer,  
 10-18  
 Formatted READ transfer,  
 random access, 10-13  
 sequential, 10-11  
 Formatted WRITE transfer,  
 random access, 10-17  
 sequential, 10-16  
**FOROTS**,  
 using, D-13  
**FOROTS** data files, D-4  
**FOROTS** error processing, D-3  
**FOROTS** features, D-2  
**FOROTS** hardware requirements,  
 D-1  
**FOROTS** input/output  
 facility, D-3  
**FOROTS** messages, H-1  
**FOROTS** software requirements,  
 D-1  
**FOROTS/FORSE** compatibility,  
 C-21  
**FOROTS/LINK** interface, D-28  
**FORSE/FOROTS** compatibility,  
 C-21  
**FORTRAN-10** compiler, B-1  
**FORTRAN-10** messages, F-1  
**FUNCTION** call, 15-16  
**Function references**,  
 order, C-8  
**FUNCTION** statement, 15-7

**Function subprogram**,  
 basic external, 15-8  
 external, 15-7  
 intrinsic, 15-3  
 statement, 15-3  
**Function subprogram structure**,  
 15-7  
**FUNCTION** type, 15-7

**G** (option after PAUSE), 9-11  
**G** format descriptor, 13-4,  
 13-7  
 .GE., 4-7  
**General (G)** numeric format,  
 13-7  
**GETOVL** in **LINK**, C-20  
**Global optimization**, C-4  
**GOTO** statement, 9-1  
 assigned, 9-2  
 computed, 9-2  
 unconditional, 9-1  
**GRIPE**, INTRO-6-3  
 .GT., 4-7

**H** (literal notation), 3-5  
**H** format descriptor, 13-12  
**Hardware requirements**,  
 FOROTS, D-1  
**Hierarchy of operators**, 4-9  
**Hollerith literal**, 3-5

**I**, INTRO-4-1  
**I** format descriptor, 13-4  
**I/O list**, 10-5  
**IF** statement, 9-3  
 arithmetic, 9-3  
 logical, 9-4  
**ILL** subroutine, 15-21  
**IMAGE** with **MODE**, 12-4  
**IMPLICIT** statement, 6-5  
**In I/O list** DO-loop,  
 implied, 10-6  
**Inaccessible code**, C-7  
**INCLUDE** statement, 5-1  
**INCLUDE** switch, B-2  
**INDEX** with **DEBUG**, B-3  
**INIOVL** in **LINK**, C-20  
**Initial line**, 2-4  
**INPUT**, INTRO-2-1  
**Input**,  
 line-sequence, 2-6  
**Input from BASIC**, 2-6  
**Input from LINED**, 2-6  
**Input/output data**, INTRO-5-1

INDEX (CONT.)

Input/output facility,  
FOROTS, D-3  
Input/output list, 10-2  
  NAMELIST, 10-10  
Input/output optimization,  
  C-8  
Input/output statement, 10-1  
  list-directed, 10-8  
Input/output statement  
  format, 10-2  
Input/output statement  
  summary, 10-24  
INSERT, INTRO-4-1  
Inserting a line, INTRO-4-1  
Integer constant, 3-2  
Integer format, 13-4  
INTEGER statement, 6-3  
Intrinsic function sub-  
  program, 15-3  
Iteration,  
  DO-loop, C-2  
Interrupting execution,  
  INTRO-3-3

Job,  
  beginning a, INTRO-1-1  
  disconnected (attach),  
    INTRO-7-3  
  killing a, INTRO-7-1  
  number forgotton, INTRO-7-4  
JOB number, INTRO-1-2

K (kill file), INTRO-7-1  
KA10 switch, B-2  
Keyword, 1-1  
K/F fast logout, INTRO-7-2  
KI10 switch, B-2  
Killing a job, INTRO-7-1  
KJOB, INTRO-7-1

L format descriptor, 13-10  
Label assignment statement, 8-4  
Label constant, 3-6  
Label field, 2-3  
LABELS with DEBUG, B-3  
.LE., 4-7  
LEGAL subroutine, 15-21  
Line,  
  blank, 2-6  
  comment, 2-5  
  continuation, 2-4  
  debug, 2-6  
  definition, 2-2  
  fields, 2-2

Line (Cont.),  
  initial, 2-4  
  multi-statement, 2-5  
Line continuation field,  
  2-3  
Line formatting characters,  
  2-2  
Line sequence number, B-5  
LINE subroutine, 15-21  
LINE terminal setting,  
  INTRO-1-1  
Line termination characters,  
  2-2  
Line types, 2-4  
Line-sequence input, 2-6  
LINED,  
  input from, 2-6  
LINK-10 overlay facility,  
  C-20  
LINK/FOROTS interface, D-28  
List,  
  input/output, 10-2  
  NAMELIST input/output, 10-10  
LIST with DISPOSE, 12-5  
List-directed input/output  
  statement, 10-8  
List-directed transfer,  
  sequential READ, 10-12  
  sequential WRITE, 10-17  
Listing,  
  program, B-5  
Literal constant, 3-5  
Literal format conversion,  
  13-13  
LNMAP switch, B-2  
LOAD command, B-4  
Location in object program,  
  B-5  
Logging in, INTRO-1-1  
LOGIN, INTRO-1-2  
Logical assignment statement,  
  8-4  
Logical constant, 3-5  
Logical expression, 4-4  
Logical FORMAT field  
  descriptor, 13-10  
Logical IF statement, 9-4  
Logical operator, 4-5  
LOGICAL statement, 6-3  
Logical unit number, 10-3  
LOGOVL in LINK, C-20  
.LT., 4-7

MACRO in listing, B-5  
MACRO-10 libraries, C-14  
MACROCODE switch, B-2

## INDEX (CONT.)

**Messages,**  
 FORDDT, E-17  
 FOROTS, H-1  
 FORTTRAN-10, F-1  
 realtime, G-7  
**Mixed-mode arithmetic,** 4-2  
**Mixed-mode assignment**  
 statement, 8-1  
**Mixed-mode expression,** 4-10,  
 4-11  
 MKTBL subroutine, 15-22  
**MODE** in file control  
 statement, 12-4  
**MONITOR, INTRO-1-2**  
**Monitor,**  
 calling the, INTRO-3-3  
**Multi-statement line,** 2-5  
**Multiple record transfer,**  
 13-14  
**Multiplication,** 4-1  
  
**N, INTRO-4-5**  
**Name,**  
 symbolic, 3-6  
**NAMELIST input/output list,**  
 10-10  
**NAMELIST statement,** 11-1  
**NAMELIST-controlled transfer,**  
 input, 11-2  
 output, 11-3  
 sequential READ, 10-13  
 sequential WRITE, 10-17  
**.NE.,** 4-7  
**Nested DO-loop,** 9-6  
**Nested expression,** 4-9  
**NOERRS switch,** B-2  
**NONE with DEBUG,** B-3  
**Nonexecutable statement,** 1-1  
**Non-FORTTRAN-10 files,** C-9  
**Non-FORTTRAN-10 programs,** C-9  
**NONSHAR,** B-18  
**.NOT.,** 4-5  
**NOWARNINGS switch,** B-2  
**NUMBER, INTRO-4-5**  
**NUMBER subroutine,** 15-22  
**Numeric,**  
 field width variable, 13-10  
**Numeric format,**  
 general (G), 13-7  
**Numeric FORMAT field**  
 descriptor, 13-4  
  
**†O, INTRO-6-2**  
**O format descriptor,** 13-4  
**Object program,** INTRO-3-1  
  
**Object program,**  
 location in, B-5  
**Octal constant,** 3-4  
**ODD with PARITY,** 12-9  
**OPEN, INTRO-5-3**  
**OPEN statement,** 12-1  
**OPEN statement summary,** 12-10  
**Operator,**  
 arithmetic, 4-1  
 hierarchy, 4-9  
 logical, 4-5  
**Operator strength,** C-5  
**Optimization,**  
 global, C-4  
 program, C-9  
**OPTIMIZE switch,** B-2  
**.OR.,** 4-5  
**Order of statements,** 2-7  
**OTS,** B-18  
**Output,**  
 suppressing printed,  
 INTRO-6-2  
**Overflow,** C-3  
**Overlay facility,**  
 LINK-10, C-20  
  
**P, INTRO-4-4**  
**P (preserve file),** INTRO-7-1  
**PARAMETER statement,** 6-9  
**PARITY in file control**  
 statement, 12-9  
**PASSWORD, INTRO-1-2**  
**PATH with DIRECTORY,** 12-7  
**PAUSE statement,** 9-11  
**PDUMP subroutine,** 15-22  
**PLOT subroutine,** 15-22  
**PLOTS subroutine,** 15-22  
**PPN, INTRO-7-3**  
**Precision for real constant,** 3-2  
**PRINT, INTRO-4-4**  
**PRINT statement,** 10-19  
**PRINT with DISPOSE,** 12-5  
**Printed output,**  
 suppressing, INTRO-6-2  
 printing lines of source,  
 INTRO-4-4  
**Program listing,** B-5  
**PROGRAM statement,** 5-1  
**Program,**  
 changing, INTRO-4-1  
 entering, INTRO-2-1  
 running, INTRO-3-1  
 storing, INTRO-2-2  
**Programs,**  
 non-FORTTRAN-10, C-9  
 optimizing, C-9  
 writing, C-1

## INDEX (CONT.)

Propagation,  
constant, C-7  
PROTECTION in file control  
statement, 12-6  
PUNCH statement, 10-20  
PUNCH with DISPOSE, 12-5

QUIT, INTRO-4-5

R, INTRO-4-3  
R format descriptor, 13-12  
.RSOS, INTRO-2-1  
RAN function, 15-12  
RANDIN with ACCESS, 12-3  
Random access data transfer,  
10-1  
Random access record  
specification, 10-7  
Random access transfer,  
formatted READ, 10-13  
formatted WRITE, 10-17  
unformatted READ, 10-13  
unformatted WRITE, 10-17  
RANDOM with ACCESS, 12-3  
Range of double-precision  
numbers, C-1  
READ, INTRO-5-1  
READ statement, 10-11  
READ statement summary,  
10-14  
READ transfer,  
random access, 10-13  
sequential, 10-11, 10-12,  
10-13  
Real constant, 3-2  
Real format, 13-4  
REAL statement, 6-3  
Realtime messages, G-7  
Realtime software, G-1  
Record formatting (T and X),  
13-15  
RECORD SIZE in file control  
statement, 12-8  
Record specification,  
random access, 10-7  
Reentrant program, B-18  
Register allocation, C-7  
.REL extension, INTRO-7-1  
Relational expression, 4-7  
RELEAS subroutine, 15-23  
Remarks field, 2-4  
REMOVL in LINK, C-20  
RENAME, INTRO-6-2  
RENAME with DISPOSE, 12-5  
Renaming a file, INTRO-6-2

Repeat for format  
descriptor, 13-3  
REPLACE, INTRO-4-3  
Replacement,  
DO-loop, C-8  
Replacing a line, INTRO-4-3  
Reporting,  
error, B-17  
REREAD statement, 10-14  
RESET in FOROTS, C-10  
Return key,  
carriage, INTRO-1-2  
RETURN statement, 15-8, 15-14  
REWIND statement, 14-1  
RUBOUT key, INTRO-2-3  
Running a program, INTRO-3-1  
RUNOVL in LINK, C-20

S (save file), INTRO-7-1  
SAVE with DISPOSE, 12-5  
SAVRAN subroutine, 15-23  
Scale factor in FORMAT  
statement, 13-7  
SCALE subroutine, 15-23  
SEG, B-18  
SEQIN with ACCESS, 12-3  
SEQINOUT with ACCESS, 12-3  
SEQOUT with ACCESS, 12-3  
Sequence number,  
line, B-5  
Sequential data transfer,  
10-1  
Sequential transfer,  
READ, 10-11, 10-12, 10-13  
WRITE, 10-16, 10-17  
SET RECORD statement, 14-3  
SETABL subroutine, 15-23  
SETRAN subroutine, 15-23  
SFD, 12-6  
Sharable program, B-18  
.SHR extension, B-18  
SIN function, 15-10  
SIND function, 15-11  
SINH function, 15-11  
SKIP FILE statement, 14-3  
SLITE subroutine, 15-23  
SLITET subroutine, 15-23  
Software requirements,  
FOROTS, D-1  
SORT subroutine, 15-24  
SOS, INTRO-2-1  
SOS examples, INTRO-8-1  
Source file, INTRO-2-1  
Source program, INTRO-2-1  
Specification statement,  
6-1

## INDEX (CONT.)

SSAVE switch, B-18  
 SSWTCH subroutine, 15-23  
 Statement,  
     ACCEPT, 10-18  
     Arithmetic assignment,  
         8-1  
     arithmetic IF, 9-3  
     ASSIGN, 8-4  
     assigned GOTO, 9-2  
     BACKFILE, 14-3  
     BACKSPACE, 14-2  
     BLOCK DATA, 16-1  
     CALL, 15-13  
     CLOSE, 12-1  
     COMMON, 6-5  
     COMPLEX, 6-3  
     computed GOTO, 9-2  
     CONTINUE, 9-10  
     control, 9-1  
     DATA, 7-1  
     DECODE, 10-22  
     device control, 14-1  
     DIMENSION, 6-1  
     DO, 9-5  
     DOUBLE PRECISION, 6-3  
     ENCODE, 10-22  
     END, 5-2, 15-7  
     END FILE, 14-2  
     ENTRY, 15-17  
     EQUIVALENCE, 6-7  
     executable, 1-1  
     EXTERNAL, 6-8  
     file control, 12-1  
     FIND, 10-21  
     FORMAT, 13-1  
     FUNCTION, 15-7  
     GOTO, 9-1  
     IF, 9-3  
     IMPLICIT, 6-5  
     INCLUDE, 5-1  
     input/output, 10-1  
     INTEGER, 6-3  
     label assignment, 8-4  
     list-directed,  
         input/output, 10-8  
     LOGICAL, 6-3  
     logical assignment, 8-4  
     logical IF, 9-4  
     mixed-mode assignment,  
         8-1  
     NAMELIST, 11-1  
     nonexecutable, 1-1  
     OPEN, 12-1  
     PARAMETER, 6-9  
     PAUSE, 9-11  
     PRINT, 10-19  
     PROGRAM, 5-1  
     PUNCH, 10-20  
     READ, 10-11

Statement (Cont.),  
     REAL, 6-3  
     REREAD, 10-14  
     RETURN, 15-7, 15-14  
     REWIND, 14-1  
     SET RECORD, 14-3  
     SKIP FILE, 14-3  
     STOP, 9-10  
     SUBROUTINE, 15-9  
     TYPE, 10-21  
     type specification, 6-3  
     unconditional GOTO, 9-1  
     UNLOAD, 14-2  
     WRITE, 10-16  
 Statement category, 1-1  
 Statement descriptor,  
     FORMAT, 13-2  
 Statement field, 2-3  
 Statement format,  
     input/output, 10-2  
 Statement function  
     subprogram, 15-3  
 Statement label constant,  
     3-6  
 Statement numbers, 2-3  
 Statement summary,  
     CLOSE, 12-10  
     device control, 14-3  
     input/output, 10-24  
     OPEN, 12-10  
     READ, 10-14  
     WRITE, 10-18  
 Statements,  
     order of, 2-7  
 STOP statement, 9-10  
 Storage of array elements,  
     3-10  
 Storing a program, INTRO-2-2  
 Sub-file directory, 12-6  
 Subprogram,  
     basic external function,  
         15-8  
     block data, 16-1  
     external function, 15-7  
     intrinsic function, 15-3  
     multiple entries to, 15-17  
     multiple returns from, 15-14  
     statement function, 15-3  
     subroutine, 15-9  
 Subprogram argument, 15-1  
 Subprogram dummy argument,  
     15-1  
 Subprograms, 15-1  
 Subroutine,  
     DATE, 15-19  
     ERRSET, 15-21  
     ERRSNS, 15-21  
     EXIT, 15-21  
     FORTRAN supplied, 15-14

INDEX (CONT.)

Subroutine (Cont.),  
  ILL, 15-21  
  LEGAL, 15-21  
  LINE, 15-21  
  programming consideration,  
    C-2  
Subroutine call, 15-13  
SUBROUTINE statement, 15-9  
Subroutine structure, 15-13  
Subroutine subprogram, 15-9  
Subscript,  
  array, 3-8  
Subtraction, 4-1  
Suppressing printed output,  
  INTRO-6-2  
Switches,  
  compiler, B-1  
SYMBOL subroutine, 15-24  
Symbolic name, 3-6  
SYNTAX switch, B-2  
SYS, INTRO-7-4  
  
T (trace after PAUSE), 9-12  
T format descriptor, 13-15  
TAB, INTRO-4-6  
TANH function, 15-11  
TIM2GO function, 15-12  
TIME subroutine, 15-24  
Trace (T) option after PAUSE,  
  9-12  
TRACE function, 9-13  
TRACE subroutine, 9-13  
TRACE with DEBUG, B-3  
Transfer operations,  
  data, 10-1  
.TRUE., 3-5  
TYPE, INTRO-5-2, INTRO-6-1  
Type,  
  FUNCTION, 15-7  
Type specification statement,  
  6-3  
TYPE statement, 10-21  
  
†U, INTRO-3-4  
UFD, 12-6

Unconditional GOTO statement,  
  9-1  
Uninitialized variable, C-8  
UNIT in file control  
  statement, 12-2  
Unit number,  
  logical, 10-3  
Unformatted transfer,  
  random access,  
    READ, 10-13  
    WRITE, 10-17  
  sequential binary,  
    READ, 10-12  
    WRITE, 10-16  
UNLOAD statement, 14-2  
User file directory, 12-6  
  
Variable, 3-7  
  compiler generated, B-6  
  uninitialized, C-8  
VERSION in file control  
  statement, 12-8  
  
Warning message, B-17  
WHERE subroutine, 15-25  
WRITE, INTRO-5-1  
WRITE statement, 10-16  
WRITE statement summary,  
  10-18  
WRITE transfer,  
  random access, 10-16, 10-17  
  sequential, 10-16, 10-17  
Writing programs, C-1  
  
X (option after PAUSE), 9-11  
X format descriptor, 13-15  
.XOR., 4-5

†Z, 2-1



READER'S COMMENTS

NOTE: This form is for document comments only. DIGITAL will use comments submitted on this form at the company's discretion. Problems with software should be reported on a Software Performance Report (SPR) form. If you require a written reply and are eligible to receive one under SPR service, submit your comments on an SPR form.

Did you find errors in this manual? If so, specify by page.

---

---

---

---

---

Did you find this manual understandable, usable, and well-organized? Please make suggestions for improvement.

---

---

---

---

---

Is there sufficient documentation on associated system programs required for use of the software described in this manual? If not, what material is missing and where should it be placed?

---

---

---

---

---

Please indicate the type of user/reader that you most nearly represent.

- Assembly language programmer
- Higher-level language programmer
- Occasional programmer (experienced)
- User with little programming experience
- Student programmer
- Non-programmer interested in computer concepts and capabilities

Name \_\_\_\_\_ Date \_\_\_\_\_

Organization \_\_\_\_\_


Street \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_ Zip Code \_\_\_\_\_  
or  
Country \_\_\_\_\_

Please cut along this line.

-----Do Not Tear - Fold Here and Tape-----

digital




No Postage  
Necessary  
if Mailed in the  
United States

**BUSINESS REPLY MAIL**

FIRST CLASS PERMIT NO.33 MAYNARD MASS.

POSTAGE WILL BE PAID BY ADDRESSEE

**SOFTWARE PUBLICATIONS**  
200 FOREST STREET MR1-2/E37  
MARLBOROUGH, MASSACHUSETTS 01752



----- Do Not Tear - Fold Here and Tape -----

Cut Along Dotted Line



